

ADDENDUM IDAP REPORT

Property:	7 Patricia Street BELFIELD Lot: 40 DP: 35173 DA2021.300
Proposal:	Demolition of existing dwelling and construction of two (2) storey dwelling house with basement level.
Applicant:	Platform Five Design
Owner:	A Bechara
Date of lodgement:	17 November 2021
Notification period:	22 November 2021 to 6 December 2021
Submissions:	NIL
Assessment officer:	G I Choice
RECOMMENDATION OF OFFICER:	APPROVAL

BACKGROUND

6 May 2022 The recommended approval of DA 2021/300 at 7 Patricia Street BELFIELD was deferred by Strathfield IDAP for further investigation of issues arising from the use of the existing outbuilding, insufficient landscaping and unnecessary bulk and massing basement floor plan, the provision of the alfresco area and elements of the dwelling design contributing to unnecessary bulk and overshadowing.

30 May 2022 Recommendations for additional amendments were provided to the Applicant (based on IDAP comments) as follows:

i. **First floor plan**

- The proposed cantilevered first floor section was not supported. The proposed dwelling design was to be amended so that no part of the first floor extends beyond the proposed alfresco area.

ii. **Amended elevations plans**

- Amended elevations plans were required to clearly show the location of the existing rear outbuilding

iii. Outbuilding floor plan

- A detailed floor plan of the existing rear outbuilding was required.

27 July 2022

Amended plans were submitted via the NSW Planning Portal.

Strathfield Local Environmental Plan

The amended plans result in the following changes with regard to the Strathfield Local Environmental Plan 2012

Part 4 – Principal Development Standards

Applicable SLEP 2012 Clause	Development Standards	Development Proposal	Compliance/ Comment
4.3 Height of Buildings	Maximum 9.5m	7.54m	Yes
4.4 Floor Space Ratio	Site area 619.1m ² 0.625:1 (371.46m ²)	0.55:1 (335.4m ²)	Yes - Change from 0.47:1 (287m ²)

The proposed development (as amended) remains compliant with relevant SLEP 2012 development standards.




Figure 1: Ground floor plan 20-029-DA 20 02 Issue C – 14/04/2022
(IDAP assessed 6 May 2022)





Figure 2: Amended ground floor plan



**Figure 3: First floor plan 20-029-DA 20 03 Issue C – 14/04/2022
(IDAP assessed 6 May 2022)**




Figure 4: Amended first floor plan




Figure 5: North elevation 20-029-DA 30 01 Issue C – 14/04/2022
(IDAP assessed 6 May 2022)




Figure 6: Amended north elevation




Figure 7: South elevation 20-029-DA 30 01 Issue C – 14/04/2022
(IDAP assessed 6 May 2022)




Figure 8: Amended south elevation




Figure 9: East (left) & west (right) elevations 20-029-DA 30 01 Issue C – 14/04/2022
(IDAP assessed 6 May 2022)




Figure 10: Amended east (front) & west (rear) elevations




Figure 11: Landscaped calculations 20-029-DA 2902 Issue C – 14/04/2022
(IDAP assessed 6 May 2022)




Figure 12: Amended landscaped calculations

DISCUSSION

1. Deletion of the cantilevered first floor component

IDAP advised that the cantilevered first floor component, which was cantilevered above a substantial proportion of real landscaped area at ground level in the rear yard.

Officer comment: Amended plans show the removal of the cantilevered first floor area. The rear alfresco footprint has been increased and the Master Bedroom area has been reduced to sit wholly above the rear alfresco area. The assessment calculates a compliant landscaped area of 258.1m² or 41.6% of the 619.1m² total site area. This design change results in a slight reduction of landscaped area than previously proposed, however the issue of meaningful landscaped area within the rear yard has been generally resolved and is considered to address IDAP requirements.

2. Additional information regarding the existing outbuilding

The outbuilding was omitted from all the elevations and sectional drawings, effectively misrepresenting what was to occur on site. Amended plans were required to show the extent of site coverage and massing from the front to rear of the site. As well as the internal floor plan of the outbuilding.

Officer comment: Amended plans show the location of the existing outbuilding. It is considered the proposal (as amended) presents a more accurate representation of the development and the removal of the cantilevered area has reduced visual impacts of bulk and massing. In this regard, the IDAP issue has been satisfactorily addressed.

3. Clarification of Floor Space Ratio

Revised FSR calculations and an amended LEP compliance table were required by the Assessing Officer to alleviate confusion for the report. This included a re-calculation of gross floor area which included the outbuilding floor plan area.

Officer comment: The outbuilding floor area has been included in the total GFA and FSR calculations as shown in the SLEP compliance table above. The proposed development remains compliant with FSR.

4. Clarification on Use of Existing Building

The Assessing Officer made note of a CDC issued for the existing outbuilding and swimming pool. The validity of this CDC has since been questioned by IDAP based on site inspection photos.

Officer comment: The existing outbuilding is not subject to works as part of the subject DA 2021/300. Furthermore, an assessment shows the development will still comply with FSR controls. A recommendation is made for referral to the Council Building and Compliance unit further investigation of any unauthorised use of the building. This is considered acceptable to address IDAP concerns.

Conclusion

It is considered this addendum report and amendment of condition 1 to include the amended plans as recommended by the Assessing Officer is sufficient to support the recommendation for approval and no further information from the Applicant is necessary.

The following revisions are recommended for the subject approval:

- i. Update Condition 1 to include amended plans; and
- ii. Refer the issue of the Outbuilding CDC and current use of the outbuilding to Council's Building and Compliance unit for further investigation.

This Addendum Report recommends to maintain the approval subject to the abovementioned revisions.



Signed:
G I Choice
Planner

Date: 25 May 2022

CONDITIONS

The following conditions of consent are imposed for the following reasons:

- (a) To ensure compliance with the terms of the relevant Environmental Planning Instrument and/or Building Code of Australia and/or Council's codes, policies and specifications.
- (b) To protect the environment.
- (c) To ensure that there is no unacceptable impact on the amenity of the area, or to private and public property.
- (d) It is in the public interest.

DEVELOPMENT DETAILS

1. Approved Plans & Documentation

The development must be implemented in accordance with the approved plans and supporting documentation listed below which have been endorsed by Council's approved stamp, except where marked up on the plans and/or amended by conditions of this consent:

Description	Reference No.	Date	Revision	Prepared by
Site Plan	20-029 – DA1002	5 July 2022	C	Platform 5 Design
Demolition Plan	20-029 – DA1004	5 July 2022	C	Platform 5 Design
Basement Floor Plan	20-029 – DA2001	5 July 2022	C	Platform 5 Design
Ground Floor Plan	20-029 – DA2002	5 July 2022	C	Platform 5 Design
Level One Floor Plan	20-029 – DA2003	5 July 2022	C	Platform 5 Design
Roof Plan	20-029 – DA2004	5 July 2022	C	Platform 5 Design
Landscaped Calculations	20-029 – DA2902	5 July 2022	C	Platform 5 Design
Elevations	20-029 – DA3001	5 July 2022	C	Platform 5 Design

Streetscape	20-029 – DA3002	5 July 2022	C	Platform 5 Design
Sections	20-029 – DA4001	5 July 2022	C	Platform 5 Design
Finishes Schedule	20-029 – DA6301	5 July 2022	C	Platform 5 Design
Stormwater Plans General Notes	A21244 - COVER	8 November 2021	B	Alpha
Sediment and Erosion Control Plan	A21244 – SW01	8 November 2021	B	Alpha
Basement Drainage Plan	A21244 – SW02	8 November 2021	B	Alpha
Ground Floor Drainage Plan	A21244 – SW03	8 November 2021	B	Alpha
First Floor and Roof Drainage Plan	A21244 – SW04	8 November 2021	B	Alpha
Stormwater Section and Details	A21244 – SW05	8 November 2021	B	Alpha
Document	Reference No.	Date	Revision	Prepared by
Survey Plan	210062 DE-01	14 July 2020	A	Ensure Consulting Pty Ltd
BASIX Certificate	1254256S	8 November 2021	-	Dural Group Pty Ltd

2. Building Height

The height of the building measured from Australian Height Datum (AHD) must not exceed Reduced Level (RL) 25.270 AHD to the roof ridge of the building.

SEPRARATE APPROVALS REQUIRED UNDER OTHER LEGISLATION

3. Section 138 Roads Act 1993 and Section 68 Local Government Act 1993

Unless otherwise specified by a condition of this consent, this Development Consent does not give any approval to undertake works on public infrastructure.

Separate approval is required under Section 138 of the [Roads Act 1993](#) and/or Section 68 of the [Local Government Act 1993](#) for any of the following activities carried out in, on or over a public road (including the footpath) listed below.

An application is required to be lodged and approved prior to the commencement of any of the following works or activities;

- (a) If any excavation is to be supported by the use of below ground (cable) anchors that are constructed under Council's roadways/footways.
- (b) Swinging or hoisting goods over any part of a public road by means of a lift, crane or the like;
- (c) Establishing a "works zone";
- (d) Placing or storing materials or equipment;
- (e) Placing or storing waste containers or skip bins;
- (f) Stormwater & ancillary to public infrastructure on private land
- (g) Erecting a structure or carrying out work

These separate activity approvals (a)-(g) must be obtained and evidence of the approval provided to the Certifying Authority prior to the issue of the Construction Certificate.

- (h) Pumping water from the site into the public road;
- (i) Constructing a vehicular crossing or footpath;
- (j) Digging up or disturbing the surface of a public road (e.g. Opening the road for the purpose of connections to utility providers);
- (k) Stormwater & ancillary works in the road reserve; and
- (l) Pumping concrete from a public road;

These separate activity approvals must be obtained and evidence of the approval provided to the Certifying Authority prior to the activities commencing.

The relevant Application Forms for these activities can be downloaded from Council's website www.strathfield.nsw.gov.au. For further information, please contact Council's Customer Service Centre on (02) 9748 9999.

4. Vehicular Crossing - Minor Development

Constructing a vehicular crossing and/or footpath requires a separate approval under Section 138 of the [Roads Act 1993](#) prior to the commencement of those works.

To apply for approval, complete the *Works Permit Application Form* which can be downloaded from Strathfield Council's Website at www.strathfield.nsw.gov.au. Lodge the application form, together with the associated fees at Council's Customer Service Centre, during business hours. Refer to Civic & Urban Services Section in Council's adopted *Fees and Charges* for the administrative and inspection charges associated with *Works Permit* applications.

An approval for a new or modified vehicular crossing will contain the approved access and/or alignment levels which will be required to construct the crossing and/or footpath. Once approved, all work shall be carried out in accordance with Council's specifications applicable at the time, prior to the issue of an Occupation Certificate.

REQUIREMENTS OF CONCURRENCE, INTEGRATED & OTHER GOVERNMENT AUTHORITIES

5. Sydney Water – Tap in™

The approved plans must be submitted to a Sydney Water Tap in™ to determine whether the development application will affect Sydney Water's sewer and water mains, stormwater drains and/or easements, and if further requirements need to be met. The approved plans will be appropriately endorsed. For details please refer to 'Plumbing, building and developing' section of Sydney Water's web site at www.sydneywater.com.au then see 'Building', or telephone 13000 TAP IN (1300 082 746). The Certifying Authority must ensure that a Tap in™ agent has appropriately stamped the plans prior to the issue of the Construction Certificate.

PRIOR TO THE ISSUE OF A CONSTRUCTION CERTIFICATE

6. Fees to be Paid

The fees listed in the table below must be paid in accordance with the conditions of this consent and Council's adopted Fees and Charges applicable at the time of payment (available at www.strathfield.nsw.gov.au).

Payments must be made prior to the issue of the Construction Certificate or prior to the commencement of work (if there is no associated Construction Certificate).

Please contact council prior to the payment of s7.11 or s7.12 Contributions to determine whether the amounts have been indexed from that indicated below in this consent and the form of payment that will be accepted by Council.

A summary of the fees to be paid are listed below:

Fee Type	Fee
GENERAL FEES	
Long Service Levy (to Long Service Corporation) Or, provide evidence of Payment direct to the Long Service Corporation. See https://longservice.force.com/bci/s/levy-calculator	\$ 3,819.00
Security Damage Deposit	\$ 15,000.00
Tree Bond	\$ 10,150.00
Administration Fee for Damage Deposit	\$ 130.00
Administration Fee for Tree Bond	\$ 130.00
DEVELOPMENT CONTRIBUTIONS	
Strathfield Section 94A Indirect Development Contributions Plan 2017	\$ 10,912.34

General Fees

The fees and charges above are subject to change and are as set out in the version of Council's Schedule of Fees and Charges or as required by other Government Authorities, applicable at the time of payment.

Development Contributions

A Section 7.12 contribution (s94A) has been levied on the subject development pursuant to the Strathfield Indirect Development Contributions Plan.

Indexation

The above contributions will be adjusted at the time of payment to reflect changes in the cost of delivering public amenities and public services, in accordance with the indices provided by the relevant Development Contributions Plan.

Timing of Payment

The contribution must be paid and receipted by Council prior to the release of the Construction Certificate.

Further Information

A copy of the *current Development Contributions Plans* may be inspected at Council's Customer Service Centre at 65 Homebush Road, Strathfield or on Council's website www.strathfield.nsw.gov.au.

7. Damage Deposit – Minor Works

In order to insure against damage to Council property the following is required:

- (a) Pay Council, before the issue of the Construction Certificate, a damage security deposit for the cost of making good any damage caused to any Council property as a result of the development: \$15,000.00.
- (b) Pay Council, before the issue of the Construction Certificate, a non-refundable administration fee to enable assessment of any damage and repairs where required: \$130.00
- (c) Submit to Council, before the commencement of work, a photographic record of the condition of the Council nature strip, footpath and driveway crossing, or any area likely to be affected by the proposal.

At the completion of work Council will inspect the public works, and the damage deposit will be refunded in full upon completion of work where no damage occurs. Otherwise the amount will be either forfeited or partly refunded according to the amount of damage.

8. Tree Bond

A tree bond of \$10,150.00 (calculated in accordance with Council's adopted Fees and Charges) shall be paid to Council, prior to the issue of a Construction Certificate.

The deposit is required as security against any damage to existing trees to be retained on Council's road reserve, during works on the site. The applicant must bear the cost of all restoration works to Council's property damaged during the course of this development.

A sound protection barrier anchored firmly into the ground 1.8m in height x 2 metres clear of the base of the tree at any one point and that the fence is to extend up to the back of the kerb and to the edge of the footpath.

Payment may be accepted in the form of cash, bank guarantee, cheque or credit card (financial transactions fees apply). Note: Additional fees apply for the lodgement of a bank guarantee in lieu of cash bond applies in accordance with Council's adopted Fees and Charges.

A request for refund of the Tree Bond must be made in writing.

Tree Bonds may be forfeited if a tree is dead, made dangerous or has been terminally damaged, or will be held until tree/s have fully recovered from the construction damage or were replacement/planted trees have become fully established and are over 6 metres in height.

9. Site Management Plan

Minor Development

A Site Management Plan detailing all weather access control points, sedimentation controls, waste management plans, fencing, builders' site sheds office, amenities, materials storage and unloading arrangements must be submitted with the application for the Construction Certificate.

10. BASIX Commitments

The approved BASIX Certificate shall be submitted to the Accredited Certifier with the application for a Construction Certificate.

All measures and commitments as detailed in the BASIX Certificate No. 1254256S must be implemented on the plans lodged with the application for the Construction Certificate.

11. Low Reflectivity Roof

Roofing materials must be low glare and reflectivity. Details of finished external materials including colours and texture must be provided to the Certifying Authority.

12. Erosion & Sedimentation Control

Erosion and sediment controls must be provided to ensure:

- (a) Compliance with the approved Erosion & Sediment Control Plan
- (b) Removal or disturbance of vegetation and top soil is confined to within 3m of the approved building area (no trees to be removed without approval)
- (c) All clean water run-off is diverted around cleared or exposed areas
- (d) Silt fences, stabilised entry/exit points or other devices are installed to prevent sediment from entering drainage systems or waterways
- (e) All erosion and sediment controls are fully maintained for the duration of demolition, excavation and/or development works
- (f) Controls are put into place to prevent tracking of sediment by vehicles onto adjoining roadway
- (g) All disturbed areas are rendered erosion-resistant by turfing, mulching, paving or similar
- (h) Compliance with [Managing Urban Stormwater – Soils and Construction \(Blue Book\) produced by Landcom 2004.](#)

These measures are to be implemented prior to the commencement of work (including demolition and excavation) and must remain until works are completed and all exposed surfaces are landscaped/sealed.

13. Pre-Construction Dilapidation Report – Private Land

A professional engineer specialising in structural or geotechnical engineering shall prepare a Pre-Construction Dilapidation Report detailing the current structural condition of adjoining premises including but not limited to:

- (a) All neighbouring buildings and/or public assets likely to be affected by the excavation as determined by the consulting engineer.

The report shall be prepared at the expense of the applicant and submitted to the satisfaction of the Certifying Authority prior to the issue of the Construction Certificate.

A copy of the pre-construction dilapidation report is to be provided to the adjoining properties (subject of the dilapidation report), a minimum of 5 working days prior to the commencement of work. Evidence confirming that a copy of the pre-construction dilapidation report was delivered to the adjoining properties must be provided to the PCA.

Should the owners of properties (or their agents) refuse access to carry out inspections, after being given reasonable written notice, this shall be reported to Council to obtain Council's agreement to complete the report without access. Reasonable notice is a request for access in no sooner than 14 days between 8.00am-6.00pm.

14. Stormwater System

The submitted stormwater plan has been assessed as a concept plan only. Final detailed plans of the drainage system in accordance with Council stormwater management code and AS/NZS 3500.3: 2015 (as amended), prepared by a professional engineer specialising in hydraulic engineering, shall be submitted for approval with the Construction Certificate.

15. Pump-Out System Design for Stormwater Disposal

The design of the pump-out system for storm water disposal will be permitted for drainage of basement areas only, and must be designed in accordance with the following criteria:

- (a) The pump system shall consist of two pumps, connected in parallel, with each pump being capable of emptying the holding tank at the rate equal to the rate of inflow for the one-hour duration storm. The holding tank shall be capable of holding four hour's runoff from a one-hour duration storm of the 1 in 100 year storm;
- (b) The pump system shall be regularly maintained and serviced, every six (6) months; and
- (c) Any drainage disposal to the street gutter from a pump system must have a stilling sump provided at the property line, connected to the street gutter by a suitable gravity line.

Details and certification of compliance from a professional engineer specialising in civil engineering shall be provided for approval with the Construction Certificate application.

16. Off Street Parking – Compliance with AS2890

All driveways, access ramps, vehicular crossings and car parking spaces shall be designed and constructed in accordance with the current version of Australian Standards, AS 2890.1 (for car parking facilities), AS 2890.6 (parking for people with disabilities) and AS 2890.2 (for commercial vehicle facilities).

17. Landscape Plan

A detailed landscape plan, drawn to scale, by a qualified landscape architect or landscape designer, must be submitted prior to the issue of the Construction Certificate. The plan must include:

A detailed landscape plan, drawn to scale, by a qualified landscape architect or landscape designer, must be submitted prior to the issue of the Construction Certificate. The plan must include:

- (a) Minimum deep soil area of 261.8m² with at least 50% of this area behind the front building line.
- (b) Location of existing and proposed structures, services and existing trees;
- (c) Details of earthworks including mounding and retaining walls and planter boxes;
- (d) At least one (1) new canopy tree in the rear yard - to have a minimum mature height of 6m to 8m planted within a minimum 50 litre container;
- (e) Location of proposed plants and a plant schedule showing the plant symbol, botanical name/ common name; quantity; pot size/; and mature height x width.
- (f) Details of planting procedure and maintenance;
- (g) Landscape specification;
- (h) Details of drainage and watering systems;
- (i) Details of garden edging and turf; and
- (j) Any required fencing, retaining walls and other structures not shown on other approved architectural and engineering plans.

18. Tree Protection and Retention (CC8098)

The following trees shall be retained and protected:

Tree No	Tree Species	Location of Tree	Tree Protection Zone (TPZ)
1	<i>Lophostemon confertus</i>	Street tree located front of 7 Patricia Street	6.6 metres

Details of the trees to be retained must be included on the Construction Certificate plans.

General Tree Protection Measures

- (a) All trees to be retained shall be protected and maintained during demolition, excavation and construction of the site.
- (b) The tree protection measures must be undertaken in accordance *AS4970 -2009 Protection of trees on development sites*.
- (c) Details of the tree protection measures to be implemented must be provided with the application for a Construction Certificate by a suitably qualified Arborist (AQF Level 5 or above in Arboriculture).
- (d) The Arborist must be present on-site during the stages of construction when works are being undertaken that could impact on the tree canopy or root zone within the tree protection zone to implement the tree protection measures as required.
- (e) Unless otherwise specified in AS 4970-2009, a protective fence consisting of 1.8 metres high, fully supported chainmesh fence shall be erected around the base of the tree. The distance of the fence from the base of each tree is to be in accordance with the TPZ listed in the table above. A layer of organic mulch 100 millimetres thick shall be placed over the protected area and no soil or fill should be placed within the protection area.
- (f) No services shall be installed within the TPZ of the tree unless approved by Council. This fence shall be kept in place during demolition, construction and also have a sign displaying 'Tree Protection Zone' attached to the fence and must also include the name and contact details of the Project Arborist.

Specific Street Tree Protection Measures

- (g) A sound protection barrier anchored firmly into the ground 1.8m in height x 2 metres clear of the base of the tree at any one point and that the fence is to extend up to the back of the kerb and to the edge of the footpath.

Excavation works near tree to be retained

- (h) Excavations around the trees to be retained on site or the adjoining properties shall be supervised by the Project Arborist to ensure that the root system will not adversely be affected.
- (i) Where the Tree Protection Zone (TPZ) of trees on site or adjoining sites become compromised by any excavation works, the Project arborist shall be consulted to establish the position of any major roots and determine the necessary measures to protect these roots. The recommendations of the Arborist shall be submitted to Council prior to any further demolition or construction works taking place.
- (j) Tree Protection Zone around the trees to be retained are not to have soil level changes or services installed in this area. Any structures proposed to be built in this area of the trees are to utilise pier and beam or cantilevered slab construction.

Details satisfying this condition shall be shown on the Construction Certificate plans.

PRIOR TO THE COMMENCEMENT OF WORK (INCLUDING DEMOLITION & EXCAVATION)

19. Demolition & Asbestos

The demolition work shall comply with the provisions of Australian Standard AS2601:2001 – Demolition of Structures, NSW [Work Health & Safety Act 2011](#) and the NSW [Work Health & Safety Regulation 2011](#). The work plans required by AS2601:2001 shall be accompanied by a written statement by a suitably qualified person that the proposals contained in the work plan comply with the safety requirements of the Standard. The work plans and the safety statement shall be submitted to the PCA prior to the commencement of works.

For demolition work which involves the removal of asbestos, the asbestos removal work must be carried out by a licensed asbestos removalist who is licensed to carry out the work in accordance with the NSW [Work Health & Safety Act 2011](#) and the NSW [Work Health & Safety Regulation 2011](#) unless specified in the Act and/or Regulation that a license is not required.

All demolition work including the removal of asbestos, shall be undertaken in accordance with the [Demolition Code of Practice](#) (NSW Work Cover July 2015)

Note: Copies of the Act, Regulation and Code of Practice can be downloaded free of charge from the SafeWork NSW website: www.SafeWork.nsw.gov.au.

20. Demolition Notification Requirements

The following notification requirements apply to this consent:

- (a) The developer /builder must notify adjoining residents five (5) working days prior to demolition. Such notification is to be a clearly written note giving the date demolition will commence, contact details of the developer/builder, licensed asbestos demolisher and the appropriate regulatory authority. Notification is to be placed in the letterbox of every premises (including every residential flat or unit, if any) either side and immediately at the rear of the demolition site.
- (b) Five (5) working days prior to demolition, the developer/builder is to provide written notification to Council advising of the demolition date, details of the SafeWork licensed asbestos demolisher and the list of residents advised of the demolition.
- (c) On demolition sites where buildings to be demolished contain asbestos, a standard commercially manufactured sign containing the words “DANGER ASBESTOS REMOVAL IN PROGRESS” measuring not less than 400mm x 300mm is to be erected in a prominent visible position (from street frontage) on the site. The sign is to be erected prior to demolition work commencing and is to remain in place until such time as all asbestos material has been removed from the site to an approved waste facility.

21. Dial Before You Dig

The applicant shall contact “Dial Before You Dig on 1100” to obtain a Service Diagram prior to the issuing of the Construction Certificate. The sequence number obtained from “Dial Before You Dig” shall be forwarded to Council’s Engineers for their records.

22. Utility Arrangements

Arrangements are to be made with utility authorities (Water, Gas, Electricity etc.) in respect to the services supplied by those authorities to the development. The cost associated with the provision or adjustment of services within the road and footway areas is to be at the applicants' expense.

DURING CONSTRUCTION

23. Hours of Construction for Demolition and Building Work

Any work activity or activity associated with the development consent that requires the use of any tools (including hand tools) or any power operated plant and machinery that creates noise on or adjacent to the site shall not be performed, or permitted to be performed, except between the hours of 7.00 am to 5.00 pm, Monday to Friday and 8:00am to 1:00pm on Saturdays. No work or ancillary activity is permitted on Sundays, or Public Holidays.

Where the development involves the use of jack hammers/rock breakers and the like, or other heavy machinery, such equipment may only be used between the hours of 7:00am to 5:00pm Monday to Friday only.

Note: A penalty infringement notice may be issued for any offence.

24. Ground Levels and Retaining Walls

The ground levels of the site shall not be excavated, raised or filled, or retaining walls constructed on the allotment boundary, except where indicated on approved plans or approved by Council.

25. Cost of Work to be Borne by the Applicant

The applicant shall bear the cost of all works associated with the construction of the development that occurs on Council property. Care must be taken to protect Council's roads, including the made footway, kerbs, etc., and, where plant and vehicles enter the site, the footway shall be protected against damage by deep-sectioned timber members laid crosswise, held together by hoop iron straps and chamfered at their ends. This construction shall be maintained in a state of good repair and condition throughout the course of construction.

26. Obstruction of Road or Footpath

The use of the road or footpath for the storage of any building materials, waste materials, temporary toilets, waste or skip bins, or any other matter is not permitted unless separately approved by Council under Section 138 of the [Roads Act 1993](#) and/or under Section 68 of the [Local Government Act 1993](#). Penalty infringement Notices may be issued for any offences and severe penalties apply.

27. Excavation Works Near Tree to be Retained

Excavation around the tree/s to be retained on site or the adjoining properties shall be supervised by the Project Arborist to ensure that the root system will not be adversely affected.

Where the Tree Protection Zone of trees on site or adjoining sites become compromised by any excavation works, the Project Arborist shall be consulted to establish the position of any major roots and determine the necessary measures to protect these roots. The recommendations of the Arborist shall be submitted to Council prior to any further demolition or construction works taking place.

PRIOR TO THE ISSUE OF THE OCCUPATION CERTIFICATE

28. BASIX Certificate

All energy efficiency measures as detailed in the approved BASIX Certificate in the plans approved with the Development Consent, must be implemented before issue of any Occupation Certificate.

29. Requirements Prior to the Issue of the Occupation Certificate

The following shall be completed and or submitted to the PCA prior to the issue of the Occupation Certificate:

- (a) All the stormwater/drainage works shall be completed in accordance with the approved Construction Certificate plans prior to the issue of the Occupation Certificate.
- (b) The internal driveway construction works, together with the provision for all services (conduits and pipes laid) shall be completed in accordance with the approved Construction Certificate plans prior to the issue of the Occupation Certificate.
- (c) Construct any new vehicle crossings required.
- (d) Replace all redundant vehicle crossing laybacks with kerb and guttering, and replace redundant concrete with turf.
- (e) A Section 73 (Sydney Water) Compliance Certificate for the Subdivision shall be issued and submitted to the PCA prior to the issue of the Occupation Certificate.
- (f) Work as Executed Plans prepared by a Chartered Professional Engineer or a Registered Surveyor when all the site engineering works are complete shall be submitted to the PCA prior to the issue of the Occupation Certificate.

30. BASIX Compliance Certificate

A Compliance Certificate must be provided to the PCA regarding the implementation of all energy efficiency measures as detailed in the approved BASIX Certificate before any Occupation Certificate is issued.

31. Post Construction Dilapidation Report – Private Land

At the completion of the construction works, a suitably qualified person is to be engaged to prepare a post-construction dilapidation report. This report is to ascertain whether the construction works associated with the subject development created any structural damage to the following adjoining premises:

- (b) All neighbouring buildings and/or public assets likely to be affected by the excavation as determined by the consulting engineer (see Condition 13)

The report is to be prepared at the expense of the applicant and submitted to the PCA prior to the issue of the Occupation Certificate. In ascertaining whether adverse structural damaged has occurred to the adjoining premises, the PCA, must compare the post-construction dilapidation report with the pre-construction dilapidation report required by conditions in this consent.

Evidence confirming that a copy of the post-construction dilapidation report was delivered to the adjoining properties subject of the dilapidation report must be provided to the PCA prior to the issue of any Occupation Certificate.

32. Minor Development

Internal driveways and parking spaces are to be adequately paved with concrete or bitumen, or interlocking pavers to provide a dust-free surface.

33. Maintenance Schedule – On-site Stormwater Management

A Maintenance Schedule for the proposed on-site stormwater management measures is to be prepared and submitted to Council. The Maintenance Schedule shall outline the required maintenance works, how and when these will be done and who will be carrying out these maintenance works.

34. Stormwater Certification of the Constructed Drainage Works (Minor)

The constructed stormwater system shall be certified by a suitably qualified person, in accordance with Council's Stormwater Management Code, prior to the issue of any Occupation Certificate.

35. Vehicular Crossing - Minor Development

The vehicular crossing and/or footpath works shall be constructed by a private contractor at the expense of the applicant, in accordance with the Works Permit Approval issued by Council's Civic & Urban Services and in accordance with Council's Driveway Specifications.

Any existing vehicular crossing and/or laybacks which are redundant must be removed. The kerb and gutter, any other footpath and turf areas shall be restored at the expense of the applicant and in accordance with Council's Driveway Specifications.

The work must be completed before the issue of an Occupation Certificate.

36. Stormwater Drainage Works – Works As Executed

Prior to the issue of the Occupation Certificate, stormwater drainage works are to be certified by a professional engineer specialising in hydraulic engineering, with Works-As-Executed drawings supplied to Council detailing:

- (a) Compliance with conditions of development consent relating to stormwater;
- (b) The structural adequacy of the On-Site Detention system (OSD);
- (c) That the works have been constructed in accordance with the approved design and will provide the detention storage volume and attenuation in accordance with the submitted calculations;

- (d) Pipe invert levels and surface levels to Australian Height Datum;
- (e) Contours indicating the direction in which water will flow over land should the capacity of the pit be exceeded in a storm event exceeding design limits.

Council's Engineering Services section must advise in writing that they are satisfied with the Works-As-Executed prior to the issue of an Occupation Certificate.

OPERATIONAL CONDITIONS (ON-GOING)

37. Entering & Exiting of Vehicles

All vehicles shall enter and exit the premises in a forward direction.

38. Greywater System

In order to conserve and re-use water, Council encourages all developments for new dwellings to incorporate a greywater reuse system. The system can incorporate a *greywater diversion device* or a *domestic greywater treatment system*. Any system installed is to ensure that it complies with the Plumbing Code of Australia, maintained at all times and does not result in any adverse amenity impacts on the subject premises and surrounding properties.

OPERATIONAL REQUIREMENTS UNDER THE ENVIRONMENTAL PLANNING & ASSESSMENT ACT 1979

39. Requirement for a Construction Certificate

The erection of a building must not commence until a Construction Certificate has been issued.

40. Appointment of a PCA

The erection of a building must not commence until the applicant has:

- (a) appointed a PCA for the building work; and
- (b) if relevant, advised the PCA that the work will be undertaken as an Owner -Builder.

If the work is not going to be undertaken by an Owner - Builder, the applicant must:

- (c) appoint a Principal Contractor to undertake the building work. If residential building work (within the meaning of the [Home Building Act 1989](#)) is to be undertaken, the Principal Contractor must be a holder of a contractor licence; and
- (d) notify the PCA of the details of any such appointment; and
- (e) notify the Principal Contractor of any critical stage inspections or other inspections that are required to be carried out in respect of the building work.

41. Notification of Critical Stage Inspections

No later than two days before the building work commences, the PCA must notify:

- (a) the consent authority and the Council (if not the consent authority) of his or her appointment; and
- (b) the applicant of the critical stage inspections and other inspections that are to be carried out with respect to the building work.

42. Notice of Commencement

The applicant must give at least two days' notice to the Council and the PCA of their intention to commence the erection of a building.

43. Occupation Certificate

A person must not commence occupation or use of the whole or any part of a new building unless an Occupation Certificate has been issued in relation to the building or part.

PRESCRIBED CONDITIONS

44. Clause 75 – BASIX Commitments

This Clause requires the fulfilment of all BASIX Commitments as detailed in the BASIX Certificate to which the development relates.

45. Clause 69 – Building Code of Australia & Home Building Act 1989

Requires all building work to be carried out in accordance with the Building Code of Australia. In the case of residential building work to which the [Home Building Act 1989](#) relates, there is a requirement for a contract of insurance to be in force before any work commences.

46. Clause 70 – Erection of Signs

Requires the erection of signs on site and outlines the details which are to be included on the sign. The sign must be displayed in a prominent position on site and include the name and contact details of the PCA and the Principal Contractor.

47. Clause 71 – Home Building Act 1989

If the development involves residential building work under the [Home Building Act 1989](#), no work is permitted to commence unless certain details are provided in writing to Council. The name and licence/permit number of the Principal Contractor or Owner Builder and the name of the Insurer by which work is insured under Part 6 of the [Home Building Act 1989](#).

ADVISORY NOTES

i. Review of Determination

Section 8.2 of the Environmental Planning and Assessment Act confers on an applicant who is dissatisfied with the determination of the application the right to lodge an application with Council for a review of such determination. Any such review must however be completed within 6 months from its determination. Should a review be contemplated sufficient time should be allowed for Council to undertake public notification and other processes involved in the review of the determination.

Note: review provisions do not apply to Complying Development, Designated Development, State Significant Development, Integrated Development or any application determined by the Sydney East Planning Panel or the Land & Environment Court.

ii. Appeal Rights

Division 8.3 (Reviews and appeals) Part 8 of the Environmental Planning and Assessment Act 1979 confers on an applicant who is dissatisfied with the determination of the application a right of appeal to the Land and Environment Court of New South Wales.

iii. Lapsing of Consent

This consent will lapse unless the development is physically commenced within 5 years from the Date of Operation of this consent, in accordance with Section 4.53 of the Environmental Planning and Assessment Act 1979 as amended.

iv. Access to NSW Legislations (Acts, Regulations and Planning Instruments)

NSW legislation can be accessed free of charge at www.legislation.nsw.gov.au

v. Stormwater & Ancillary Works – Applications under Section 138 Roads Act and/or Section 68 Local Government Act 1993

To apply for approval under Section 138 of the [Roads Act 1993](http://www.legislation.nsw.gov.au):

- (a) Complete the Works Permit Application Form which can be downloaded from Strathfield Council's Website at www.strathfield.nsw.gov.au.
- (b) In the Application Form, quote the Development Consent No. (DA 2021/300) and reference this condition number (Advisory Note v.)
- (c) Lodge the application form, together with the associated fees at Council's Customer Service Centre, during business hours. Refer to Council's adopted Fees and Charges for the administrative and inspection charges associated with Works Permit applications.

An approval for a new or modified vehicular crossing will contain the approved access and/or alignment levels which will be required to construct the crossing and/or footpath. Once approved, all work shall be carried out by a private contractor in accordance with Council's specifications prior to the issue of an Occupation Certificate.

The developer must meet all costs of the extension, relocation or reconstruction of any part of Council's drainage system (including design drawings and easements) required to carry out the approved development.

vi. Site Safety Fencing

Site fencing must be erected in accordance with SafeWork Guidelines, to exclude public access to the site throughout the demolition and/or construction work, except in the case of alterations to an occupied dwelling. The fencing must be erected before the commencement of any work and maintained throughout any demolition and construction work.

A demolition licence and/or a high risk work license may be required from SafeWork NSW (see www.SafeWork.nsw.gov.au).

vii. Electricity Supply

This development may need a connection to the Ausgrid network which may require the network to be extended or its capacity augmented. You are advised to contact Ausgrid on 13 13 65 or www.ausgrid.com.au (Business and Commercial Services) for further details and information on lodging your application to connect to the network.

viii. Residential Waste

Council's residential waste collection service comprises one (1) x 120 litre (L) general waste bin, one (1) x 240L recycling bin and one (1) x 240L garden vegetation bin per dwelling for single dwellings, semi-detached and dual occupancy developments. Waste containers should be stored in a suitable place to avoid vandalism, nuisance (odour, vermin) and adverse visual impacts on residents and the streetscape. Waste storage areas should be located to minimise the distance of travel to the collection point, be easily accessible and be of sufficient size to accommodate the necessary waste storage bins in accordance with Appendix C, Section H Waste Minimisation and Management, Strathfield Consolidated Development Control Plan 2005.