

Minutes

Of the meeting of the:

Strathfield Internal Development Assessment Panel Meeting

Held on:

Friday, 29 May 2020

Commencing at 10:00am Main Building Meeting Room,
65 Homebush Road, Strathfield

TABLE OF CONTENTS

Item	Page No.
IDAP AGENDA ITEMS	
IDAP - Report No. 1	
DA2020/38 - 55 Bareena Street, Strathfield - Lot 1 DP 513302.....	4
IDAP - Report No. 2	
DA2020/059 15 Sylvanus Street, Greenacre Lot 19 Sec 7 DP 845.....	19
IDAP - Report No. 3	
DA2017/101/03 - 37-39 Punchbowl Road & 90 Water Street, Belfield Lot 5 DP 7675 & Lot 11 DP 592982	38
IDAP - Report No. 4	
DA2020/056: 40 Myrna Road, Strathfield Lot 23 DP14613.....	74
IDAP - Report No. 5	
DA2020/022 2 Ismay Avenue, Homebush Lot 16 DP35204	91

The meeting of the Strathfield Internal Development Assessment Panel Meeting was held in the Main Building Meeting Room, 65 Homebush Road, Strathfield on Friday 29 May 2020.

PRESENT

Stephen Clements, Deputy CEO/General Manager Planning, Environment & Urban Services
Kandace Lindeberg, Executive Manager, Landuse Planning and Development
George Andonoski, Specialist Strategic Planner

ALSO PRESENT

Nil

DECLARATIONS OF PECUNIARY INTEREST / CONFLICT OF INTEREST

NIL

TO: Strathfield Internal Development Assessment Panel Meeting - 29 May 2020
REPORT: IDAP – Report No. 1
SUBJECT: DA2020/38 - 55 BAREENA STREET, STRATHFIELD - LOT 1 DP 513302
DA NO. DA2020/38

RECOMMENDATION

That Development Application No. DA2020/38 for alterations and additions to the rear of building to enclose BBQ area and installation of BBQ at No. 55 Bareena Street, Strathfield be **APPROVED**, subject to the following conditions:

SPECIAL CONDITIONS (SC)

1. PROPOSED TREE REMOVAL (SC)

Any annotations indicating the removal of the existing tree – Lemon-scented Gum (*Corymbia citriodora*) in the rear yard of the site must be deleted from all plans and documentation that are to be submitted as part of any application for a Construction Certificate.

The existing tree must be retained and protected in perpetuity, and this must be reflected on in the revised architectural plans and any other documentation that are to be submitted and approved by the Principal Certifying Authority prior to the issue of any Construction Certificate.

(Reason: To ensure the significant and highly valued canopy tree is retained and protected.)

2. DESIGN CHANGES (SC)

To ensure the existing tree – Lemon-scented Gum (*Corymbia citriodora*) in the rear yard of the site is retained and protected, and to minimise any impacts on this tree, the proposed development must be re-designed:

- The entire development (including new footings, columns, walls, roofing, drainage infrastructure) must be located more than 3m away from the existing tree – Lemon-scented Gum (*Corymbia citriodora*);
- The entire development must be re-designed and amended to ensure that the existing tree – Lemon-scented Gum (*Corymbia citriodora*) is retained and protected in perpetuity and negligible/minimal impacts on this tree are inflicted; and
- Any new support footings and columns must be located within the footprint of the existing deck/BBQ area and must be directly above the existing footings of the deck/BBQ area. Any new footings and columns must not result in additional ground disturbance or excavation within the site.

Any design changes that are required to address this condition must be reflected in the revised architectural plans and any other documentation to be submitted and approved by the Principal Certifying Authority prior to the issue of a Construction Certificate.

(Reason: To ensure the significant and highly valued canopy tree is retained and protected.)

3. APPROVED DEVELOPMENT COMPONENTS (SC)

This consent **does not grant approval for any components** within the site (including the

existing dwelling, deck/BBQ area and pool) that are not the subject of this consent and have been approved under a separate approval process such as via a Complying Development Certificate.

A Final Occupation Certificate must be submitted to Council for the development that is the subject of Complying Development Certificate CDC16/2010 prior to the application of a Construction Certificate (for the approved development).

(Reason: To clarify the components approved under this consent and to ensure final approval and occupation is granted for the existing dwelling and deck/BBQ area.)

GENERAL CONDITIONS (GC)

4. APPROVED PLANS AND REFERENCE DOCUMENTATION (GC)

The development, except where modified by a condition(s) of consent, is to be carried out in accordance with the following plans and reference documentation:

Plans affixed with Council's 'Development Consent' stamp relating to Development Consent No. DA2020/38:

Drawing No.	Title/Description	Prepared by	Issue / Revision & Date	Date received by Council
DA.01	Floor Plans	Bechara Chan & Associates	Rev B 02.04.20	02.04.20
DA.02	Roof Plan & Site Plan	Bechara Chan & Associates	Rev B 02.04.20	02.04.20
DA.05	Elevations	Bechara Chan & Associates	Rev C 14.04.20	04.05.20
DA.06	Sections	Bechara Chan & Associates	Rev B 14.04.20	04.05.20
A20074 -Cover	General Notes	Alpha Engineering & Development	Rev B 02.04.20	02.04.20
A20074 -SW01	Sediment and Erosion Control Plan	Alpha Engineering & Development	Rev B 02.04.20	02.04.20
A20074 -SW02	Ground Floor Drainage Plan	Alpha Engineering & Development	Rev B 02.04.20	02.04.20
A20074 -SW03	Roof Drainage Plan	Alpha Engineering & Development	Rev B 02.04.20	02.04.20

In the event of any inconsistency, the conditions of this consent shall prevail.

(Reason: To ensure that the form of the development undertaken is in accordance with the determination of Council.)

5. CONSTRUCTION HOURS (GC)

No construction or any other work related activities shall be carried out on the site outside the hours of 7.00 am to 5.00 pm Mondays to Fridays and 8am to 1pm Saturdays.

No building activities are to be carried out at any time on a Sunday or public holiday.

Where the development involves the use of jackhammers/rock breakers and the like or other heavy machinery, such equipment may only be used between the hours of 7.00 am - 5.00 pm Monday to Friday only.

(Reason: To maintain amenity to adjoining land owners.)

6. DEMOLITION – GENERALLY (GC)

Alteration and demolition of the existing building is limited to that documented on the approved plans (by way of notation). No approval is given or implied for removal and/or rebuilding of any portion of the existing building which is not shown to be altered or demolished.

(Reason: To ensure compliance with the approved development.)

7. DEMOLITION - SITE SAFETY FENCING (GC)

Site fencing is to be erected to a minimum height of 1.8m complying with WorkCover Guidelines, to exclude public access to the site, prior to any demolition works occurring and maintained for the duration of the demolition works.

If applicable, a separate Hoarding Application for the erection of an A class (fence type) or B class (overhead type) hoarding/fencing along the street frontage(s) complying with WorkCover requirements must be obtained including:

- payment to Council of a footpath occupancy fee based on the area of footpath to be occupied and Council's Schedule of Fees and Charges before the commencement of work; and
- provision of a Public Risk Insurance Policy with a minimum cover of \$10 million in relation to the occupation of and works within Council's road reserve, for the full duration of the proposed works, must be obtained with a copy provided to Council.

(Reasons: Statutory requirement and health and safety.)

8. ENVIRONMENTAL PROTECTION – TREE (GC)

All street trees and trees on private property that are protected under Council's controls, shall be retained except where Council's prior written consent has been obtained. The felling, lopping, topping, ringbarking, wilful destruction or removal of any tree/s unless in conformity with this approval or subsequent approval is prohibited.

All healthy trees and shrubs identified for retention on the approved drawings are to be suitably protected in accordance with Section 4, Tree protection measures, and Appendix C Tree Protection Zone Sign, of Australian Standard AS4970 - 2009, Protection of Trees on Development Sites, prior to the commencement of any works (including any demolition and excavation) and maintained for the duration of the works.

In this regard the street tree and all protected trees on or adjacent to the site will be protected as described below;

- i. A Tree Protection (Management) Plan prepared by a AQF Level 5 Arborist is to be available on site at all times prior to the issue of the Construction Certificate, for all demolition and site works. This Tree Protection (Management) Plan must be shown on the demand of Authorised Council staff.
- ii. Protective perimeter fencing must be consistent with AS 4687, using metal

- fence posts greater than 20mm diameter and solid or chain wire mesh 2 metres in height supported on concrete pads/feet at 2-2.5 metre spacing. Fencing placement should not be closer than 2.5 metres from the trunk of each protected tree, or at a distance as specified by the approved Tree Protection (Management) Plan and approved by Council's Tree Management Officer. Shade cloth is to be used to prevent entry of dust and contaminated liquids into the root protection area.
- iii. Signs must be placed on the Fencing. These signs must comply with AS1319. The signs must state the purpose of the fencing and the name and contact details of the builder and the appointed AQF Level 5 consultant arborist.
 - iv. Root protection is to be provided in the form of mulching to a depth of 50-100mm, inside of the fenced tree protection zone.
 - v. Ground (Root) Trunk and Branch Protection must comply with the diagram of Figure 4 of AS4970 – 2009. Ground protection within the tree protection zone and drip line should be in the form of heavy steel plates or timber rumble boards over mulch or aggregate. Trunk and branch protection should be to a minimum height of 2 metres and must include measures to protect the tree/s against damage from the movement of trucks, plant equipment and materials at greater heights above ground level.
 - vi. Temporary signs, cables, wires must not be attached to, or suspended, on any street tree or protected tree.
 - vii. Above ground utilities must not be placed within the canopy of an existing protected tree, or create the future need for clearance pruning.
 - viii. Below ground utilities/services must not be located inside the fenced tree protection zone.
 - ix. Scaffolding must not be located in the fenced tree protection zone unless authorised by the approved Tree Protection (Management) Plan and Council's Tree Management Officer
 - x. Council must be notified in writing within 24 hours, for all temporary removal of the tree protection fencing ground (root) trunk and branch protection within the root protection area.
 - xi. Pruning of a street tree is prohibited without the written consent of Council.

(Reason: To ensure the protection of trees to be retained on the site.)

9. **LIGHTING (GC)**

Any lighting for the approved structure shall be installed and maintained in accordance with Australian Standard AS 4282-1997: Control of the Obtrusive Effects of Outdoor Lighting so as to avoid annoyance to the occupants of adjoining premises or glare to motorists on nearby roads.

No flashing, moving or intermittent lighting, visible from any public place may be installed on the premises or external signage associated with the development, without the prior approval of Council.

(Reason: To protect the amenity of surrounding development and protect public safety.)

10. **MATERIALS – CONSISTENT WITH SUBMITTED SCHEDULE (GC)**

All external materials, finishes and colours are to be consistent with the schedule submitted and approved by Council with the development application.

(Reason: To ensure compliance with this consent.)

11. PRINCIPAL CERTIFYING AUTHORITY (PCA) IDENTIFICATION SIGN (GC)

Prior to commencement of any work, signage must be erected in a prominent position on the work site identifying:

- i) The Principal Certifying Authority (PCA) by showing the name, address and telephone number of the PCA;
- ii) The Principal Contractor by showing the Principal Contractor's name, address and telephone number (outside of work hours) for that person; and
- iii) The sign must state that unauthorised entry to the work site is prohibited.

Any such sign is to be maintained while the work is being carried out, but must be removed when the work has been completed.

This clause does not apply to building work, subdivision work or demolition work that is carried out inside an existing building that does not affect the external walls of the building.

(Reason: Statutory requirement.)

12. SITE MANAGEMENT (DURING DEMOLITION AND CONSTRUCTION WORKS)

All of the following are to be satisfied/complied with during demolition, construction and any other site works:

- i) All demolition is to be carried out in accordance with Australian Standard AS 2601-2001.
- ii) Demolition must be carried out by a registered demolition contractor.
- iii) A single entrance is permitted to service the site for demolition and construction. Protection pads are to be installed to the kerb, gutter and nature strip where trucks and vehicles enter the site.
- iv) No blasting is to be carried out at any time during construction of the building.
- v) Care must be taken during demolition/ excavation/ building/ construction to prevent any damage to adjoining buildings.
- vi) Adjoining owner property rights and the need for owner's permission must be observed at all times, including the entering onto land for the purpose of undertaking works.
- vii) Any demolition and excess construction materials are to be recycled wherever practicable.
- viii) The disposal of construction and demolition waste must be in accordance with the requirements of the Protection of the Environment Operations Act 1997.
- ix) All waste on the site is to be stored, handled and disposed of in such a manner as to not create air pollution (including odour), offensive noise or pollution of land and/or water as defined by the Protection of the Environment Operations Act 1997. All excavated material should be removed from the site in an approved manner and be disposed of lawfully to a tip or other authorised disposal area.
- x) All waste must be contained entirely within the site.
- xi) A site plan including temporary waste storage locations, construction material storage areas and vehicular access to and from the site must be included with application.
- xii) Section 143 of the Protection of the Environment Operations Act 1997 requires waste to be transported to a place which can lawfully accept it. All non-recyclable demolition materials are to be disposed of at an approved waste disposal depot in accordance with legislation.
- xiii) Details as to the method and location of disposal of demolition materials (weight dockets, receipts, etc.) should be kept on site as evidence of approved methods of disposal or recycling and must be presented to Council and/or Principal Certifying

- Authority upon request.
- xiv) All materials on site or being delivered to the site are to generally be contained within the site. The requirements of the Protection of the Environment Operations Act 1997 must be complied with when placing/stockpiling loose material, disposing of concrete waste, or other activities likely to pollute drains or water courses.
 - xv) Any materials stored on site must be stored out of view or in such a manner so as not to cause unsightliness when viewed from nearby lands or roadways.
 - xvi) Public footways, include nature strips and roadways adjacent to the site must be maintained and cleared of obstructions during construction. No building materials, waste containers or skips may be stored on the road reserve or footpath without prior separate approval from Council, including payment of relevant fees.
 - xvii) Building operations such as brick-cutting, washing tools or paint brushes, and mixing mortar not be performed on the roadway or public footway or any other locations which could lead to the discharge of materials into the stormwater drainage system.
 - xviii) All site waters during excavation and construction must be contained on site in an approved manner to avoid pollutants entering into waterways or Council's stormwater drainage system.
 - xix) Any work must not prohibit or divert any natural overland flow of water.
 - xx) Toilet facilities for employees must be provided in accordance with WorkCover NSW.

(Reason: To ensure that demolition, building and any other site works are undertaken in accordance with relevant legislation and policy and in a manner which will be non-disruptive to the local area.)

13. WASTE – TRACKABLE (GC)

Removal of trackable waste (as defined by the NSW Environment Protection Authority) from the site must comply with the Protection of the Environment Operations (Waste) Regulation 2005 for the transportation, treatment and disposal of waste materials. Waste materials must not be disposed on land without permission of the land owner and must with the provisions of the Protection of the Environment and Operations Act 1997.

(Reason: To ensure compliance with legislation.)

14. STORMWATER DRAINAGE SYSTEM (GC)

The stormwater drainage system, where altered/modified or newly constructed, must be designed to comply with the Australian Standard AS3500.3:2003. A detailed Stormwater Management Plan (SWMP) in line with Council's Stormwater Management Code is to be prepared and certified by an Accredited Civil/Hydraulic Engineer and submitted to the Principal Certifying Authority and Council, prior to the issue of a Construction Certificate. The SWMP is to be based on the approved development as modified by any conditions of consent.

(Reason: To ensure appropriate provision is made for the disposal and management of stormwater generated by the development, and to ensure public infrastructure in Council's care and control is not overloaded.)

15. SYDNEY WATER - TAP IN TM (GC)

The approved plans must be submitted to a Sydney Water Tap inTM to determine whether the development application will affect Sydney Water's sewer and water mains, stormwater drains and/or easements, and if further requirements need to be met. The approved plans will be appropriately endorsed. For details please refer to 'Plumbing, building and developing' section of Sydney Water's web site at www.sydneywater.com.au then see

'Building', or telephone 13000 TAP IN (1300 082 746). The Certifying Authority must ensure that a Tap in™ agent has appropriately stamped the plans prior to the issue of the Construction Certificate.

(Reason: Compliance with Sydney Water requirements.)

16. UTILITIES AND SERVICES - PROTECTION OF (GC)

Any footings or excavation to be located or undertaken adjacent to Council's stormwater must be designed to address the following requirements:

- i) All footings and excavation must be located wholly within the site and clear of any easement boundaries;
- ii) All footings and excavation must be located a minimum of 1000mm from the centreline of the pipeline or 500mm from the outside of the pipeline, whichever is the greater distance from the centreline; and
- iii) Footings must extend to at least the depth of the invert of the pipeline unless the footings are to be placed on competent bedrock.

If permanent excavation is proposed beneath the obvert of the pipeline, suitable means to protect the excavation and proposed retaining structures from seepage or other water flow from the pipeline and surrounding subsoil, must be provided. The design must be prepared by a qualified practicing Structural/Civil Engineer.

Construction plans must be approved by the appropriate utility's office (e.g. council, Sydney Water Corporation) to demonstrate that the development complies with the utility's requirements.

The applicant must provide written evidence (e.g. compliance certificate, formal advice) of compliance with the requirements of all relevant utility providers (e.g. Water, Energy, Telecommunications, Gas).

(Reason: To ensure protection of Council assets.)

CONDITIONS TO BE SATISFIED PRIOR TO THE ISSUE OF A CONSTRUCTION CERTIFICATE (PCC)

17. BUILDING CODE OF AUSTRALIA - COMPLIANCE WITH (CC)

All architectural drawings, specifications and related documentation shall comply with the Building Code of Australia (BCA). All work must be carried out in accordance with the requirements of the Building Code of Australia (BCA).

In the case of residential building work for which the Home Building Act 1989 requires there to be a contract of insurance in force in accordance with Part 6 of that Act, such a contract of insurance is to be in force before any building work authorised to be carried out by the consent commences.

Details demonstrating compliance with this condition are to be submitted to the Principle Certifying Authority, prior to issue of the Construction Certificate.

(Reason: This is a 'prescribed' condition under clause 98(1) of the Environmental Planning and Assessment Regulation 2000.)

18. COMMENCEMENT OF WORKS (NO WORKS UNTIL A CC IS OBTAINED)

Building work, demolition or excavation must not be carried out until a Construction Certificate has been issued by either Strathfield Council or a Principal Certifying Authority.

Demolition of any part of a building triggers 'commencement of erection of building' pursuant of section 4.19 of the EP&A Act 1979. Accordingly, demolition works must not commence until a Construction Certificate has been issued, a Principal Certifying Authority has been appointed and a Notice of Commencement has been issued.

(Reason: To ensure compliance with statutory provisions.)

19. CONSTRUCTION AND ENVIRONMENTAL MANAGEMENT PLAN (CC)

The applicant must prepare and submit a Construction and Environmental Management Plan (CEMP) to the Principal Certifying Authority, including:

- i) Detailed information on any approvals required from other authorities prior to or during construction.
- ii) Traffic management, including details of:
 - ingress and egress of vehicles to the site;
 - management of loading and unloading of materials;
 - the location of heavy vehicle parking off-site; and
 - designated routes for vehicles to the site.
- iii) The proposed areas within the site to be used for a builder's site office and amenities, the storage of excavated material, construction materials and waste containers during the construction period.
- iv) Erosion and sediment control, detailing measures and procedures consistent with the requirements of Council's guidelines for managing stormwater, including:
 - the collection and treatment of stormwater and wastewater generated on site prior to discharge; and
 - procedures to prevent run-off of solid material and waste from the site.
- v) Waste management, including:
 - details of the types and estimated volumes of waste materials that will be generated;
 - procedures for maximising reuse and recycling of construction materials; and
 - details of the off-site disposal or recycling facilities for construction waste.
- vi) Dust control, outlining measures to minimise the generation and off-site transmission of dust and fine particles, such as watering or damp cloth fences.
- vii) A soil and water management plan, which includes:
 - measures to minimise the area of soils exposed at any one time and conserve top soil;
 - identification and protection of proposed stockpile locations;
 - preservation of existing vegetation and revegetation;
 - measures to prevent soil, sand, sediments leaving the site in an uncontrolled manner;
 - measures to control surface water flows through the site in a manner that diverts clean run-off around disturbed areas, minimises slope gradient and flow distance within disturbed areas, ensures surface run-off occurs at non-erodible velocities, and ensures disturbed areas are promptly rehabilitated;
 - details of sediment and erosion control measures in place before work commences;
 - measures to ensure materials are not tracked onto the road by vehicles entering or leaving the site; and
 - details of drainage to protect and drain the site during works.

viii) Asbestos management procedures:

- Anyone who removes, repairs or disturbs bonded or a friable asbestos material must hold a current removal licence from Workcover NSW holding either a Friable (Class A) or a Non- Friable (Class B) Asbestos Removal License which ever applies and a current WorkCover Demolition License where works involve demolition. To find a licensed asbestos removalist please see www.workcover.nsw.gov.au
- Removal of asbestos by a person who does not hold a Class A or Class B asbestos removal license is permitted if the asbestos being removed is 10m2 or less of non-friable asbestos (approximately the size of a small bathroom). Friable asbestos materials must only be removed by a person who holds a current Class A asbestos license.
- Before starting work, a work site-specific permit approving each asbestos project must be obtained from WorkCover NSW. A permit will not be granted without a current WorkCover licence. All removal, repair or disturbance of or to asbestos material must comply with the following:
 - The Work Health and Safety Act 2011;
 - The Work Health and Safety Regulation 2011;
 - How to Safety Remove Asbestos Code of Practice – WorkCover 2011; and
 - Safe Work Australia Code of Practice for the Management and Control of Asbestos in the Workplace.
- Following completion of asbestos removal works undertaken by a licensed asbestos removalist re-occupation of a workplace must not occur until an independent and suitably licensed asbestos removalist undertakes a clearance inspection and issues a clearance certificate.
- The developer or demolition contractor must notify adjoining residents at least two (2) working days (i.e. Monday to Friday exclusive of public holidays) prior to the commencement of asbestos removal works. Notification is to include, at a minimum:
 - the date and time when asbestos removal works will commence;
 - the name, address and business hours contact telephone number of the demolisher, contractor and/or developer;
 - the full name and license number of the asbestos removalist/s; and
 - the telephone number of WorkCover's Hotline 13 10 50
 - warning signs informing all people nearby that asbestos removal work is taking place in the area. Signs should be placed at all of the main entry points to the asbestos removal work area where asbestos is present. These signs should be weatherproof, constructed of light-weight material and adequately secured so they remain in prominent locations. The signs should be in accordance with AS 1319-1994 Safety signs for the occupational environment for size, illumination, location and maintenance; and
 - appropriate barricades installed as appropriate to prevent public access and prevent the escape of asbestos fibres. Barricades must be installed prior to the commencement of asbestos removal works and remain in place until works are completed.

(Reason: Safety, amenity and protection of public infrastructure and the environment.)

20. COUNCIL PERMITS – FOR ALL ACTIVITIES ON COUNCIL LAND (CC)

Works Permit

(as per Section 68 of the Local Government Act 1993 and Section 138 and 139 of the Roads Act 1993)

A Works Permit is required for construction of a vehicular crossing (driveway), new

stormwater down pipe connection to kerb and gutter, new footpath and/or stormwater connection. A Works Permit Application Form is available from Council's Customer Centre or can be downloaded from Council's website. The applicable fees and charges are located on Council's website.

Standing Plant Permit

This permit must be applied for where it is intended to park a concrete pump, crane or other plant on the roadway or footpath. A Standing Plant Permit Application Form is available from Council's Customer Centre or can be downloaded from Council's website. The applicable fees and charges are located on Council's website. Please note a Road Closure Permit is not required for standing plant.

Skip Bin Permit

This permit must be applied for if you intend to place a skip bin on the roadway or footpath. A Skip Bin Application Form is available from Council's Customer Centre or can be downloaded from Council's website. The applicable fees and charges are located on Council's website.

Temporary Full or Part Road Closure Permit

This permit must be applied for if you require a full or a part road closure to take place to assist in your construction works. Please use the Works Permit Application Form, which is available from Council's Customer Service Centre or can be downloaded from Council's website. The applicable fees and charges are located on Council's website. Please note a Road Closure Permit is not required for standing plant.

Hoarding/Fencing Permit

This permit must be applied for if you intend to erect a Class A (fence type) or Class B (overhead type) hoarding/fencing along the street frontage(s). A Hoarding Permit Application Form is available from Council's Customer Service Centre or can be downloaded from Council's website. The applicable fees and charges are located on Council's website.

Work Zone Permit

This permit must be applied for if you require permanent parking along the kerbside at the front of the site during construction works. A Work Zone Permit Application Form is available from Council's Customer Service Centre or can be downloaded from Council's website. The applicable fees and charges are located on Council's website.

Ground Anchoring Permit

This permit must be applied for, for the installation of ground anchors under Council's footway/road reserve. It does not cover ground anchors under private properties. A separate approval is required to be obtained from Roads and Maritime Services (RMS) if it is proposed to install ground anchors under a State or Classified Regional Road (please refer to the end of this application form for more information).

(Reason: Council requirement.)

21. **SECURITY PAYMENT – DAMAGE DEPOSIT FOR COUNCIL INFRASTRUCTURE (CC)**

A security (damage deposit) of \$330.00 (calculated in accordance with Council's adopted Fees and Charges) shall be paid to Council, prior to the issue of a Construction Certificate.

The deposit is required as security against any damage to Council property during works on the site. The applicant must bear the cost of all restoration works to Council's property damaged during the course of this development. All building work must be carried out in accordance with the Building Code of Australia.

Payment may be accepted in the form of cash, bank guarantee, cheque or credit card (financial transactions fees apply). Note: Additional fees apply for the lodgement of a bank guarantee in lieu of cash bond applies in accordance with Council's adopted Fees and Charges.

Any costs associated with works necessary to be carried out to rectify any damages caused by the development, shall be deducted from the Damage Deposit.

Note: Should Council property adjoining the site be defective e.g. cracked footpath, broken kerb etc., this should be reported in writing, or by photographic record, submitted to Council at least seven (7) days prior to the commencement of any work on site. This documentation will be used to resolve any dispute over damage to infrastructure. It is in the applicant's interest for it to be as full and detailed as possible.

The damage deposit shall be refunded upon completion of all works upon receipt of a Final Occupation Certificate stage and inspection by Council.

(Reason: Protection of Council infrastructure.)

22. EROSION AND SEDIMENTATION CONTROL PLAN (CC)

An Erosion and Sediment Control Plan is to be prepared where construction or excavation activity requires the disturbance of the soil surface and existing vegetation. Details including drawings and specifications must provide adequate measures for erosion and sediment control to ensure:

- i) Compliance with the approved Soil and Water Management Plan.
- ii) Removal or disturbance of vegetation and top soil is confined to within 3m of the approved building area (no trees to be removed without approval).
- iii) All uncontaminated run-off is diverted around cleared or disturbed areas.
- iv) Silt fences or other devices are installed to prevent sediment and other debris escaping from the cleared or disturbed areas into drainage systems or waterways.
- v) All erosion and sediment controls are fully maintained for the duration of demolition/development works.
- vi) Controls are put into place to prevent tracking of sediment by vehicles onto adjoining roadways.
- vii) All disturbed areas are rendered erosion-resistant by turfing, mulching, paving or similar.
- viii) All water pumped or otherwise removed from excavations or basement areas is filtered to achieve suspended solids/non filterable residue levels complying with the Australian Water Quality guidelines for Fresh and Marine Waters.
- ix) Pumped or overland flows of water are discharged so as not to cause, permit or allow erosion before the commencement of work (and until issue of the occupation certificate).

Details of the proposed soil erosion and sedimentation controls are to be submitted to the Principal Certifying Authority with the Construction Certificate Application. Under no circumstances are any works to commence, prior to these details being approved by the Principal Certifying Authority and the controls being in place on the site.

(Reason: Environmental protection.)

23. NOISE – CONSTRUCTION (CC)

All works carried out on site during construction/demolition/excavation/earthworks shall

comply with the NSW Protection of the Environment Operations Act 1997, the Department of Environment and Climate Changes "Interim construction noise guideline" and AS 2436-2010 – "Guide to noise and vibration control on construction, demolition and maintenance sites" for the control of construction noise which specifies that:

- Construction period of 4 weeks and under – The L90 Level measured over a period of not less than 15 minutes when the construction site is operating must not exceed the background level by more than 20 dB(A) at the boundary.
- Construction period greater than 4 weeks but not exceeding 26 weeks – The L90 level measured over a period of not less than 15 minutes when the construction site is operating must not exceed the background level by more than 10 dB(A) at the boundary.
- Construction period exceeding 26 weeks – The L90 level measured over a period of not less than 15 minutes when the construction site is operating must not exceed the background level by more than 5 dB(A) at the boundary.

Should complaints of a noise nuisance be substantiated, Council may require the acoustic treatment of the premises to ensure compliance with the NSW Department of Environment and Climate Changes "Interim construction noise guideline" and AS 2436-2010 – "Guide to noise and vibration control, demolition and maintenance sites" for the control of construction noise. A further acoustic assessment and report will be required to be provided to Council assessing the premises in working order.

(Reason: Noise attenuation.)

24. **STORMWATER DRAINAGE (CC)**

The following stormwater precautions are required to be provided on the site:

- i) Grated drains shall be provided along the driveway/basement entry at the vehicular crossing(s) and are to connect to the internal drainage system.
- ii) Overflow paths shall be provided to allow for flows in excess of the capacity of the pipe/drainage system draining the site.
- iii) Allowance shall be made for surface runoff from adjacent properties, and to retain existing surface flow path systems through the site. Any redirection or treatment of these flows shall not adversely affect any other properties
- iv) Boundary fencing shall be erected in such a manner as not to interfere with the natural flow of ground and surface water to the detriment of any other party.

(Reason: To ensure the site is drained appropriately and does not interfere with the natural flow of flood waters.)

CONDITIONS TO BE SATISFIED PRIOR TO THE COMMENCEMENT OF WORKS (PCW)

25. **APPOINTMENT OF A PRINCIPAL CERTIFYING AUTHORITY (PCA) (CW)**

No work shall commence in connection with this Development Consent until:

- i) A construction certificate for the building work has been issued by the consent authority or a Principal Certifying Authority.
- ii) The person having the benefit of the development consent has appointed a principal certifying authority for the building work, and notified the principal certifying authority that the person will carry out the building work as an owner/builder, if that is the case.
- iii) The principal certifying authority has, no later than 2 days before the building work commences:

- notified the Council of his or her appointment, and
 - notified the person having the benefit of the development consent of any critical stage inspections and other inspections that are to be carried out in respect of the building work.
- iv) The person having the benefit of the development consent, if not carrying out the work as an owner-builder, has:
- appointed a principal contractor for the building work who must be the holder of a contractor licence if any residential building work is involved;
 - notified the principal certifying authority of such appointment; and
 - unless that person is the principal contractor, notified the principal contractor of any critical stage inspections and other inspections that are to be carried out in respect of the building work.
- v) The person having the benefit of the development consent has given at least 2 days' notice to the Council of the person's intention to commence the erection of the building.

Note: If the principal certifying authority is the Council, the nomination will be subject to the payment of a fee for the service to cover the cost of undertaking all necessary inspections and the issue of the appropriate certificates.

Under the Environment Planning and Assessment (Quality of Construction) Act, 2003, a sign must be erected in a prominent position on the work site showing the name, address and telephone number of the principal certifying authority; the name of the principal contractor (if any) for the building work and a telephone number at which that person may be contacted outside working hours. That sign must also state that unauthorised entry is prohibited. The sign must not be removed until all work has been completed.

(Reason: Statutory requirement.)

26. NOTICE OF COMMENCEMENT (CW)

No work shall commence until the following details are submitted to Council:

- i) A Notice of Commencement (form will be attached with issue of a Construction Certificate or available from our website) within two (2) days of the date on which it is proposed to commence works associated with the Development Consent;
- ii) Details of the appointment of a Principal Certifying Authority (either Council or another Principal Certifying Authority); and
- iii) Details of the name, address and licence details of the Builder.

(Reason: Statutory requirement.)

CONDITIONS TO BE SATISFIED DURING DEMOLITION AND BUILDING WORKS (DBW)

27. CONSTRUCTION INSPECTIONS (DW)

The building works are to be inspected during construction by the Principal Certifying Authority (PCA) in accordance with the Building Legislation Amendment (Quality of Construction) Act 2002 and 162A Critical stage inspections for building work of the Environmental Planning and Assessment Regulation 2000.

28. OBSTRUCTION OF PUBLIC WAY NOT PERMITTED DURING WORKS (DW)

The public way must not be obstructed by any materials, vehicles, refuse, skips or the like, under any circumstances, without the prior approval of Council.

(Reason: To maintain public access and safety.)

29. PUBLIC INFRASTRUCTURE AND SERVICES (DW)

The applicant must comply with the requirements (including financial costs) of any relevant utility provider (e.g. Energy Australia, Sydney Water, Telstra, RMS, Council etc.) in relation to any connections, works, repairs, relocation, replacements and/or adjustments to public infrastructure or services affected by the development.

(Reason: To maintain public infrastructure and/or services.)

CONDITIONS TO BE SATISFIED PRIOR TO THE ISSUE OF AN OCCUPATION CERTIFICATE (POC)

30. DRAINAGE SYSTEM - MAINTENANCE OF EXISTING SYSTEM (OC)

Where elements of the existing drainage system are to be utilised, the existing drainage system shall be overhauled and maintained clear of silt and accumulated debris. Silt and the like shall be removed, not flushed from the system.

A certificate shall be provided by a suitably qualified person (a registered plumber or a person of equivalent or greater experience or qualification) to the satisfaction of the Principal Certifying Authority, prior to the issue of any Occupation Certificate to confirm that the system is in good working order and adequate to accept additional flows having regard to any relevant standards and/or Sydney Water requirements.

(Reason: Maintenance and environment.)

31. ENGINEERING WORKS (CERTIFICATION OF)

Prior to occupation of the premises, a Work As Executed (WAE) Plan of all engineering and/or drainage works is to be submitted to the Principal Certifying Authority. The WAE Plan is to be certified by an Accredited Civil/Hydraulic Engineer demonstrating that:

- i) The stormwater drainage system; and/or
- ii) The car parking arrangement and area; and/or
- iii) Any related footpath crossing works; and/or
- iv) The proposed basement pump and well system; and/or
- v) The proposed driveway and layback; and/or
- vi) Any other civil works

have been constructed in accordance with the approved plans and any relevant Standards and Council policies/specifications.

For major works, such as subdivisions, works within the road reserve (requiring separate S138 approval) and as where specified by Council, a Part 4A Certificate will be required. It is strongly recommended that an Engineer supervise all engineering related works.

Where Council is not the Principal Certifying Authority, an electronic copy of the above documents is to be provided to Council, prior to the issue of any Occupation Certificate.

(Reason: Asset management.)

32. OCCUPATION OF BUILDING (OC)

A person must not commence occupation or use (or change of use where an existing

building) of the whole or any part of a new building (within the meaning of section 109H (4) of the Act) unless an Interim Occupation Certificate or Final Occupation Certificate has been issued in relation to the building or part.

The Principal Certifying Authority is required to be satisfied, amongst other things, that:

- i) All required inspections (including each applicable mandatory critical stage inspection) have been carried out; and
- ii) Any preconditions to the issue of the certificate required by a development consent have been met.

Note: New building includes an altered portion of, or an extension to, an existing building.

(Reason: Statutory requirement.)

33. **STORMWATER - CERTIFICATION OF THE CONSTRUCTED DRAINAGE SYSTEM (OC)**

The constructed stormwater system shall be certified by a suitably qualified person, in accordance with Council's Stormwater Management Code, prior to the issue of any Occupation Certificate.

(Reason: Adequate stormwater management.)

RESOLUTION

The application be **APPROVED** subject to the recommended conditions.

FOR: S. Clements, K. Lindeberg, G. Andonoski

AGAINST: Nil

**** End Minutes - Report No. 1****

TO: Strathfield Internal Development Assessment Panel Meeting - 29 May 2020
REPORT: IDAP – Report No. 2
SUBJECT: DA2020/059 15 SYLVANUS STREET, GREENACRE
 LOT 19 SEC 7 DP 845
DA NO. DA2020/059

RECOMMENDATION

That Development Application No. DA2020/059 for demolition of existing building and construction of a two (2) storey attached dual occupancy development with front boundary fencing and strata subdivision at 15 Sylvanus Street, Greenacre be **APPROVED**, subject to the following conditions:

SPECIAL CONDITIONS (SC)

1. FINAL SUBDIVISION PLAN (SC)

Prior to the release of the Subdivision Certificate, the final subdivision plan must indicate the following:

- a) Driveway;
- b) Garage;
- c) First floor of each dwelling; and
- d) Shared wall as common property.

The final subdivision plan is to be submitted and approved by the Principal Certifying Authority.

(Reason: Compliance with SCDCP 2005).

GENERAL CONDITIONS (GC)

2. APPROVED PLANS AND REFERENCE DOCUMENTATION (GC)

The development, except where modified by a condition(s) of consent, is to be carried out in accordance with the following plans and reference documentation:

Plans affixed with Council's 'Development Consent' stamp relating to Development Consent No.DA2020/059:

Drawing No.	Title/Description	Prepared by	Issue / Revision & Date	Date received by Council
DA11	Subdivision Plan	RM Designers	Issue A	27 March 2020
DA13	Demolition & Sediment Control Plan		Issue A	27 March 2020
DA14	Site Plan	RM Designers	Issue B	13 May 2020
DA20	Ground Floor	RM Designers	Issue B	13 May 2020
DA21	First Floor	RM Designers	Issue B	13 May 2020
DA22	Roof Plan	RM Designers	Issue B	13 May 2020
DA23	Concept Landscape	RM Designers	Issue B	13 May 2020
DA30	Elevations E & W – Section BB – Streetscape &	RM Designers	Issue B	13 May 2020

	Fence Elevation			
DA31	Elevations S & N – Section AA	RM Designers	Issue B	13 May 2020
DA40	Finishes Schedule	RM Designers	Issue B	13 May 2020
DA60	Windows & Doors Schedule	RM Designers	Issue B	13 May 2020
S01	Stormwater Plan	MBC Engineering Pty Ltd	Rev A	27 March 2020

Reference Documentation affixed with Council's 'Development Consent' stamp relating to Development Consent No.DA2020/059:

Title / Description	Prepared by	Issue/Revision & Date	Date received by Council
Flood Impact Statement	Alpha Engineering & Development	Rev B	13 May 2020
BASIX Certificate	No. 1077043M	Issued on 19 February 2020	27 March 2020
Waste Management Plan	R. Moussawel	-	27 March 2020

In the event of any inconsistency, the conditions of this consent shall prevail.

(Reason: To ensure that the form of the development undertaken is in accordance with the determination of Council.)

3. **BUILDING HEIGHT - MAXIMUM RL TO BE COMPLIED WITH (GC)**

The height of the building measured from Australian Height Datum (AHD) must not exceed Relative Level (RL) 33.40AHD to the ridge of the building.

(Reason: To ensure the approved building height is complied with.)

4. **CONSTRUCTION HOURS (GC)**

No construction or any other work related activities shall be carried out on the site outside the hours of 7.00 am to 5.00 pm Mondays to Fridays and 8am to 1pm Saturdays.

No building activities are to be carried out at any time on a Sunday or public holiday.

Where the development involves the use of jackhammers/rock breakers and the like or other heavy machinery, such equipment may only be used between the hours of 7.00 am - 5.00 pm Monday to Friday only.

(Reason: To maintain amenity to adjoining land owners.)

5. **CONSTRUCTION WITHIN BOUNDARIES (GC)**

The development including but not limited to footings, walls, roof barges and guttering must be constructed wholly within the boundary of the premises. No portion of the proposed structure shall encroach onto the adjoining properties. Gates must be installed so they do not open onto any footpath or adjoining land.

(Reason: Approved works are to be contained wholly within the subject site.)

6. DEMOLITION – GENERALLY (GC)

Alteration and demolition of the existing building is limited to that documented on the approved plans (by way of notation). No approval is given or implied for removal and/or rebuilding of any portion of the existing building which is not shown to be altered or demolished.

(Reason: To ensure compliance with the approved development.)

7. DEMOLITION - SITE SAFETY FENCING (GC)

Site fencing is to be erected to a minimum height of 1.8m complying with WorkCover Guidelines, to exclude public access to the site, prior to any demolition works occurring and maintained for the duration of the demolition works.

If applicable, a separate Hoarding Application for the erection of an A class (fence type) or B class (overhead type) hoarding/fencing along the street frontage(s) complying with WorkCover requirements must be obtained including:

- payment to Council of a footpath occupancy fee based on the area of footpath to be occupied and Council's Schedule of Fees and Charges before the commencement of work; and
- provision of a Public Risk Insurance Policy with a minimum cover of \$10 million in relation to the occupation of and works within Council's road reserve, for the full duration of the proposed works, must be obtained with a copy provided to Council.

(Reasons: Statutory requirement and health and safety.)

8. LANDSCAPING - CANOPY TREES IN REAR SETBACK (GC)

At least one (1) canopy tree shall be provided in the rear setback for each dwelling. New canopy trees shall be at least three (3) metres high at the time of planting and capable of reaching a mature height of 10m.

Species shall be selected from Council's Recommended Tree List (Available from Council's website or from the Customer Service Centre). Compliance with this condition is to be demonstrated to the Principal Certifying Authority, prior to the issue of any Occupation Certificate.

(Reason: To ensure the landscape character of the locality is maintained.)

9. ENVIRONMENTAL PROTECTION – TREE (GC)

All street trees and trees on private property that are protected under Council's controls, shall be retained except where Council's prior written consent has been obtained. The felling, lopping, topping, ringbarking, wilful destruction or removal of any tree/s unless in conformity with this approval or subsequent approval is prohibited.

All healthy trees and shrubs identified for retention on the approved drawings are to be suitably protected in accordance with Section 4, Tree protection measures, and Appendix C Tree Protection Zone Sign, of Australian Standard AS4970 - 2009, Protection of Trees on Development Sites, prior to the commencement of any works (including any demolition and excavation) and maintained for the duration of the works.

In this regard the street tree and all protected trees on or adjacent to the site will be protected as described below;

- i. A Tree Protection (Management) Plan prepared by a AQF Level 5 Arborist is to be available on site at all times prior to the issue of the Constriction Certificate, for all demolition and site works. This Tree Protection (Management) Plan must be shown on the demand of Authorised Council staff.
- ii. Protective perimeter fencing must be consistent with AS 4687, using metal fence posts greater than 20mm diameter and solid or chain wire mesh 2 metres in height supported on concrete pads/feet at 2-2.5 metre spacing. Fencing placement should not be closer than 2.5 metres from the trunk of each protected tree, or at a distance as specified by the approved Tree Protection (Management) Plan and approved by Council's Tree Management Officer. Shade cloth is to be used to prevent entry of dust and contaminated liquids into the root protection area.
- iii. Signs must be placed on the Fencing. These signs must comply with AS1319. The signs must state the purpose of the fencing and the name and contact details of the builder and the appointed AQF Level 5 consultant arborist.
- iv. Root protection is to be provided in the form of mulching to a depth of 50-100mm, inside of the fenced tree protection zone.
- v. Ground (Root) Trunk and Branch Protection must comply with the diagram of Figure 4 of AS4970 – 2009. Ground protection within the tree protection zone and drip line should be in the form of heavy steel plates or timber rumble boards over mulch or aggregate. Trunk and branch protection should be to a minimum height of 2 metres and must include measures to protect the tree/s against damage from the movement of trucks, plant equipment and materials at greater heights above ground level.
- vi. Temporary signs, cables, wires must not be attached to, or suspended, on any street tree or protected tree.
- vii. Above ground utilities must not be placed within the canopy of an existing protected tree, or create the future need for clearance pruning.
- viii. Below ground utilities/services must not be located inside the fenced tree protection zone.
- ix. Scaffolding must not be located in the fenced tree protection zone unless authorised by the approved Tree Protection (Management) Plan and Council's Tree Management Officer
- x. Council must be notified in writing within 24 hours, for all temporary removal of the tree protection fencing ground (root) trunk and branch protection within the root protection area.
- xi. Pruning of a street tree is prohibited without the written consent of Council.

(Reason: To ensure the protection of trees to be retained on the site.)

10. **MATERIALS – CONSISTENT WITH SUBMITTED SCHEDULE (GC)**

All external materials, finishes and colours are to be consistent with the schedule submitted and approved by Council with the development application.

(Reason: To ensure compliance with this consent.)

11. **PRINCIPAL CERTIFYING AUTHORITY (PCA) IDENTIFICATION SIGN (GC)**

Prior to commencement of any work, signage must be erected in a prominent position on the work site identifying:

- i) The Principal Certifying Authority (PCA) by showing the name, address and telephone number of the PCA;
- ii) The Principal Contractor by showing the Principal Contractor's name, address and

- telephone number (outside of work hours) for that person; and
- iii) The sign must state that unauthorised entry to the work site is prohibited.

Any such sign is to be maintained while the work is being carried out, but must be removed when the work has been completed.

This clause does not apply to building work, subdivision work or demolition work that is carried out inside an existing building that does not affect the external walls of the building.

(Reason: Statutory requirement.)

12. **SITE MANAGEMENT (DURING DEMOLITION AND CONSTRUCTION WORKS)**

All of the following are to be satisfied/complied with during demolition, construction and any other site works:

- i) All demolition is to be carried out in accordance with Australian Standard AS 2601-2001.
- ii) Demolition must be carried out by a registered demolition contractor.
- iii) A single entrance is permitted to service the site for demolition and construction. Protection pads are to be installed to the kerb, gutter and nature strip where trucks and vehicles enter the site.
- iv) No blasting is to be carried out at any time during construction of the building.
- v) Care must be taken during demolition/ excavation/ building/ construction to prevent any damage to adjoining buildings.
- vi) Adjoining owner property rights and the need for owner's permission must be observed at all times, including the entering onto land for the purpose of undertaking works.
- vii) Any demolition and excess construction materials are to be recycled wherever practicable.
- viii) The disposal of construction and demolition waste must be in accordance with the requirements of the Protection of the Environment Operations Act 1997.
- ix) All waste on the site is to be stored, handled and disposed of in such a manner as to not create air pollution (including odour), offensive noise or pollution of land and/or water as defined by the Protection of the Environment Operations Act 1997. All excavated material should be removed from the site in an approved manner and be disposed of lawfully to a tip or other authorised disposal area.
- x) All waste must be contained entirely within the site.
- xi) A site plan including temporary waste storage locations, construction material storage areas and vehicular access to and from the site must be included with application.
- xii) Section 143 of the Protection of the Environment Operations Act 1997 requires waste to be transported to a place which can lawfully accept it. All non-recyclable demolition materials are to be disposed of at an approved waste disposal depot in accordance with legislation.
- xiii) Details as to the method and location of disposal of demolition materials (weight dockets, receipts, etc.) should be kept on site as evidence of approved methods of disposal or recycling and must be presented to Council and/or Principal Certifying Authority upon request.
- xiv) All materials on site or being delivered to the site are to generally be contained within the site. The requirements of the Protection of the Environment Operations Act 1997 must be complied with when placing/stockpiling loose material, disposing of concrete waste, or other activities likely to pollute drains or water courses.
- xv) Any materials stored on site must be stored out of view or in such a manner so as not to cause unsightliness when viewed from nearby lands or roadways.
- xvi) Public footways, include nature strips and roadways adjacent to the site must be

- maintained and cleared of obstructions during construction. No building materials, waste containers or skips may be stored on the road reserve or footpath without prior separate approval from Council, including payment of relevant fees.
- xvii) Building operations such as brick-cutting, washing tools or paint brushes, and mixing mortar not be performed on the roadway or public footway or any other locations which could lead to the discharge of materials into the stormwater drainage system.
 - xviii) All site waters during excavation and construction must be contained on site in an approved manner to avoid pollutants entering into waterways or Council's stormwater drainage system.
 - xix) Any work must not prohibit or divert any natural overland flow of water.
 - xx) Toilet facilities for employees must be provided in accordance with WorkCover NSW.

(Reason: To ensure that demolition, building and any other site works are undertaken in accordance with relevant legislation and policy and in a manner which will be non-disruptive to the local area.)

13. **STORMWATER MANAGEMENT PLAN - CERTIFICATION REQUIREMENT (GC)**

A detailed Stormwater Management Plan (SWMP) in line with Council's Stormwater Management Code is to be prepared and certified by an Accredited Civil/Hydraulic Engineer and submitted to the Principal Certifying Authority and Council, prior to the issue of a Construction Certificate. The SWMP is to be based on the approved development as modified by any conditions of consent.

(Reason: To ensure appropriate provision is made for the disposal and management of stormwater generated by the development, and to ensure public infrastructure in Council's care and control is not overloaded.)

14. **SYDNEY WATER - TAP IN™ (GC)**

The approved plans must be submitted to a Sydney Water Tap in™ to determine whether the development application will affect Sydney Water's sewer and water mains, stormwater drains and/or easements, and if further requirements need to be met. The approved plans will be appropriately endorsed. For details please refer to 'Plumbing, building and developing' section of Sydney Water's web site at www.sydneywater.com.au then see 'Building', or telephone 13000 TAP IN (1300 082 746). The Certifying Authority must ensure that a Tap in™ agent has appropriately stamped the plans prior to the issue of the Construction Certificate.

(Reason: Compliance with Sydney Water requirements.)

CONDITIONS TO BE SATISFIED PRIOR TO THE ISSUE OF A CONSTRUCTION CERTIFICATE (PCC)

15. **BASIX COMMITMENTS (CC)**

The approved BASIX Certificate shall be submitted to the Principal Certifying Authority with the application for a Construction Certificate.

Where a change or changes are proposed in the BASIX commitments, the applicant must submit a new BASIX Certificate to the Principal Certifying Authority and Council. If any proposed change in the BASIX commitments is inconsistent with the development consent the applicant will be required to submit a modification to the development consent to Council under Section 4.55 of the Environmental Planning and Assessment Act 1979.

All commitments in the BASIX Certificate must be shown on the plans accompanying the Construction Certificate.

(Reason: Statutory compliance.)

16. BUILDING CODE OF AUSTRALIA - COMPLIANCE WITH (CC)

All architectural drawings, specifications and related documentation shall comply with the Building Code of Australia (BCA). All work must be carried out in accordance with the requirements of the Building Code of Australia (BCA).

In the case of residential building work for which the Home Building Act 1989 requires there to be a contract of insurance in force in accordance with Part 6 of that Act, such a contract of insurance is to be in force before any building work authorised to be carried out by the consent commences.

Details demonstrating compliance with this condition are to be submitted to the Principle Certifying Authority, prior to issue of the Construction Certificate.

(Reason: This is a 'prescribed' condition under clause 98(1) of the Environmental Planning and Assessment Regulation 2000.)

17. CAR PARKING - COMPLIANCE WITH AS/NZS 2890.1:2004 (CC)

Car parking dimensions must comply with the Australian/New Zealand Standard AS/NZS 2890.1:2004 - Parking facilities - Off-street car parking. Details demonstrating compliance are to be submitted to the Principal Certifying Authority, prior to the issue of a Construction Certificate.

(Reason: To ensure compliance with Australian Standards relating to parking of vehicles.)

18. CAR PARKING - VEHICULAR CROSSING WIDTH AT PROPERTY BOUNDARY (CC)

Vehicular crossings are to have a maximum width of 3m at the property boundary. Details demonstrating compliance are to be submitted to the Principal Certifying Authority, prior to the issue of a Construction Certificate.

The vehicular crossing (and all associated excavation works) must not be constructed closer than 2 metres from a retained protected street tree.

(Reason: Compliance with SCDCP 2005.)

19. COMMENCEMENT OF WORKS (NO WORKS UNTIL A CC IS OBTAINED)

Building work, demolition or excavation must not be carried out until a Construction Certificate has been issued by either Strathfield Council or a Principal Certifying Authority.

Demolition of any part of a building triggers 'commencement of erection of building' pursuant of section 4.19 of the EP&A Act 1979. Accordingly, demolition works must not commence until a Construction Certificate has been issued, a Principal Certifying Authority has been appointed and a Notice of Commencement has been issued.

(Reason: To ensure compliance with statutory provisions.)

20. COUNCIL PERMITS – FOR ALL ACTIVITIES ON COUNCIL LAND (CC)Works Permit

(as per Section 68 of the Local Government Act 1993 and Section 138 and 139 of the Roads Act 1993)

A Works Permit is required for construction of a vehicular crossing (driveway), new stormwater down pipe connection to kerb and gutter, new footpath and/or stormwater connection. A Works Permit Application Form is available from Council's Customer Centre or can be downloaded from Council's website. The applicable fees and charges are located on Council's website.

Standing Plant Permit

This permit must be applied for where it is intended to park a concrete pump, crane or other plant on the roadway or footpath. A Standing Plant Permit Application Form is available from Council's Customer Centre or can be downloaded from Council's website. The applicable fees and charges are located on Council's website. Please note a Road Closure Permit is not required for standing plant.

Skip Bin Permit

This permit must be applied for if you intend to place a skip bin on the roadway or footpath. A Skip Bin Application Form is available from Council's Customer Centre or can be downloaded from Council's website. The applicable fees and charges are located on Council's website.

Temporary Full or Part Road Closure Permit

This permit must be applied for if you require a full or a part road closure to take place to assist in your construction works. Please use the Works Permit Application Form, which is available from Council's Customer Service Centre or can be downloaded from Council's website. The applicable fees and charges are located on Council's website. Please note a Road Closure Permit is not required for standing plant.

Hoarding/Fencing Permit

This permit must be applied for if you intend to erect a Class A (fence type) or Class B (overhead type) hoarding/fencing along the street frontage(s). A Hoarding Permit Application Form is available from Council's Customer Service Centre or can be downloaded from Council's website. The applicable fees and charges are located on Council's website.

Work Zone Permit

This permit must be applied for if you require permanent parking along the kerbside at the front of the site during construction works. A Work Zone Permit Application Form is available from Council's Customer Service Centre or can be downloaded from Council's website. The applicable fees and charges are located on Council's website.

Ground Anchoring Permit

This permit must be applied for, for the installation of ground anchors under Council's footway/road reserve. It does not cover ground anchors under private properties. A separate approval is required to be obtained from Roads and Maritime Services (RMS) if it is proposed to install ground anchors under a State or Classified Regional Road (please refer to the end of this application form for more information).

(Reason: Council requirement.)

21. EROSION AND SEDIMENTATION CONTROL PLAN (CC)

The submitted Erosion and Sediment Control shall be complied with for the duration of demolition and development works and the following measures:

- i) Removal or disturbance of vegetation and top soil is confined to within 3m of the approved building area (no trees to be removed without approval).
- ii) All uncontaminated run-off is diverted around cleared or disturbed areas.
- iii) Silt fences or other devices are installed to prevent sediment and other debris escaping from the cleared or disturbed areas into drainage systems or waterways.
- iv) Controls are put into place to prevent tracking of sediment by vehicles onto adjoining roadways.
- v) All disturbed areas are rendered erosion-resistant by turfing, mulching, paving or similar.
- vi) All water pumped or otherwise removed from excavations is filtered to achieve suspended solids/non filterable residue levels complying with the Australian Water Quality guidelines for Fresh and Marine Waters.
- vii) Pumped or overland flows of water are discharged so as not to cause, permit or allow erosion before the commencement of work (and until issue of the occupation certificate).

Details of the proposed soil erosion and sedimentation controls are to be submitted to the Principal Certifying Authority with the Construction Certificate Application. Under no circumstances are any works to commence, prior to these details being approved by the Principal Certifying Authority and the controls being in place on the site.

(Reason: Environmental protection.)

22. FEES - ADDITIONAL DEVELOPMENT APPLICATION FEES (CC)

In accordance with Regulation 50(1)(c) and the table to Regulation 246 of the Environmental Planning and Assessment Act Council must charge a development application fee based on the estimated cost of works applied for.

The construction costs of the approved development are estimated at \$792,000 and the applicable Development Application Fee on this amount would be \$2,223.88 which includes a Planning Reform Fee of \$506.88. As a Development Application fee of \$2,155.00 was paid when lodging the application, the difference of \$68.88 shall be paid to Council prior to the issue of a Construction Certificate.

(Reason: Statutory requirement.)

23. FLOODING - COMPLY WITH FLOOD IMPACT REPORT (CC)

The applicant shall comply with the flood recommendations provided in the Flood Impact Report prepared by Alpha Engineering and Development Rev B dated 13 May 2020. A certificate from a suitably qualified Engineer shall be submitted to the Certifying Authority stating compliance with these recommendations, prior to the issue of a Construction Certificate.

(Reason: To mitigate flood risk and associated damage.)

24. PRIVACY - OBSCURE GLAZING IN WET AREAS (CC)

All bathroom, ensuite and toilet windows shall be installed with obscure glazing. Plans shall be notated accordingly and details demonstrating compliance submitted to the Principal

Certifying Authority, prior to the issue of a Construction Certificate.

(Reason: Privacy amenity.)

25. **SECTION 7.11 CONTRIBUTION PAYMENT - DIRECT CONTRIBUTIONS PLAN (CC)**

In accordance with the provisions of Section 7.13 of the Environmental Planning and Assessment Act 1979 and the Strathfield Direct Development Contributions Plan 2010-2030, a contribution in the form of cash, cheque or credit card (financial transaction fee applies) shall be paid to Council for the following purposes:

Provision of Community Facilities	\$3,013.35
Provision of Major Open Space	\$13,709.85
Provision of Local Open Space	\$ 3,016.96
Provision Roads and Traffic Management	\$ 0.00
Administration	\$ 259.83
TOTAL	\$20,000.00

The total amount of the contribution is valid as at the date of determination and is subject to quarterly indexation. Contributions shall be indexed at the time of payment in accordance with clause 2.14 of the Strathfield Direct Development Contributions Plan 2010-2030.

Contributions must be receipted by Council and submitted to the Accredited Certifier, prior to the issue of any Construction Certificate.

Please present a copy of this condition when paying the contribution at the Customer Service Centre so that it can be recalculated.

Note: A copy of Strathfield Council's Section 7.11 Direct Development Contributions Plan may be downloaded from Council's website.

(Reason: To enable the provision of public amenities and services required/anticipated as a consequence of increased demand resulting from the development.)

26. **STORMWATER - RAINWATER RE-USE (CC)**

A rainwater re-use system shall be provided in accordance with either the BASIX minimum requirements, any relevant Council Rainwater Policy and/or specification of the management of stormwater, whichever is applicable. A detailed stormwater plan showing the proposed re-use system shall be submitted to and approved by the Principal Certifying Authority, prior to the issue of a Construction Certificate.

(Reason: Compliance and amenity.)

27. **STORMWATER DRAINAGE (CC)**

The following stormwater precautions are required to be provided on the site:

- i) Grated drains shall be provided along the driveway/basement entry at the vehicular crossing(s) and are to connect to the internal drainage system.
- ii) Overflow paths shall be provided to allow for flows in excess of the capacity of the pipe/drainage system draining the site.
- iii) Allowance shall be made for surface runoff from adjacent properties, and to retain existing surface flow path systems through the site. Any redirection or treatment of these flows shall not adversely affect any other properties
- iv) Boundary fencing shall be erected in such a manner as not to interfere with the

natural flow of ground and surface water to the detriment of any other party.

(Reason: To ensure the site is drained appropriately and does not interfere with the natural flow of flood waters.)

28. TREE BONDS (CC)

A tree bond of **\$10,000** (calculated in accordance with Council's adopted Fees and Charges) shall be paid to Council, prior to the issue of a Construction Certificate.

The deposit is required as security against any damage to existing trees to be retained on Council's road reserve, during works on the site. The applicant must bear the cost of all restoration works to Council's property damaged during the course of this development.

Payment may be accepted in the form of cash, bank guarantee, cheque or credit card (financial transactions fees apply). Note: Additional fees apply for the lodgement of a bank guarantee in lieu of cash bond applies in accordance with Council's adopted Fees and Charges.

A refund of the Tree Bond must be made in writing.

Tree Bonds may be forfeited if a tree is dead, made dangerous or has been terminally damaged, or will be held until tree/s have fully recovered from the construction damage or were replacement/planted trees have become fully established and are over 6 metres in height.

(Reason: To ensure the protection of trees to be retained on Council's Road Reserve.)

29. SECURITY PAYMENT – DAMAGE DEPOSIT FOR COUNCIL INFRASTRUCTURE (CC)

A security (damage deposit) of \$12,200.00 (calculated in accordance with Council's adopted Fees and Charges) shall be paid to Council, prior to the issue of a Construction Certificate.

The deposit is required as security against any damage to Council property during works on the site. The applicant must bear the cost of all restoration works to Council's property damaged during the course of this development. All building work must be carried out in accordance with the Building Code of Australia.

Payment may be accepted in the form of cash, bank guarantee, cheque or credit card (financial transactions fees apply). Note: Additional fees apply for the lodgement of a bank guarantee in lieu of cash bond applies in accordance with Council's adopted Fees and Charges.

Any costs associated with works necessary to be carried out to rectify any damages caused by the development, shall be deducted from the Damage Deposit.

Note: Should Council property adjoining the site be defective e.g. cracked footpath, broken kerb etc., this should be reported in writing, or by photographic record, submitted to Council at least seven (7) days prior to the commencement of any work on site. This documentation will be used to resolve any dispute over damage to infrastructure. It is in the applicant's interest for it to be as full and detailed as possible.

The damage deposit shall be refunded upon completion of all works upon receipt of a Final Occupation Certificate stage and inspection by Council.

(Reason: Protection of Council infrastructure.)

30. VEHICULAR CROSSINGS - WORKS PERMIT FOR CONSTRUCTION OF (CC)

Full-width, heavy-duty concrete vehicular crossing(s) shall be provided across the footpath at the entrance(s) and/or exit(s) to the site and designed in accordance with Council's guidelines and specifications. In this regard, a Works Permit is to be obtained (available from Council's Customer Services Centre or downloaded from Council's website), and the appropriate fees and charges paid, prior to the lodgement of a Construction Certificate.

(Reason: To ensure appropriate access to the site can be achieved.)

31. WATER SUSTAINABILITY – GENERALLY (CC)

Water collected in the rainwater tank must comprise roof water only and not surface water. Water from the rainwater tank must only be used for following purposes and not for human consumption:

- i) Toilet flushing;
- ii) Clothes washing;
- iii) Garden irrigation;
- iv) Car washing and similar outdoor uses;
- v) Filling swimming pools, spa pools and ornamental ponds; and
- vi) Fire fighting.

(Reason: To promote sustainable water management practice.)

32. WATER HEATING SYSTEMS - LOCATION OF (CC)

Water heating systems shall be located so as not to be visible from public places and the ground level of adjoining properties. Details (type and location) of the water heaters shall be submitted to and approved by the Principal Certifying Authority, prior to the issue of a Construction Certificate.

(Reason: To maintain streetscape character.)

CONDITIONS TO BE SATISFIED PRIOR TO THE COMMENCEMENT OF WORKS (PCW)

33. APPOINTMENT OF A PRINCIPAL CERTIFYING AUTHORITY (PCA) (CW)

No work shall commence in connection with this Development Consent until:

- i) A construction certificate for the building work has been issued by the consent authority or a Principal Certifying Authority.
- ii) The person having the benefit of the development consent has appointed a principal certifying authority for the building work, and notified the principal certifying authority that the person will carry out the building work as an owner/builder, if that is the case.
- iii) The principal certifying authority has, no later than 2 days before the building work commences:
 - notified the Council of his or her appointment, and
 - notified the person having the benefit of the development consent of any critical stage inspections and other inspections that are to be carried out in respect of the building work.
- iv) The person having the benefit of the development consent, if not carrying out the

work as an owner-builder, has:

- appointed a principal contractor for the building work who must be the holder of a contractor licence if any residential building work is involved;
 - notified the principal certifying authority of such appointment; and
 - unless that person is the principal contractor, notified the principal contractor of any critical stage inspections and other inspections that are to be carried out in respect of the building work.
- v) The person having the benefit of the development consent has given at least 2 days' notice to the Council of the person's intention to commence the erection of the building.

Note: If the principal certifying authority is the Council, the nomination will be subject to the payment of a fee for the service to cover the cost of undertaking all necessary inspections and the issue of the appropriate certificates.

Under the Environment Planning and Assessment (Quality of Construction) Act, 2003, a sign must be erected in a prominent position on the work site showing the name, address and telephone number of the principal certifying authority; the name of the principal contractor (if any) for the building work and a telephone number at which that person may be contacted outside working hours. That sign must also state that unauthorised entry is prohibited. The sign must not be removed until all work has been completed.

(Reason: Statutory requirement.)

34. **HOME BUILDING COMPENSATION FUND (CW)**

No residential building work within the meaning of the Home Building Act 1989 may commence until:

- i) A contract of insurance in accordance with Part 6 of the Home Building Act 1989 is entered into and in force, where such a contract is required under that Act (this is a prescribed condition of consent pursuant to clause 981(b) Environmental Planning and Assessment Regulation 2000.
- ii) The PCA is satisfied that the principal contractor for the work is the holder of the appropriate licence and is covered by the appropriate insurance, in each case if required by the Home Building Act 1989 (unless the work is to be carried out by an owner-builder).
- iii) If the work is to be carried out by an owner builder, that the owner builder is the holder of any owner -builder permit required under the Home Building Act 1989.
- iv) Written notice of the following information has been provided to Council (this is a prescribed condition of consent pursuant to clause 98B of the Environmental Planning and Assessment Regulation 2000):
 - In the case of work for which a principal contractor is required to be appointed:
 - the name and licence number of the principal contractor; and
 - the name of the insurer by which the work is insured under Part 6 of the Home Building Act 1989.
 - In the case of work to be done by an owner-builder:
 - the name of the owner-builder; and
 - if the owner-builder is required to hold an owner-builder permit under the Home Building Act 1989, the number of the owner-builder permits.

Where Council is not the PCA, the PCA is responsible for notifying Council of the above matters.

Note: Where arrangements for doing residential building work change while the work is in

progress so that the above information becomes out of date, the PCA (where not the Council) must provide Council with written notice of the updated information.

(Reason: Statutory requirement.)

35. NOTICE OF COMMENCEMENT (CW)

No work shall commence until the following details are submitted to Council:

- i) a Notice of Commencement (form will be attached with issue of a Construction Certificate or available from our website) within two (2) days of the date on which it is proposed to commence works associated with the Development Consent;
- ii) details of the appointment of a Principal Certifying Authority (either Council or another Principal Certifying Authority); and
- iii) details of the name, address and licence details of the Builder.

(Reason: Statutory requirement.)

CONDITIONS TO BE SATISFIED DURING DEMOLITION AND BUILDING WORKS (DBW)

36. FILL MATERIAL (DW)

The only waste derived material which may be received at the development site is:

- i) Virgin excavated material (within the meaning of the Protection of the Environment Operations Act 1997), and
- ii) any other waste-derived material the subject of a resource recovery exemption under cl.51A of the Protection of the Environment Operations (Waste) Regulation 2005 that is permitted to be used as fill material.

Any (b)-type material received at the development site must be accompanied by documentation certifying by an appropriately qualified environmental consultant the materials compliance with the exemption conditions; and this documentation must be provided to the Principal Certifying Authority on request.

(Reason: To ensure imported fill is of an acceptable standard for environmental protection purposes.)

37. OBSTRUCTION OF PUBLIC WAY NOT PERMITTED DURING WORKS (DW)

The public way must not be obstructed by any materials, vehicles, refuse, skips or the like, under any circumstances, without the prior approval of Council.

(Reason: To maintain public access and safety.)

38. PUBLIC INFRASTRUCTURE AND SERVICES (DW)

The applicant must comply with the requirements (including financial costs) of any relevant utility provider (e.g. Energy Australia, Sydney Water, Telstra, RMS, Council etc.) in relation to any connections, works, repairs, relocation, replacements and/or adjustments to public infrastructure or services affected by the development.

(Reason: To maintain public infrastructure and/or services.)

39. SURVEY REPORT OF APPROVED LEVELS DURING AND POST CONSTRUCTION (DW)

A Survey Certificate to Australian Height Datum shall be prepared by a Registered Surveyor as follows:

- i) At the completion of the first structural floor level prior to the pouring of concrete indicating the level of that floor and the relationship of the building to the boundaries.
- ii) At the completed height of the building, prior to the placement of concrete inform work, or the laying of roofing materials.
- iii) At the completion of the development.

Progress certificates in response to points (1) through to (3) shall be provided to the Principal Certifying Authority at the time of carrying out relevant progress inspections. Under no circumstances is work allowed to proceed until such survey information is submitted to and approved by the Principal Certifying Authority.

(Reason: To ensure compliance with the approved plans.)

CONDITIONS TO BE SATISFIED PRIOR TO THE ISSUE OF AN OCCUPATION CERTIFICATE (POC)**40. ATTACHED DWELLINGS - CROSS EASEMENT FOR SUPPORT (OC)**

A cross easement for support must be registered with Land and Property Information (LPI) NSW, prior to the issue of a Final Occupation Certificate.

(Reason: To protect the rights of residents of both dwellings and long term structural integrity of the party wall between the dwellings.)

41. DRAINAGE SYSTEM - MAINTENANCE OF EXISTING SYSTEM (OC)

Where elements of the existing drainage system are to be utilised, the existing drainage system shall be overhauled and maintained clear of silt and accumulated debris. Silt and the like shall be removed, not flushed from the system.

A certificate shall be provided by a suitably qualified person (a registered plumber or a person of equivalent or greater experience or qualification) to the satisfaction of the Principal Certifying Authority, prior to the issue of any Occupation Certificate to confirm that the system is in good working order and adequate to accept additional flows having regard to any relevant standards and/or Sydney Water requirements.

(Reason: Maintenance and environment.)

42. ENGINEERING WORKS (CERTIFICATION OF)

Prior to occupation of the premises, a Work As Executed (WAE) Plan of all engineering and/or drainage works is to be submitted to the Principal Certifying Authority. The WAE Plan is to be certified by an Accredited Civil/Hydraulic Engineer demonstrating that:

- i) The stormwater drainage system; and/or
- ii) The car parking arrangement and area; and/or
- iii) Any related footpath crossing works; and/or
- iv) The proposed basement pump and well system; and/or
- v) The proposed driveway and layback; and/or
- vi) Any other civil works

have been constructed in accordance with the approved plans and any relevant Standards and Council policies/specifications.

For major works, such as subdivisions, works within the road reserve (requiring separate S138 approval) and as where specified by Council, a Part 4A Certificate will be required. It is strongly recommended that an Engineer supervise all engineering related works.

Where Council is not the Principal Certifying Authority, an electronic copy of the above documents is to be provided to Council, prior to the issue of any Occupation Certificate.

(Reason: Asset management.)

43. OCCUPATION OF BUILDING (OC)

A person must not commence occupation or use (or change of use where an existing building) of the whole or any part of a new building (within the meaning of section 109H (4) of the Act) unless an Interim Occupation Certificate or Final Occupation Certificate has been issued in relation to the building or part.

The Principal Certifying Authority is required to be satisfied, amongst other things, that:

- i) All required inspections (including each applicable mandatory critical stage inspection) have been carried out; and
- ii) Any preconditions to the issue of the certificate required by a development consent have been met.

Note: New building includes an altered portion of, or an extension to, an existing building.

(Reason: Statutory requirement.)

44. RAINWATER TANKS (OC)

Rainwater tanks must be installed on residential properties by a suitably qualified and licensed plumber and in accordance with the following:

- i) Australian/New Zealand Standard AS/NZS 3500:2003;
- ii) NSW Code of Practice Plumbing and Drainage, 2006 produced by Committee on Uniformity of Plumbing and Drainage Regulations in NSW (CUPDR); and
- iii) Council's rainwater tank policy.

Details demonstrating compliance with this condition are to be submitted to the Principal Certifying Authority, prior to the issue of any Occupation Certificate.

(Reason: To protect public health and amenity.)

45. STORMWATER - CERTIFICATION OF THE CONSTRUCTED DRAINAGE SYSTEM (OC)

The constructed stormwater system shall be certified by a suitably qualified person, in accordance with Council's Stormwater Management Code, prior to the issue of any Occupation Certificate.

(Reason: Adequate stormwater management.)

46. STORMWATER - COVENANT AND RESTRICTION AS TO USER FOR STORMWATER CONTROLLED SYSTEMS (OC)

Prior to the issue of any Occupation Certificate, the applicant shall register a Positive Covenant and a Restriction as to User under section 88E and or section 88B of the Conveyancing Act as appropriate in favour of Council, ensuring the ongoing retention, maintenance and operation of the stormwater facility (on-site detention, pump-out, charged lines, etc).

Where any drainage line or service conduit is to traverse any property other than that which it serves, an appropriate easement will be required. In this case, the applicant shall register an easement no less than 1200mm wide over the proposed drainage line or service concurrently with any subdivision registration.

The wording on the 88E and/or the 88B Instrument is to make reference to the Council file where the Construction plans and the Work As Executed (as built), plans are held. Typical wording can be obtained from Council's Specification for the Management of Stormwater document.

(Reason: To ensure the on-site detention and/or pump system is maintained to an appropriate operational standard.)

CONDITIONS TO BE SATISFIED PRIOR TO THE ISSUE OF A SUBDIVISION CERTIFICATE (PSC)

47. COMMENCEMENT OF SUBDIVISION WORKS - REQUIREMENTS PRIOR TO (SC)

Subdivision work in accordance with a consent must not commence until:

- i) A Construction Certificate has been issued;
- ii) The person having the benefit of the development consent has appointed the Principal Certifying Authority (PCA);
- iii) The PCA (if not Council) has, no later than two (2) days before the subdivision work commences, notified the Council (or other consent authority where applicable) of the PCA's appointment; and
- iv) The person having the benefit of the consent has given at least two (2) day's notice to the Council of the person's intention to commence the subdivision work.

NB: Crown work certified in accordance with s109R of the Environmental Planning and Assessment Act 1979 is exempted from the above requirements.

(Reason: Statutory requirements.)

48. ENGINEERING WORKS - CERTIFICATION OF WORK AS EXECUTED (SC)

Prior to the issue of the Subdivision Certificate, a Work As Executed (WAE) plan of all engineering and/or drainage works is to be submitted to the Principal Certifying Authority. The WAE Plan is to be certified by a suitably Qualified Engineer, with Corporate Membership standing in the Institution of Engineers Australia and registered on the National Professional Engineers Register (NPER) under the appropriate professional category, demonstrating that all engineering works including the provision of services, drainage, driveways and earthworks have been constructed in accordance with the approved plans and any relevant Standards and Council policies/specifications.

Where Council is not the Principal Certifying Authority, an electronic copy of the above documents is to be provided to Council.

(Reason: To ensure adequate access and services have been provided for the new lots.)

49. SUBDIVISION CERTIFICATE - REQUIREMENTS PRIOR TO THE ISSUE OF (SC)

A Subdivision Certificate allows a person to lodge a plan of subdivision with NSW Land registry Services (LRS). The plan of subdivision identifies each of the allotments approved under the original consent (if required) or each allotment subject to an exempt boundary adjustment. The plan of subdivision is required to be prepared by a registered surveyor.

All types of subdivision (Torrens, Strata and Community Title) are required to be registered with NSW LRS before a new 'allotment' of a subdivision of land can be created.

The release of a Subdivision Certificate confirms that the Certifier (Council or Accredited Certifier) is satisfied that works are completed in accordance with the applicable Development Consent and that the land is suitable to occupy.

Prior to the issuing of any Subdivision Certificate under Part 4 of the Strata Schemes Development Act 2015 and Part 4 of the Strata Schemes Development regulation 2016, the Certifier is required to be satisfied that:

- i) the floors, external walls and ceilings depicted in the plan correspond to those of the building as constructed; and
- ii) the floors, external walls and ceilings of the building as constructed correspond to those depicted in the building plans and specifications that accompanied the construction certificate for the building; and
- iii) any facilities required by the relevant development consent (such as parking spaces, terraces and courtyards) have been provided in accordance with those requirements.

As construction of the building nears completion, or after it has been completed, the Certifier must inspect the building and the common property areas around the building, so as to be satisfied, as required by Part 4 of the Strata Schemes Development Regulations 2016, that the above requirements have been met.

(Reason: Statutory requirements.)

50. SUBDIVISION - LODGEMENT OF FINAL PLAN OF SUBDIVISION (SC)

Once a Subdivision Certificate is issued by the Principal Certifying Authority, the Final Plan of Subdivision must be registered with NSW Land Registry Services (LRS). Documentary evidence that the final plan has been registered with Land Registry Services must be submitted to Strathfield Council as soon as practicable.

(Reason: Statutory requirement.)

51. SYDNEY WATER - SECTION 73 CERTIFICATE (SC)

A Section 73 Compliance Certificate under the Sydney Water Act 1994 must be obtained before the issue of the Subdivision Certificate. An application must be made through an authorised Water Servicing Coordinator (refer www.sydneywater.com.au).

Following receipt of the application a 'Notice of Requirements' will be issued detailing water and sewer extensions to be built and charges to be paid. Please make early contact with the Water Servicing Coordinator, as building of water/sewer extensions can be time consuming and may impact on other services and building, driveway or landscape design.

Sydney Water written advice that you have obtained the Notice of Requirements must be submitted to the Principal Certifying Authority.

The Section 73 Compliance Certificate must be submitted to the Principal Certifying Authority prior to release of the Subdivision Certificate/any occupation of the premises.

(Reason: To comply with the statutory requirements of Sydney Water.)

RESOLUTION

The application is **APPROVED** subject to the recommended conditions and deletion of Conditions 1, 40 and 47 as they do not directly relate to Strata Subdivision and that the requirements for Strata Plans is governed under separate Acts and Regulations.

FOR: S. Clements, K. Lindeberg, G. Andonoski

AGAINST: Nil

**** End Minutes - Report No. 2****

TO: Strathfield Internal Development Assessment Panel Meeting - 29 May 2020
REPORT: IDAP – Report No. 3
SUBJECT: DA2017/101/03 - 37-39 PUNCHBOWL ROAD & 90 WATER STREET, BELFIELD
LOT 5 DP 7675 & LOT 11 DP 592982
DA NO. DA2017/101/03

RECOMMENDATION

Pursuant to Section 4.55(1A) of the *Environmental Planning and Assessment Act 1979*, the proposed modifications to Development Consent No. 2017/101 to modify basement level one and ground floor at 37-39 Punchbowl Road & 90 Water Street, Belfield be **APPROVED**, subject to:

1. The original conditions of consent of Development Application No. (DA2017/101) as approved by SLPP for the demolition of all existing structures on the site, construction of eight (8) storeys mixed use development comprising of 61 residential apartments, 270m² of commercial/retail floor space at ground floor and three (3) storeys of basement car parking.
2. As modified by this Section 4.55(1A) Application (DA2017/101/03) as follows:
 - Modification of Condition No. 6 to reflect amended plans and waste management plan;
 - Modification of Condition No. 30 regarding basement car parking requirements;
 - Deletion of Condition No. 37 regarding width of driveway at property boundary;

Accordingly, Development Consent No. DA2017/101/03 is approved as following:

SPECIAL CONDITIONS (SC)

1. SILVER LEVEL UNIVERSAL DESIGN (SC)

A minimum (20%) apartments to the building shall achieve the Livable Housing Guideline's silver level universal design features as per Part 4Q of the Apartment Design Guide. Plans demonstrating compliance with this requirement shall be submitted and approved by a Private Certifying Authority **prior to the issue of a Construction Certificate.**

(Reason: Comply with the ADG)

2. BASEMENT PARKING (SC)

Amended plans shall be prepared and submitted to a Private Certifying Authority for approval demonstrating compliance with the following:

- A minimum one (1) surplus carparking space shall be allocated as an additional visitor parking space so as to achieve a minimum (13) spaces are required by the ADG;
- A minimum six (6) motorcycle spaces are to be provided in the basement;
- Where there are stacked parking spaces provided in the basement, they shall be allocated to the same unit and clearly indicated as part of any future strata subdivision of the site.

(Reason: Provide sufficient on-site parking for the site)

3. WATER NSW (SC)

- A Water Supply Work Approval from WaterNSW must be obtained prior to commencing dewatering activity on the proposed site. Please complete an Application for approval for water supply works, and/or water use.

- An application for a Water Supply Works Approval will only be accepted upon receipt of supporting documentation, and payment of the applicable fee (see Application fees for New or amended Works and/or Use Approvals). The information required for the processing of the water supply work application may include preparation of a dewatering management plan.
- If approved, the Approval will be issued for a period of up to 24 months to cover the dewatering requirements during the construction phase. It will include conditions to ensure that impacts are acceptable and that adequate monitoring and reporting procedures are carried out. The Approval will be issued subject to the proponent meeting requirements of other agencies and consent authorities. For example, an authorisation by either Sydney Water or the local Council, depending where the water will be discharged. If contaminants are likely, or are found to be present in groundwater, and are being discharged to stormwater, including high salinities, a discharge licence under the *Protection of the Environment Operations Act 1997 (NSW)* may also be required.
- WaterNSW prefers “tanking” (ie. total water proofing below the seasonal high water table) of basement excavations, and avoids the ongoing extraction of groundwater after the initial construction phase. It is also advised to adopt measures to facilitate movement of groundwater post construction (eg. a drainage blanket behind the water-proof membrane).
- If the basement is not “tanked”, the proponent will require a Water Access Licence (WAL) and need to acquire groundwater entitlements equivalent to the yearly ongoing take of groundwater. Please note: Acquiring groundwater entitlements could be difficult, and may cause delay in project completion. If a WAL is required, please complete an Application for a new water access licence with a zero share component.

(Reason: Compliance with Water NSW requirements)

4. **RMS (SC)**

- a. Any new buildings or structures (other than pedestrian footpath awnings), together with any improvements integral to the future use of the site, are erected clear of the land reserved for road widening (unlimited in height or depth). Furthermore, no substantial trees or trees with the potential to be substantial trees are to be planted in the area reserved for road widening.
- b. All vehicular access is to be provided from Water Street at the furthest possible extent from the traffic signals at Punchbowl Road and Water Street.
 - a.
- c. The layout of the proposed car parking areas associated with the subject development (including, driveways, grades, turn paths, sight distance requirements in relation to landscaping and/or fencing, aisle widths, aisle lengths, and parking bay dimensions) shall be in accordance with AS 2890.1-2004, A52890.6-2009 and AS 2890.2-2002 for heavy vehicle usage.
- d. Construction works zone will not be permitted on Punchbowl Road.

(Reason: compliance with RMS)

5. AUSGRID (SC)

Method of Electricity Connection

The method of connection will be in line with Ausgrid's Electrical Standard (ES)1 – 'Premise Connection Requirements'.

Supply of Electricity

It is recommended for the nominated electrical consultant/contractor to provide a preliminary enquiry to Ausgrid to obtain advice for the connection of the proposed development to the adjacent electricity network infrastructure. An assessment will be carried out based on the enquiry which may include whether or not:

- The existing network can support the expected electrical load of the development
- A substation may be required on-site, either a pad mount kiosk or chamber style and;
- site conditions or other issues that may impact on the method of supply.

Please direct the developer to Ausgrid's website, www.ausgrid.com.au about how to connect to Ausgrid's network.

Conduit Installation

The need for additional electricity conduits in the footway adjacent to the development will be assessed and documented in Ausgrid's Design Information, used to prepare the connection project design.

Vegetation

All proposed vegetation underneath overhead power lines and above underground cables must comply with the requirements of ISSC 3 Guideline For Managing Vegetation Near Power Lines.

Streetlighting

The developer is to consider the impact that existing streetlighting and any future replacement street lighting and maintenance may have on the development. Should the developer determine that any existing streetlighting may impact the development, the developer should either review the development design, particular the placement of windows, or discuss with Ausgrid the options for relocating the streetlighting. The relocating of any street lighting will generally be at the developers cost. In many cases is not possible to relocate streetlighting due to its strategic positioning.

Service Mains

It appears the existing overhead electricity service mains, that supply the subject property, may not have sufficient clearance to the proposed construction as per the requirements of "The Installation and Service Rules of NSW".

It is recommended that the developer engage a Level 2 Accredited Service Provider (ASP) Electrician to ensure that the installation will comply with the Service Rules.

Proximity to Existing Network Assets Overhead Powerlines

There are existing overhead electricity network assets in Water St & Punchbowl Rd.

Safework NSW Document – Work Near Overhead Powerlines: Code of Practice, outlines the minimum safety separation requirements between these mains/poles to structures within the development throughout the construction process. It is a statutory requirement that these distances be maintained throughout construction. Special consideration should be given to the positioning and operating of cranes and the location of any scaffolding.

The "as constructed" minimum clearances to the mains should also be considered. These distances are outlined in the Ausgrid Network Standard, NS220 Overhead Design Manual. This document can be sourced from Ausgrid's website, www.ausgrid.com.au

Before a Construction Certificate is issued, the developer will be required to submit a survey plan to Ausgrid showing the location of all overhead mains within 5 metres of the proposed development. This drawing must contain a plan view and an elevated view clearly indicating the location of the overhead mains in relation to the development. This information should be forwarded to email address at the top of this letter for further comment.

Should the existing overhead mains require relocating due to the minimum safety clearances being compromised in either of the above scenarios, this relocation work is generally at the developers cost.

It is also the responsibility of the developer to ensure that the existing overhead mains have sufficient clearance from all types of vehicles that are expected be entering and leaving the site.

Underground Cables

There are existing underground electricity network assets in Punchbowl Rd.

Special care should also be taken to ensure that driveways and any other construction activities within the footpath area do not interfere with the existing cables in the footpath. Ausgrid cannot guarantee the depth of cables due to possible changes in ground levels from previous activities after the cables were installed.

Hence it is recommended that the developer locate and record the depth of all known underground services prior to any excavation in the area.

Should ground anchors be required in the vicinity of the underground cables, the anchors must not be installed within 300mm of any cable, and the anchors must not pass over the top of any cable. Safework Australia – Excavation Code of Practice, and Ausgrid's Network Standard NS156 outlines the minimum requirements for working around Ausgrid's underground cables.

(Reason: Compliance with Ausgrid)

- 5A. Prior to the release of the Construction Certificate (CC) Council requires the site to be remediated and validated by an appropriately qualified land contamination consultant to the requirements of the NSW Environment Protection Authority and to the standard acceptable for residential development; and Council shall be furnished with a Site Audit Statement completed and signed by an accredited site auditor under the Contaminated Land Management Act, 1997 which clearly states that the land is suitable for the proposed residential development, without the need for any further remediation or testing.

GENERAL CONDITIONS (GC)

6. APPROVED PLANS AND REFERENCE DOCUMENTATION (GC)

The development, except where modified by a condition(s) of consent, is to be carried out in accordance with the following plans and reference documentation:

Plans affixed with Council's 'Development Consent' stamp relating to Development Consent No. 2017/101:

Drawing No.	Title/Description	Prepared by	Issue / Revision & Date	Date received by Council
DA-003	Site Roof and Demolition Plan	Zhinar Architects	C	30 November 2017
CC-100	Basement 3	Zhinar	1	5 April 2018

MINUTES

		Architects		
CC-101	Basement 2	Zhinar Architects	1	5 April 2018
CC-102 S4.55 102	Basement 1	Zhinar Architects	1	5 April 2018 17 April 2020 MODIFIED: DA 2017/101/03 – 29 May 2020
CC-103 S4.55 103	Ground Floor Plan	Zhinar Architects	1	10 May 2018 17 April 2020 MODIFIED: DA 2017/101/03 – 29 May 2020
DA-105	Typical Floor Plan L1-L3	Zhinar Architects	C	30 November 2017
DA-106	Floor Plan L4	Zhinar Architects	C	30 November 2017
DA-107	Floor Plan L5	Zhinar Architects	C	30 November 2017
DA-108 S4.55 109	Floor Plan L6	Zhinar Architects	C 1	30 November 2017 8 May 2020 MODIFIED: DA2017/101/03 29 May 2020
DA-109	Floor Plan L7	Zhinar Architects	C	30 November 2017
DA-201	West Elevation - Streetscape	Zhinar Architects	C	30 November 2017
DA-202 S4.55 114	East Elevation	Zhinar Architects	C 1	30 November 2017 8 May 2020 MODIFIED: DA2017/101/03 – 29 May 2020
DA-203	South Elevation - Streetscape	Zhinar Architects	C	30 November 2017
DA-204	North Elevation	Zhinar Architects	C	30 November 2017
CC 250	Section A-A	Zhinar Architects	1	5 April 2018
CC 251	Section B-B	Zhinar Architects	1	5 April 2018
CC 700	Entry Ramp Section	Zhinar Architects	1	5 April 2018
DA-301	Materials Schedule	Zhinar Architects	C	30 November 2017
Sheet 1 of 2	Landscape Site Plan	Paul Scrivener	C	30 November 2017
Sheet 2 of 2	Planting Plan/Calculations Plan	Paul Scrivener	C	30 November 2017
Sheets 1-7	Stormwater	Mance Arraj	A	30 November

MINUTES

SW001 – SW050	Plans	Civil and Structural Engineers		2017
Project No.17140	Turning Paths 180405	Varga Traffic Planning Pty Ltd	-	5 April 2018
Project No.17140	Turning Paths 180405	Varga Traffic Planning Pty Ltd	-	5 April 2018
Project No.17140	B99 Vehicle Turning Path Entering Loading Bay Area	Varga Traffic Planning Pty Ltd	-	10 May 2018
Project No.17140	Turning Paths 180405	Varga Traffic Planning Pty Ltd	-	5 April 2018

Reference Documentation affixed with Council's 'Development Consent' stamp relating to Development Consent No. 2017/101:

Title / Description	Prepared by	Issue/Revision & Date	Date received by Council
Statement of Environmental Effects	Caladines Town Planning	November 2017	30 November 2017
Access Report	Vista Access Architects		30 November 2017
Acoustic Report	Sebastian Giglio Acoustic Consultant	Ref: 2833/D05	30 November 2017
Arborist Report	Regum Horticultural	REF: 2812	30 November 2017
BASIX Certificate	-	Cert No: 829246M_03	30 November 2017
Phase 1 Contamination Assessment and Geotechnical Investigation Report	GeoEnviro Consultancy Pty Ltd	June 2017	30 November 2017
Phase 2 Contamination Assessment	GeoEnviro Consultancy Pty Ltd	October 2017	30 November 2017
On-Site Detention Calculation Sheet	Guiseppe Serratore	Job No.2293-C	30 November 2017
Stormwater Quality Management Plan	Mance Arraj	Revision A	4 July 2017
Traffic Report	Varga Traffic Planning Pty Ltd	Ref 17140	30 November 2017
Waste Management Plan	-		30 November 2017 21 May 2020 MODIFIED: DA2017/101/03 – 29 May 2020
Acid Sulphate Soil Repost	GeoEnviro Consultancy Pty Ltd	16 February 2018	16 February 2018

In the event of any inconsistency, the conditions of this consent shall prevail.

(Reason: To ensure that the form of the development undertaken is in accordance with the determination of Council.)

MODIFIED: DA2017/101/07 – 29 May 2020

7. APPROVAL - SEPARATE APPROVAL REQUIRED (GC)

This consent does not include approval for the fit out and use of the ground floor commercial tenancies on the site. Separate development consent shall be obtained for each of the commercial tenancies on the site.

(Reason: To control future development of the site.)

8. CONSTRUCTION HOURS (GC)

No construction or any other work related activities shall be carried out on the site outside the hours of 7.00 am to 5.00 pm Mondays to Fridays and 8am to 1pm Saturdays.

No building activities are to be carried out at any time on a Sunday or public holiday.

Where the development involves the use of jackhammers/ rock breakers and the like or other heavy machinery, such equipment may only be used between the hours of 7.00 am - 5.00 pm Monday to Friday only.

(Reason: To maintain amenity to adjoining land owners.)

9. CONSTRUCTION WITHIN BOUNDARIES (GC)

The development including but not limited to footings, walls, roof barges and guttering must be constructed wholly within the boundary of the premises. No portion of the proposed structure shall encroach onto the adjoining properties. Gates must be installed so they do not open onto any footpath or adjoining land.

(Reason: Approved works are to be contained wholly within the subject site.)

10. DEMOLITION – GENERALLY (GC)

Alteration and demolition of the existing building is limited to that documented on the approved plans (by way of notation). No approval is given or implied for removal and/or rebuilding of any portion of the existing building which is not shown to be altered or demolished.

(Reason: To ensure compliance with the approved development.)

11. DEMOLITION - SITE SAFETY FENCING (GC)

Site fencing is to be erected to a minimum height of 1.8m complying with WorkCover Guidelines, to exclude public access to the site, prior to any demolition works occurring and maintained for the duration of the demolition works.

If applicable, a separate Hoarding Application for the erection of an A class (fence type) or B class (overhead type) hoarding along the street frontage(s) complying with WorkCover requirements must be obtained including:

payment to Council of a footpath occupancy fee based on the area of footpath to be occupied and Council's Schedule of Fees and Charges before the commencement of work; and

provision of a Public Risk Insurance Policy with a minimum cover of \$10 million in relation to the occupation of and works within Council's road reserve, for the full duration of the proposed works, must be obtained with a copy provided to Council.

(Reasons: Statutory requirement and health and safety.)

12. LANDSCAPING - IRRIGATION OF COMMON AND PRIVATE LANDSCAPE AREAS (GC)

All common and private landscape areas including all planters of new multi-unit, commercial, mixed-use and industrial development are to have full coverage by a fully automatic irrigation system. The design, materials and installation are to be in accordance with Sydney Water Codes and satisfy all relevant Australian Standards. Details demonstrating compliance shall be submitted to the Principal Certifying Authority, prior occupation of the premises.

(Reason: To ensure appropriate landscape maintenance.)

13. LANDSCAPING - TREES PERMITTED TO BE REMOVED (GC)

The following listed trees are permitted to be removed to accommodate the proposed development:

<u>Tree</u>	<u>Height/ Spread (m)</u>	<u>Location</u>
3)Lophostemon confertus	6 x 5	Road reserve
4)Acacia fimbriata	5 x 4	Subject site
5)Jacaranda mimosifolia	8 x 7	Subject site
6)Callistemon viminalis	6 x 7	Subject site
8)Eucalyptus sp.	16 x 9	Subject site
9)Acacia decurrens	5 x 4	Subject site
10) Acacia decurrens	5 x 3	Subject site

- i) All trees permitted to be removed by this consent shall be replaced by species selected from Council's Recommended Tree List.

NOTE: Consent is given for the removal of the existing Tree 3 Lophostemon confertus street tree subject to the following:

- A minimum of one (1) replacement Lophostemon confertus shall be provided within Council's nature strip in Water St
- Trees are to conform to the *NATSPEC guide* and *Guide for assessing the quality of and purchasing of landscape trees* by Ross Clarke, 2003.
- Replacement trees shall be minimum 50 litre container size. Trees are to be true to type, healthy and vigorous at time of delivery and planting, shall be pest and disease free, free from injury and wounds and self-supporting. Supplied trees are to have an appropriate stem taper. Roots shall generally grow in an outwards (radial) or downwards direction.
- All trees are to be staked and tied with a minimum of three (3) hardwood stakes.

Ties are to be hessian and fixed firmly to the stakes, one tie at half the height of the main stem, others as necessary to stabilise the plant.

- (e) Root deflection barriers having a minimum depth of 600mm are to be installed adjacent to all footpaths and driveways.
- (f) Minimum 75mm depth of organic mulch shall be placed within an area 0.5m radius from the base of the tree.

ii) A minimum of 6 x 100 litre size additional trees, which have a minimum mature height of 6 metres shall be planted between the front of the building and the street frontage boundary. Trees are to conform to the *NATSPEC guide* and *Guide for assessing the quality of and purchasing of landscape trees* by Ross Clarke, 2003.

Replacement trees shall be a minimum 50 litre container size. Trees are to conform to the NATSPEC guide and *Guide for assessing the quality of and purchasing of landscape trees* by Ross Clarke, 2003. Trees are to be true to type, healthy and vigorous at time of delivery and planting, shall be pest and disease free, free from injury and wounds and self-supporting; and shall be maintained until maturity.

All trees are to be staked and tied with a minimum of three (3) hardwood stakes. Ties are to be hessian and fixed firmly to the stakes, one tie at half the height of the main stem, others as necessary to stabilise the plant.

Root deflection barriers having a minimum depth of 600mm are to be installed adjacent to all footpaths and driveways.

Soil conditioner/fertilizer/moisture retention additive/s are to be applied in accordance with manufacturer's recommendations, and mixed into the backfilling soil after planting tree/s.

A minimum 75mm depth of organic mulch shall be placed within an area 0.5m from the base of the tree.

Details demonstrating compliance shall be demonstrated to the Principal Certifying Authority, prior to the issue of any Occupation Certificate.

(Reason: To ensure appropriate planting back onto the site.)

14. **LANDSCAPING - TREE PRESERVATION (GC)**

All street trees and trees on private property that are protected under Council's controls, shall be retained except where Council's prior written consent has been obtained. The felling, lopping, topping, ringbarking, wilful destruction or removal of any tree/s unless in conformity with this approval or subsequent approval is prohibited.

All healthy trees and shrubs identified for retention on the approved drawings are to be suitably protected in accordance with Australian Standard AS4970 – Protection of Trees on Development prior to the commencement of any works (including any demolition and excavation) and maintained for the duration of the works.

(Reason: To ensure the protection of trees to be retained on the site.)

15. **LIGHTING (GC)**

Any lighting of the premises shall be installed and maintained in accordance with Australian Standard AS 4282-1997: Control of the Obtrusive Effects of Outdoor Lighting so as to avoid annoyance to the occupants of adjoining premises or glare to motorists on nearby roads.

No flashing, moving or intermittent lighting, visible from any public place may be installed on the premises or external signage associated with the development, without the prior approval of Council.

(Reason: To protect the amenity of surrounding development and protect public safety.)

16. MATERIALS – CONSISTENT WITH SUBMITTED SCHEDULE (GC)

All external materials, finishes and colours are to be consistent with the schedule submitted and approved by Council with the development application.

(Reason: To ensure compliance with this consent.)

17. PRINCIPAL CERTIFYING AUTHORITY (PCA) IDENTIFICATION SIGN (GC)

Prior to commencement of any work, signage must be erected in a prominent position on the work site identifying:

- i) the Principal Certifying Authority (PCA) by showing the name, address and telephone number of the PCA;
- ii) the Principal Contractor by showing the Principal Contractor's name, address and telephone number (outside of work hours) for that person; and
- iii) the sign must state that unauthorised entry to the work site is prohibited.

Any such sign is to be maintained while the work is being carried out, but must be removed when the work has been completed.

This clause does not apply to building work, subdivision work or demolition work that is carried out inside an existing building that does not affect the external walls of the building.

(Reason: Statutory requirement.)

18. PRIVACY - SCREEN PLANTING TO SIDE AND REAR BOUNDARIES (GC)

Evergreen shrubs with a minimum 5 litre container size achieving a minimum mature height of 3m shall be planted along the side and rear boundaries to provide suitable privacy screening. Screen planting shall be maintained at all times. Details of the selected plants shall be submitted to and approved by the Principal Certifying Authority. Compliance with this condition shall be certified by the Principal Certifying Authority, prior to occupation of the premises.

(Reason: To maintain privacy amenity to neighbouring residences.)

19. SITE MANAGEMENT (DURING DEMOLITION AND CONSTRUCTION WORKS)

All of the following are to be satisfied/complied with during demolition, construction and any other site works:

- i) All demolition is to be carried out in accordance with Australian Standard AS 2601-2001.
- ii) Demolition must be carried out by a registered demolition contractor.
- iii) A single entrance is permitted to service the site for demolition and construction. The footway and nature strip at the service entrance must be planked out.
- iv) No blasting is to be carried out at any time during construction of the building.
- v) Care must be taken during demolition/ excavation/ building/ construction to prevent

- any damage to adjoining buildings.
- vi) Adjoining owner property rights and the need for owner's permission must be observed at all times, including the entering onto land for the purpose of undertaking works.
 - vii) Any demolition and excess construction materials are to be recycled wherever practicable.
 - viii) The disposal of construction and demolition waste must be in accordance with the requirements of the Protection of the Environment Operations Act 1997.
 - ix) All waste on the site is to be stored, handled and disposed of in such a manner as to not create air pollution (including odour), offensive noise or pollution of land and/or water as defined by the Protection of the Environment Operations Act 1997. All excavated material should be removed from the site in an approved manner and be disposed of lawfully to a tip or other authorised disposal area.
 - x) All waste must be contained entirely within the site.
 - xi) Section 143 of the Protection of the Environment Operations Act 1997 requires waste to be transported to a place which can lawfully accept it. All non-recyclable demolition materials are to be disposed of at an approved waste disposal depot in accordance with legislation.
 - xii) All materials on site or being delivered to the site are to generally be contained within the site. The requirements of the Protection of the Environment Operations Act 1997 must be complied with when placing/stockpiling loose material, disposing of concrete waste, or other activities likely to pollute drains or water courses.
 - xiii) Details as to the method and location of disposal of demolition materials (weight dockets, receipts, etc.) should be kept on site as evidence of approved methods of disposal or recycling.
 - xiv) Any materials stored on site must be stored out of view or in such a manner so as not to cause unsightliness when viewed from nearby lands or roadways.
 - xv) Public footways, include nature strips and roadways adjacent to the site must be maintained and cleared of obstructions during construction. No building materials, waste containers or skips may be stored on the road reserve or footpath without prior separate approval from Council, including payment of relevant fees.
 - xvi) Building operations such as brick-cutting, washing tools or paint brushes, and mixing mortar not be performed on the roadway or public footway or any other locations which could lead to the discharge of materials into the stormwater drainage system.
 - xvii) All site waters during excavation and construction must be contained on site in an approved manner to avoid pollutants entering into waterways or Council's stormwater drainage system.
 - xviii) Any work must not prohibit or divert any natural overland flow of water.
 - xix) Toilet facilities for employees must be provided in accordance with WorkCover NSW.
 - xx) Protection pads are to be installed to the kerb and gutter where trucks and vehicles enter the site.

(Reason: To ensure that demolition, building and any other site works are undertaken in accordance with relevant legislation and policy and in a manner which will be non-disruptive to the local area.)

20. **STORMWATER MANAGEMENT PLAN - CERTIFICATION REQUIREMENT (GC)**

A detailed Stormwater Management Plan (SWMP) in line with Council's Stormwater Management Code is to be prepared and certified by a practicing Chartered Professional Engineer on the National Professional Engineer's Register (NPER) at Engineers Australia and submitted to the Principal Certifying Authority and Council, prior to the issue of a Construction Certificate. The SWMP is to be based on the approved development as modified by any conditions of consent.

(Reason: To ensure appropriate provision is made for the disposal and management of stormwater generated by the development, and to ensure public infrastructure in Council's care and control is not overloaded.)

21. SYDNEY WATER - STAMPED PLANS PRIOR TO COMMENCEMENT (GC)

The approved plans must be submitted to a Sydney Water Quick Check agent or Customer Centre to determine whether the development will affect Sydney Water's sewer and water mains, stormwater drains and/or easements, and if further requirements need to be met. Plans will be appropriately stamped.

For Quick Check agent details please refer to the web site www.sydneywater.com.au (see Building Developing and Plumbing then Quick Check) or telephone 13 20 92. The consent authority or a Certifying Authority must ensure that a Quick Check agent/Sydney Water has stamped the plans before the commencement of work.

(Reason: Compliance with Sydney Water requirements.)

22. UTILITIES AND SERVICES - PROTECTION OF (GC)

Any footings or excavation to be located or undertaken adjacent to Council's stormwater must be designed to address the following requirements:

- i) All footings and excavation must be located wholly within the site and clear of any easement boundaries;
- ii) All footings and excavation must be located a minimum of 1000mm from the centreline of the pipeline or 500mm from the outside of the pipeline, whichever is the greater distance from the centreline; and
- iii) Footings must extend to at least the depth of the invert of the pipeline unless the footings are to be placed on competent bedrock.

If permanent excavation is proposed beneath the obvert of the pipeline, suitable means to protect the excavation and proposed retaining structures from seepage or other water flow from the pipeline and surrounding subsoil, must be provided. The design must be prepared by a qualified practicing Structural/Civil Engineer.

Construction plans must be approved by the appropriate utility's office (e.g. council, Sydney Water Corporation) to demonstrate that the development complies with the utility's requirements.

The applicant must provide written evidence (e.g. compliance certificate, formal advice) of compliance with the requirements of all relevant utility providers (e.g. Water, Energy, Telecommunications, Gas).

(Reason: To ensure protection of Council assets.)

CONDITIONS TO BE SATISFIED PRIOR TO THE ISSUE OF A CONSTRUCTION CERTIFICATE (CC)

23. ACCESS - ACCESS FOR PEOPLE WITH DISABILITIES (CC)

Access for people with disabilities must be provided in accordance with the requirements of the Building Code of Australia, relevant Australian Standards and with regard to the Disability Discrimination Act 1992. Plans shall be notated demonstrating compliance and approved by the Principal Certifying Authority, prior to the issue of a Construction

Certificate.

Note: Disability (Access to Premises - Buildings) Standards 2010 - As of 1 May 2011, if access is provided to the extent covered by this Standard, then such access cannot be viewed as unlawful under the Disability Discrimination Act 1992.

(Reason: To provide equitable access for people(s) with disabilities in accordance with the relevant legislation and Australian Standards.)

24. ACCESS - DISABLED TOILETS (CC)

Plans and details of the disabled toilet/s complying with the relevant Australian Standards, the Building Code of Australia, and with regard to the Disability Discrimination Act 1992. Plans shall be notated demonstrating compliance and approved by the Principal Certifying Authority, prior to the issue of a Construction Certificate.

Note: Disability (Access to Premises - Buildings) Standards 2010 - As of 1 May 2011, if access is provided to the extent covered by this Standard, then such access cannot be viewed as unlawful under the Disability Discrimination Act 1992.

(Reason: To provide equitable access for people(s) with disabilities in accordance with the relevant legislation and Australian Standards.)

25. ACID SULFATE SOILS - CERTIFICATION OF SOIL REMOVED FROM THE SITE (CC)

A Certificate is to be provided by a suitably qualified geo-technical engineer stating that no more than 1 tonne of soil will be removed from the site and the groundwater table will not be affected by the development. This Statement shall be submitted to Council, prior to the issue of a Construction Certificate.

(Reason: Compliance and environmental protection.)

26. ARBORIST REPORT – INITIAL (CC)

The applicant must engage a suitably qualified and experienced arborist (Australian Qualification Framework Level 5 or above) to assess the impact of the proposed works and determine best practices (e.g. minimise compaction, soil build up and or excavation within the Primary Root Zone*) to ensure the longevity of the trees to be retained. The arborist is to prepare and submit, to the satisfaction of the Principal Certifying Authority, a report prior to the issue of a Construction Certificate, documenting the measures to be employed and certifying that they have been implemented.

- i) *Primary root zone = 10 x trunk diameter 1400mm from ground level (measured as a radius from the centre of the trunk).

(Reason: Qualified assessment of impact of proposed works on trees to be retained on the site.)

27. BASIX COMMITMENTS (CC)

The approved BASIX Certificate shall be submitted to the Principal Certifying Authority with the application for a Construction Certificate.

Where a change or changes are proposed in the BASIX commitments, the applicant must submit a new BASIX Certificate to the Principal Certifying Authority and Council. If any proposed change in the BASIX commitments is inconsistent with the development consent

the applicant will be required to submit a modification to the development consent to Council under Section 96 of the Environmental Planning and Assessment Act 1979.

All commitments in the BASIX Certificate must be shown on the plans accompanying the Construction Certificate.

(Reason: Statutory compliance.)

28. BICYCLE STORAGE PROVISION (CC)

On-site provision for bicycle storage facilities shall be in accordance with the Strathfield Consolidated Development Control Plan 2005. Details demonstrating compliance shall be submitted to the Principal Certifying Authority, prior to the issue of a Construction Certificate.

(Reason: Compliance with SCDCP 2005 and to encourage sustainable transport options.)

29. BUILDING CODE OF AUSTRALIA - COMPLIANCE WITH (CC)

All architectural drawings, specifications and related documentation shall comply with the Building Code of Australia (BCA). All work must be carried out in accordance with the requirements of the Building Code of Australia (BCA).

In the case of residential building work for which the Home Building Act 1989 requires there to be a contract of insurance in force in accordance with Part 6 of that Act, such a contract of insurance is to be in force before any building work authorised to be carried out by the consent commences.

Details demonstrating compliance with this condition are to be submitted to the Principle Certifying Authority, prior to issue of the Construction Certificate.

(Reason: This is a 'prescribed' condition under clause 98(1) of the Environmental Planning and Assessment Regulation 2000.)

30. CAR PARKING - BASEMENT CAR PARKING REQUIREMENTS (CC)

Details demonstrating compliance with the following is to be submitted to the Principal Certifying Authority, prior to issue of the Construction Certificate:

- ~~i) Minimal internal clearance of the basement is 2.2m in accordance with BCA requirements.~~
- i) Headroom clearance minimum of 2.7 metres is provided along the path of loading vehicular travel between the basement floor and any overhead obstruction (including overhead services).**
- ii) Driveways shall comply with Australian/New Zealand Standard AS/NZS 2890.1:2004 - Parking facilities - Off-street car parking and achieve a maximum gradient of 1:4.
- ~~iii) Basement entries and ramps/driveways within the property are to be no more than 3.5m wide.~~
- iv) Provision of pump-out systems and stormwater prevention shall be in accordance with Council's Stormwater Management Guide.
- v) Headroom clearance minimum of 2.5 metres is provided to all parking spaces for people with disabilities for compliance with Clause 2.4 of AS/NZS 2890.6:2009.**
- vi) Headroom clearance minimum of 2.2 metres is provided along the path of any vehicular travel between the basement floor and any overhead obstruction (including overhead services) for compliance with Clause 5.3.1 of AS/NZA**

2890.1:2004.

(Reason: To ensure suitable development.)

MODIFIED: DA2017/101/03 – 29 May 2020

31. CAR PARKING - DISABLED CAR PARKING SPACES (CC)

car parking spaces shall be provided as part of the total requirement shall for disabled persons. These spaces shall be a minimum of 2.4m wide x 5.4m long and located near pedestrian access routes designed for disabled persons. Each space shall be clearly marked as such. A shared area 2.4 m wide x 5.4m long shared area should be provided. Bollard shall be placed in this shared area.

Car parking for people with disabilities shall be provided in accordance with the Building Code of Australia, relevant Australian Standards and with regard to the Disability Discrimination Act 1992. Prior to the issue of a Construction Certificate, the plans shall be notated to demonstrate compliance.

The above details shall be submitted to and approved by the Principal Certifying Authority prior to the issue of a Construction Certificate.

(Reason: To ensure adequate parking for persons with a disability.)

32. CAR PARKING - REQUIREMENTS FOR MULTIPLE USE BUILDINGS (CC)

The following car parking and service vehicle requirements apply:-

- i) A minimum **(72) car spaces** shall be provided on the development site. This shall consist of:
 - (52) residential spaces;
 - (13) visitor spaces;
 - (7) commercial spaces;
 - 10% car parking spaces for people with mobility impairment, in accordance with AS 2890.1.
- ii) All car spaces shall be allocated and marked according to this requirement.
- iii) If the development is to be strata subdivided, the car park layout must reflect the above allocation and thereafter be regarded as part of the entitlement of that strata lot.
- iv) Under no circumstances shall parking spaces be sold, let or otherwise disposed of for use other than in accordance with this condition.
- v) Each car parking space shall have minimum dimensions in accordance with the relevant Australian Standard and be provided on-site in accordance with the approved plans.
- vi) The parking bays shall be delineated by line marking.
- vii) Visitor spaces shall be clearly line marked and/or signposted and shall only be used by persons visiting residents of the property or commercial/business/retail premises located within the development. Visitor spaces shall not be allocated as permanent residential parking spaces. Access to visitor parking spaces shall not be restricted without development approval and a sign shall be erected at the vehicular entrance indicating the availability of visitor parking.
- viii) The following traffic control measures shall be implemented on site:-
 - Signage indicating 'Entry Only' shall be prominently displayed at the entrance to the development.
 - Signage indicating 'Exit Only' shall be prominently displayed at the exit to the development.

One-Way directional arrows shall be painted on the driveway pavement to indicate the required vehicular directional movement through the car parking area.

Details demonstrating compliance with this condition shall be submitted to and approved by the Principal Certifying Authority, prior to the issue of a Construction Certificate.

(Reason: To ensure car parking provision in accordance with this consent.)

33. CAR PARKING – STACKED (CC)

Any stacked parking spaces (maximum 2 spaces, nose to tail) must be attached to the same strata title comprising a single dwelling unit or commercial/retail tenancy, subject to the maximum parking limit applying. The stacked parking spaces must be designated (with appropriate signage) for employee or tenant parking only (not visitor parking). Details in this regard must be reflected in the plan documentation to be lodged with a Construction Certificate application. Manoeuvring of stacked vehicles must occur wholly within the property.

(Reason: Compliance and appropriate allocation of parking.)

34. CAR PARKING - VEHICULAR ACCESS RAMPS (CC)

Vehicular access ramps shall comply with the provisions of AS/NZS 2890.1:2004. Plans to be submitted shall contain the following details:

- i) Longitudinal section along the extreme wheel paths of each driveway/access ramp at a scale of 1:25 demonstrating compliance with the scraping provisions of AS/NZS 2890.1:2004. It shall include all levels and grades, including those levels stipulated as boundary levels, both existing and proposed. It shall extend from the centre-line of the roadway through to the parking area.
- ii) Sections showing the clearance to the underside of any overhead structure (minimum headroom requirements 2200mm minimum for standard headroom clearance or 2400mm where disabled access provisions are to be provided) demonstrating compliance with the provisions of AS/NZS 2890.1:2004.
- iii) Longitudinal section along the gutter line showing how it is intended to transition the vehicular crossing into the existing kerb and gutter. Boundary levels shall generally run parallel with the kerb levels.
- iv) Location of verge trees, street furniture and service installations.
- v) Superimposition of vehicle turning circles for access into parking spaces.
- vi) Certification that the design complies with AS/NZS 2890.1:2004 by a Qualified Engineer.

The certification referred to in (vi) above shall be submitted to the Principal Certifying Authority prior to the issue of a Construction Certificate (for the design) and to the Principal Certifying Authority prior to the issue of any Occupation Certificate for the 'as-built works'.

(Reason: To ensure adequate vehicular access can be achieved.)

35. CAR PARKING - COMPLIANCE WITH AS/NZS 2890.1:2004 (CC)

Car parking dimensions must comply with the Australian/New Zealand Standard AS/NZS 2890.1:2004 - Parking facilities - Off-street car parking. Details demonstrating compliance are to be submitted to the Principal Certifying Authority, prior to the issue of a Construction Certificate.

(Reason: To ensure compliance with Australian Standards relating to parking of vehicles.)

36. CAR PARKING - VEHICULAR CIRCULATION, AISLE AND RAMP WIDTHS (CC)

The aisle widths, internal circulation, ramp widths and grades of the car park shall comply with the Roads and Traffic Authority Guidelines and ASNZS 2890.1:2004 - Off-Street Car Parking Code.

Vehicular manoeuvring paths are to be prepared demonstrating that all vehicles can enter or depart the site in a forward direction without encroaching on required car parking spaces.

(Reason: To ensure compliance with Australian Standards relating to manoeuvring, access and parking of vehicles.)

37. ~~CAR PARKING - VEHICULAR CROSSING WIDTH AT PROPERTY BOUNDARY (CC)~~

~~Vehicular crossings are to have a maximum width of 3m at the property boundary. Details demonstrating compliance are to be submitted to the Principal Certifying Authority, prior to the issue of a Construction Certificate.~~

~~(Reason: Compliance with SCDGP 2005.)~~

DELETED: 29 May 2020 (DA2017/101/03)

38. COMMENCEMENT OF WORKS (NO WORKS UNTIL A CC IS OBTAINED)

Building work, demolition or excavation must not be carried out until a Construction Certificate has been issued by either Strathfield Council or a Principal Certifying Authority.

Demolition of any part of a building triggers 'commencement of erection of building' pursuant of section 81A(2) of the EP&A Act 1979. Accordingly, demolition works must not commence until a Construction Certificate has been issued, a Principal Certifying Authority has been appointed and a Notice of Commencement has been issued.

(Reason: To ensure compliance with statutory provisions.)

39. CONSTRUCTION AND ENVIRONMENTAL MANAGEMENT PLAN (CC)

The applicant must prepare and submit a Construction and Environmental Management Plan (CEMP) to the Principal Certifying Authority, including:

- i) Detailed information on any approvals required from other authorities prior to or during construction.
- ii) Traffic management, including details of:
 - ingress and egress of vehicles to the site;
 - management of loading and unloading of materials;
 - the location of heavy vehicle parking off-site; and
 - designated routes for vehicles to the site.
- iii) The proposed areas within the site to be used for a builder's site office and amenities, the storage of excavated material, construction materials and waste containers during the construction period.
- iv) Erosion and sediment control, detailing measures and procedures consistent with the requirements of Council's guidelines for managing stormwater, including:
 - the collection and treatment of stormwater and wastewater generated on site prior to discharge; and
 - procedures to prevent run-off of solid material and waste from the site.

- v) Waste management, including:
 - details of the types and estimated volumes of waste materials that will be generated;
 - procedures for maximising reuse and recycling of construction materials; and
 - details of the off-site disposal or recycling facilities for construction waste.
- vi) Dust control, outlining measures to minimise the generation and off-site transmission of dust and fine particles, such as watering or damp cloth fences.
- vii) A soil and water management plan, which includes:
 - measures to minimise the area of soils exposed at any one time and conserve top soil;
 - identification and protection of proposed stockpile locations;
 - preservation of existing vegetation and revegetation;
 - measures to prevent soil, sand, sediments leaving the site in an uncontrolled manner;
 - measures to control surface water flows through the site in a manner that diverts clean run-off around disturbed areas, minimises slope gradient and flow distance within disturbed areas, ensures surface run-off occurs at non-erodible velocities, and ensures disturbed areas are promptly rehabilitated;
 - details of sediment and erosion control measures in place before work commences;
 - measures to ensure materials are not tracked onto the road by vehicles entering or leaving the site; and
 - details of drainage to protect and drain the site during works.
- viii) Asbestos management procedures:
 - Anyone who removes, repairs or disturbs bonded or a friable asbestos material must hold a current removal licence from Workcover NSW holding either a Friable (Class A) or a Non- Friable (Class B) Asbestos Removal License which ever applies and a current WorkCover Demolition License where works involve demolition. To find a licensed asbestos removalist please see www.workcover.nsw.gov.au
 - Removal of asbestos by a person who does not hold a Class A or Class B asbestos removal license is permitted if the asbestos being removed is 10m² or less of non-friable asbestos (approximately the size of a small bathroom). Friable asbestos materials must only be removed by a person who holds a current Class A asbestos license.
 - Before starting work, a work site-specific permit approving each asbestos project must be obtained from Workcover NSW. A permit will not be granted without a current Workcover licence. All removal, repair or disturbance of or to asbestos material must comply with the following:
 - The Work Health and Safety Act 2011;
 - The Work Health and Safety Regulation 2011;
 - How to Safely Remove Asbestos Code of Practice – WorkCover 2011; and
 - Safe Work Australia Code of Practice for the Management and Control of Asbestos in the Workplace.
 - Following completion of asbestos removal works undertaken by a licensed asbestos removalist re-occupation of a workplace must not occur until an independent and suitably licensed asbestos removalist undertakes a clearance inspection and issues a clearance certificate.
 - The developer or demolition contractor must notify adjoining residents at least two (2) working days (i.e. Monday to Friday exclusive of public holidays) prior to the commencement of asbestos removal works. Notification is to include, at a minimum:
 - the date and time when asbestos removal works will commence;
 - the name, address and business hours contact telephone number of the demolisher, contractor and/or developer;

the full name and license number of the asbestos removalist/s; and
the telephone number of WorkCover's Hotline 13 10 50
warning signs informing all people nearby that asbestos removal work is taking place in the area. Signs should be placed at all of the main entry points to the asbestos removal work area where asbestos is present. These signs should be weatherproof, constructed of light-weight material and adequately secured so they remain in prominent locations. The signs should be in accordance with AS 1319-1994 Safety signs for the occupational environment for size, illumination, location and maintenance; and
appropriate barricades installed as appropriate to prevent public access and prevent the escape of asbestos fibres. Barricades must be installed prior to the commencement of asbestos removal works and remain in place until works are completed.

(Reason: Safety, amenity and protection of public infrastructure and the environment.)

40. **COUNCIL PERMITS – FOR ALL ACTIVITIES ON COUNCIL LAND (CC)**

Works Permit

(as per Section 68 of the Local Government Act 1993 and Section 138 and 139 of the Roads Act 1993)

A Works Permit is required for construction of a vehicular crossing (driveway), new stormwater down pipe connection to kerb and gutter, new footpath and/or stormwater connection. A Works Permit Application Form is available from Council's Customer Centre or can be downloaded from Council's website. The applicable fees and charges are located on Council's website.

Standing Plant Permit

This permit must be applied for where it is intended to park a concrete pump, crane or other plant on the roadway or footpath. A Standing Plant Permit Application Form is available from Council's Customer Centre or can be downloaded from Council's website. The applicable fees and charges are located on Council's website. Please note a Road Closure Permit is not required for standing plant.

Skip Bin Permit

This permit must be applied for if you intend to place a skip bin on the roadway or footpath. A Skip Bin Application Form is available from Council's Customer Centre or can be downloaded from Council's website. The applicable fees and charges are located on Council's website.

Temporary Full or Part Road Closure Permit

This permit must be applied for if you require a full or a part road closure to take place to assist in your construction works. Please use the Works Permit Application Form, which is available from Council's Customer Service Centre or can be downloaded from Council's website. The applicable fees and charges are located on Council's website. Please note a Road Closure Permit is not required for standing plant.

Hoarding Permit

This permit must be applied for if you intend to erect a Class A (fence type) or Class B (overhead type) hoarding along the street frontage(s). A Hoarding Permit Application Form is available from Council's Customer Service Centre or can be downloaded from Council's website. The applicable fees and charges are located on Council's website.

Work Zone Permit

This permit must be applied for if you require permanent parking along the kerbside at the front of the site during construction works. A Work Zone Permit Application Form is available from Council's Customer Service Centre or can be downloaded from Council's website. The applicable fees and charges are located on Council's website.

Ground Anchoring Permit

This permit must be applied for, for the installation of ground anchors under Council's footway/road reserve. It does not cover ground anchors under private properties. A separate approval is required to be obtained from Roads and Maritime Services (RMS) if it is proposed to install ground anchors under a State or Classified Regional Road (please refer to the end of this application form for more information).

(Reason: Council requirement)

41. DILAPIDATION REPORT - PRE-COMMENCEMENT (CC)

Subject to access being granted, a pre-commencement Dilapidation Report is to be undertaken on all adjoining properties, which in the opinion of a suitably qualified engineer, could be potentially affected by the construction of the project. The Dilapidation Report shall be carried out prior to the issue of a Construction Certificate.

The Dilapidation Report is to be prepared by a suitably Qualified Engineer with current Corporate Membership with the Institution of Engineers, Australia or Geotechnical Practitioner. The report shall include a photographic survey of adjoining properties detailing the physical condition of those properties, both internally and externally, including walls, ceilings, roof, structural members and other such items.

If access for undertaking the dilapidation survey is denied by an adjoining owner, the applicant must demonstrate, in writing, to Council's satisfaction attempts have been made to obtain access and/or advise the affected property owner of the reason for the survey and these attempts have been unsuccessful. Written concurrence must be obtained from Council in such circumstances.

The Report shall cover structural and geotechnical factors likely to arise from the development. A copy of this Report shall be submitted to Council as a record. The person having the benefit of the development consent must, at their own cost, rectify any damage caused to other properties during the construction of the project.

(Reason: To ensure no damage to adjoining properties occurs.)

42. DRIVEWAY WIDTH - MULTI-UNIT DEVELOPMENT (CC)

The internal driveway must be a minimum 5.50m wide (clear width) for the first 6 metres inside the property so as to allow entering & exiting vehicles to pass within the site. Should the driveway narrow after this point it is then to be designed with a minimum 1.5m x 1.5m splay to allow the passing to work. Details demonstrating compliance shall be submitted to the Principal Certifying Authority, prior the issue of a Construction Certificate.

(Reason: Safety and traffic management.)

43. DRIVEWAY DESIGN - SPEED HUMP AND STOP SIGN ON EXIT (CC)

The applicant shall install a stop sign and a speed hump at the exit from the site. The stop sign must be accompanied by the associated line marking and the speed hump shall be set back by 1.5 metres from the boundary alignment. The devices shall be designed and constructed in accordance with the provision of all relevant Australian Standards. The

building plans shall indicate compliance with this requirement, prior to the issue of a Construction Certificate.

(Reason: Traffic safety and management.)

44. EXCAVATION - AFFECTING ADJOINING LAND (CC)

If an excavation associated with the approved development extends below the level of the base of the footings of a building on an adjoining allotment of land, the person having the benefit of the development consent must, at the person's own expense, comply with the requirements of clause 98E of the Environmental Planning and Assessment Regulation 2000, including:

- i) protect and support the adjoining premises from possible damage from the excavation, and
- ii) where necessary, underpin the adjoining premises to prevent any such damage.

The condition referred to in subclause (i) does not apply if the person having the benefit of the development consent owns the adjoining land or the owner of the adjoining land has given consent in writing to that condition not applying. Details shall be submitted to the Principal Certifying Authority, prior to the issue of a Construction Certificate.

(Reason: Structural safety.)

45. FEES - PUBLIC RISK INSURANCE POLICY (CC)

b.A Public Risk Insurance Policy with a minimum cover of \$20 million in relation to the occupation of and works within Council's road reserve, for the full duration of the proposed works, must be obtained with a copy also provided to Council.

c.

d.The Policy is to note Council as an interested party. The copy is to be provided to Council, prior to the issue of a Construction Certificate.

(Reason: Ensure public risk is mitigated.)

46. HAZARDOUS GOODS AND WASTE (CC)

Dangerous and hazardous goods shall be stored in accordance with NSW WorkCover requirements and AS1940-2004 - The Storage and Handling of Flammable and Combustible Liquids.

Hazardous waste must be contained, managed and disposed of in a responsible manner in accordance with the Protection of Environment and Operations Act 1997, NSW Environment Protection Authority (EPA) and the New South Wales WorkCover Authority.

Material Safety Data Sheets of all hazardous substances used, such as bleaches and nail products must be kept on site and readily available to all staff. Staff must be trained how to safely use and store these chemicals prior to the commencement of work.

Details demonstrating compliance with the requirements of this condition are to be submitted to the satisfaction of the Principal Certifying Authority prior to the issue of any Construction Certificate.

(Reason: Health and safety.)

47. LANDSCAPING - MAINTENANCE STRATEGY (CC)

To ensure the survival of landscaping following works, a landscape maintenance strategy for the owner/occupier to administer over a 12 month establishment period following the issue of the Occupation Certificate shall be prepared and provided to the satisfaction of the Principal Certifying Authority with the Construction Certificate application. The strategy is to address maintenance issues such as, but not limited to plant survival, irrigation, soil testing, weeding, staking, fertilizing, remedial pruning and plant replacement.

(Reason: Ensure landscape survival.)

48. PRIVACY - OBSCURE GLAZING IN WET AREAS (CC)

All bathroom, ensuite and toilet windows shall be installed with obscure glazing. Plans shall be notated accordingly and details demonstrating compliance submitted to the Principal Certifying Authority, prior to the issue of a Construction Certificate.

(Reason: Privacy amenity.)

49. SECTION 94 CONTRIBUTION PAYMENT - DIRECT CONTRIBUTIONS PLAN (CC)

In accordance with the provisions of Section 94(1)(b) of the Environmental Planning and Assessment Act 1979 and the Strathfield Direct Development Contributions Plan 2010-2030, a contribution in the form of cash, cheque or credit card (financial transaction fee applies) shall be paid to Council for the following purposes:

Provision of Community Facilities	\$120,399.13
Provision of Major Open Space	\$549,555.69
Provision of Local Open Space	\$120,933.97
Provision Roads and Traffic Management	\$22,488.96
Administration	\$10,417.24
TOTAL	\$823,794.99

The total amount of the contribution is valid as at the date of determination and is subject to quarterly indexation. Contributions shall be indexed at the time of payment in accordance with clause 2.14 of the Strathfield Direct Development Contributions Plan 2010-2030.

Contributions must be receipted by Council and submitted to the Accredited Certifier, prior to the issue of any Construction Certificate.

Please present a copy of this condition when paying the contribution at the Customer Service Centre so that it can be recalculated.

Note: A copy of Strathfield Council's Section 94 Direct Development Contributions Plan may be downloaded from Council's website.

(Reason: To enable the provision of public amenities and services required/anticipated as a consequence of increased demand resulting from the development.)

50. SECURITY PAYMENT - DAMAGE DEPOSIT FOR COUNCIL INFRASTRUCTURE (CC)

A security (damage deposit) of **\$33,000.00** (calculated in accordance with Council's adopted Fees and Charges) shall be paid to Council, prior to the issue of a Construction Certificate.

The deposit is required as security against any damage to Council property during works on

the site. The applicant must bear the cost of all restoration works to Council's property damaged during the course of this development. All building work must be carried out in accordance with the Building Code of Australia.

Payment may be accepted in the form of cash, bank guarantee, cheque or credit card (financial transactions fees apply). Note: Additional fees apply for the lodgement of a bank guarantee in lieu of cash bond applies in accordance with Council's adopted Fees and Charges.

Any costs associated with works necessary to be carried out to rectify any damages caused by the development, shall be deducted from the Damage Deposit.

Note: Should Council property adjoining the site be defective e.g. cracked footpath, broken kerb etc., this should be reported in writing, or by photographic record, submitted to Council at least seven (7) days prior to the commencement of any work on site. This documentation will be used to resolve any dispute over damage to infrastructure. It is in the applicant's interest for it to be as full and detailed as possible.

The damage deposit shall be refunded upon completion of all works upon receipt of a Final Occupation Certificate stage and inspection by Council.

(Reason: Protection of Council infrastructure.)

51. **TRAFFIC - CONSTRUCTION TRAFFIC MANAGEMENT PLAN (CC)**

A Construction Traffic Management Plan (CTMP) is to be prepared by an appropriately qualified Traffic Management Consultant and submitted to and approved by Council's Engineering Section, prior to the commencement of any works including demolition.

The following matters should be addressed in the CTMP (where applicable):

- i) description of the demolition, excavation and construction works;
- ii) site plan/s showing the site, roads, footpaths, site access points and vehicular movements;
- iii) size, type and estimated number of vehicular movements (including removal of excavated materials, delivery of materials and concrete to the site);
- iv) proposed route(s) from the arterial (state) road network to the site and the proposed route from the site back to the arterial road network;
- v) impacts of the work and vehicular movements on the road network, traffic and pedestrians and proposed methods to safely manage pedestrians and construction related vehicles in the frontage roadways;
- vi) any Traffic Control Plans (TCP's) proposed to regulate traffic and pedestrian movements for construction activities (such as concrete pours, crane installation/removal etc.);
- vii) proposed hours of construction related activities and vehicular movements to and from the site;
- viii) current/proposed approvals from other Agencies and Authorities (including Roads and Maritime Services, Police and State Transit Authority);
- ix) any activities proposed to be located or impact upon Council's road, footways or any public place;
- x) measures to maintain public safety and convenience;
- xi) any proposed road and/or footpath closures;
- xii) turning areas within the site for construction and spoil removal vehicles, allowing a forward egress for all construction vehicles on the site;
- xiii) locations of work zones (where it is not possible for loading/unloading to occur on the site) in the frontage roadways accompanied by supporting documentation that

- such work zones have been approved by the Local Traffic Committee and Council;
- xiv) location of any proposed crane and concrete pump and truck standing areas on and off the site (and relevant approvals from Council for plant on road);
 - xv) a dedicated unloading and loading point within the site for all construction vehicles, plant and deliveries;
 - xvi) material, plant and spoil bin storage areas within the site, where all materials are to be dropped off and collected;
 - xvii) on-site parking area for employees, tradespersons and construction vehicles as far as possible;
 - xviii) proposed areas within the site to be used for the storage of excavated material, construction materials and waste and recycling containers during the construction period; and
 - xix) how it is proposed to ensure that soil/excavated material is not transported onto surrounding footpaths and roadways.

(Reason: To mitigate traffic impacts on the surrounding area during the construction period.)

52. VEHICULAR CROSSINGS - WORKS PERMIT FOR CONSTRUCTION OF (CC)

Full-width, heavy-duty concrete vehicular crossing(s) shall be provided across the footpath at the entrance(s) and/or exit(s) to the site and designed in accordance with Council's guidelines and specifications. In this regard, a Works Permit is to be obtained (available from Council's Customer Services Centre or downloaded from Council's website), and the appropriate fees and charges paid, prior to the lodgement of a Construction Certificate.

(Reason: To ensure appropriate access to the site can be achieved.)

53. VENTILATION SYSTEMS – MECHANICAL (CC)

The mechanical ventilation system is to comply with the following:

- i) The Building Code of Australia;
- ii) Protection of the Environment Operations Act 1997; and
- iii) Australian Standard AS1668-1991.

In addition, odour control measures, such as activated carbon or catalytic oxidisers, must be used to treat ventilation gases prior to discharge. The method of odour control must be designed by a suitably qualified mechanical ventilation engineer.

Details demonstrating compliance with the above are to be submitted to the Principal Certifying Authority, prior to the issue of a Construction Certificate.

(Reason: To ensure the mechanical ventilation system complies with the relevant requirements/standards.)

54. WASTE MANAGEMENT PLAN (CC)

A Waste Management Plan (WMP) is to be provided in accordance with Part H of Strathfield Consolidated Development Control Plan 2005. All requirements of the approved Waste Management Plan must be implemented during demolition, construction and on-going use of the premises.

The WMP must identify the types of waste that will be generated and all proposals to re-use, recycle or dispose of the waste. The WMP is to be submitted to the Principal Certifying Authority, prior to issue of the Construction Certificate.

NOTE: The property must be inspected by a Council Waste Officer prior to the issue of an Occupation Certificate so as to ensure that the correct number of general waste and recycling bins are ordered from Strathfield Council.

(Reason: To ensure appropriate management of waste.)

55. WASTE - SEPARATE WASTE AREAS FOR MIXED-USE DEVELOPMENTS (CC)

The building must include not less than two independently designated areas or garbage rooms for commercial and for residential occupants; to keep commercial waste and recycling separate to residential waste and recycling.

(Reason: To ensure the appropriate separation and collection of waste generated by commercial and residential activities.)

56. WASTE - GARBAGE ROOMS OR GREASE ARRESTOR ROOMS (CC)

Garbage rooms or grease arrester rooms must be constructed of solid material: cement rendered and steel trowelled to a smooth even surface. The door to the garbage room is to be designed and constructed to ensure the room is vermin proof and can be opened from the inside at all times. The garbage room is to be ventilated to the external air by natural ventilation or an approved air handling exhaust system.

(Reason: To keep garbage rooms in a clean and sanitary condition to protect public health.)

57. WATER SUSTAINABILITY - WATER SENSITIVE URBAN DESIGN (CC)

Details of the Water Sensitive Urban Design (WSUD) components (stormwater treatment measures) shall be submitted to and approved by the Principal Certifying Authority prior to the issue of a Construction Certificate. Details shall demonstrate compliance with the water conservation and stormwater quality targets set out under Sections 3.1 and 3.2 respectively under Part N of the SCDCP 2005, and be prepared by a suitably qualified professional engineer.

(Reason: To promote Water Sensitive Urban Design.)

58. WORKS WITHIN THE ROAD RESERVE (CC)

Detailed drawings including long and short sections and specifications of all works within existing roads (including but not limited to structures, road works, driveway crossings, footpaths and stormwater drainage) shall be submitted to and approved by Council under Section 138 of the Roads Act 1993 and all fees and charges paid, prior to the issue of a Construction Certificate.

Detailed drawings and specifications are to be prepared and certified by an appropriately qualified Civil Engineer.

Upon completion of the works, the Applicant is to provide to Council with electronic copies of 'Work as Executed Plans'. The plans are to show relevant dimensions and finished levels and are to be certified by a surveyor.

The Applicant is to provide to Council, in an approved format, details of all public infrastructure created as part of the works.

All civil engineering works adjacent/near/outside Water Street and Punchbowl Road are to

be fully supervised by Council. A maintenance period of six (6) months shall apply to the work, after it has been completed and approved. In that period the Applicant shall be liable for any part of the work which fails to perform in the manner outlined in Council's specifications, or as would reasonably be expected under the design conditions.

(Reason: To ensure compliance of engineering works/Council assets are constructed to acceptable standards for engineering works.)

59. WORKS ZONE - APPROVAL BY COUNCIL'S TRAFFIC COMMITTEE (CC)

An application for a 'Works Zone' must be submitted to and approved by the Strathfield Council Traffic Committee prior to the commencement of any site work (including demolition).

The suitability of the proposed length and duration of the Works Zone is to be demonstrated in the application for the Works Zone. The application for the Works Zone must be submitted to Council at least six (6) weeks prior to the commencement of work on the site to allow for assessment and tabling of agenda for the Strathfield Council Traffic Committee.

The requirement for a Works Zone may be varied or waived only if it can be demonstrated in the Construction Traffic Management Plan (to the satisfaction of Council) that all construction related activities (including all loading and unloading operations) can and will be undertaken wholly within the site. The written approval of Council must be obtained to provide a Works Zone or to waive the requirement to provide a Works Zone prior to the commencement of any site work.

(Reason: Council requirement.)

CONDITIONS TO BE SATISFIED PRIOR TO THE COMMENCEMENT OF WORKS (CW)

60. APPOINTMENT OF A PRINCIPAL CERTIFYING AUTHORITY (PCA) (CW)

No work shall commence in connection with this Development Consent until:

- i) A construction certificate for the building work has been issued by the consent authority or a Principal Certifying Authority.
- ii) The person having the benefit of the development consent has appointed a principal certifying authority for the building work, and notified the principal certifying authority that the person will carry out the building work as an owner/builder, if that is the case.
- iii) The principal certifying authority has, no later than 2 days before the building work commences:
 - notified the Council of his or her appointment, and
 - notified the person having the benefit of the development consent of any critical stage inspections and other inspections that are to be carried out in respect of the building work.
- iv) The person having the benefit of the development consent, if not carrying out the work as an owner-builder, has:
 - appointed a principal contractor for the building work who must be the holder of a contractor licence if any residential building work is involved;
 - notified the principal certifying authority of such appointment; and
 - unless that person is the principal contractor, notified the principal contractor of any critical stage inspections and other inspections that are to be carried out in respect of the building work.
- v) The person having the person having the benefit of the development consent has given at least 2 days notice to the Council of the person's intention to commence the

erection of the building.

Note: If the principal certifying authority is the Council, the nomination will be subject to the payment of a fee for the service to cover the cost of undertaking all necessary inspections and the issue of the appropriate certificates.

Under the Environment Planning and Assessment (Quality of Construction) Act, 2003, a sign must be erected in a prominent position on the work site showing the name, address and telephone number of the principal certifying authority; the name of the principal contractor (if any) for the building work and a telephone number at which that person may be contacted outside working hours. That sign must also state that unauthorised entry is prohibited. The sign must not be removed until all work has been completed.

(Reason: Statutory requirement.)

61. NOTICE OF COMMENCEMENT (CW)

No work shall commence until the following details are submitted to Council:

- i) a Notice of Commencement (form will be attached with issue of a Construction Certificate or available from our website) within two (2) days of the date on which it is proposed to commence works associated with the Development Consent;
- ii) details of the appointment of a Principal Certifying Authority (either Council or another Principal Certifying Authority); and
- iii) details of the name, address and licence details of the Builder.

(Reason: Statutory requirement.)

CONDITIONS TO BE SATISFIED DURING DEMOLITION AND BUILDING WORKS (DW)

62. CONTAMINATED LAND UNEXPECTED FINDS (DW)

In the instance works cause the generation of odours or uncovering of unexpected contaminants works are to immediately cease, Council is to be notified and a suitably qualified environmental scientist appointed to further assess the site.

The contaminated land situation is to be evaluated by the supervising environmental consultant and an appropriate response determined in consultation with the applicant, which is agreed to by Strathfield Council's Environmental Services Manager.

Note: Council may also request that a NSW EPA accredited site auditor is involved to assist with the assessment of the contaminated land situation and review any new contamination information. The applicant must also adhere to any additional conditions which may be imposed by the accredited site auditor.

(Reason: To ensure compliance with statutory requirements.)

63. FILL MATERIAL (DW)

The only waste derived material which may be received at the development site is:

- i) Virgin excavated material (within the meaning of the Protection of the Environment Operations Act 1997), and
- ii) any other waste-derived material the subject of a resource recovery exemption under cl.51A of the Protection of the Environment Operations (Waste) Regulation 2005 that is permitted to be used as fill material.

Any (b)-type material received at the development site must be accompanied by documentation certifying by an appropriately qualified environmental consultant the materials compliance with the exemption conditions; and this documentation must be provided to the Principal Certifying Authority on request.

(Reason: To ensure imported fill is of an acceptable standard for environmental protection purposes.)

64. OBSTRUCTION OF PUBLIC WAY NOT PERMITTED DURING WORKS (DW)

The public way must not be obstructed by any materials, vehicles, refuse, skips or the like, under any circumstances, without the prior approval of Council.

(Reason: To maintain public access and safety.)

65. PUBLIC INFRASTRUCTURE AND SERVICES (DW)

The applicant must comply with the requirements (including financial costs) of any relevant utility provider (e.g. Energy Australia, Sydney Water, Telstra, RMS, Council etc.) in relation to any connections, works, repairs, relocation, replacements and/or adjustments to public infrastructure or services affected by the development.

(Reason: To maintain public infrastructure and/or services.)

66. SITE REQUIREMENTS DURING DEMOLITION AND CONSTRUCTION

All of the following are to be satisfied/complied with during demolition, construction and any other site works:

- i) All demolition is to be carried out in accordance with Australian Standards AS 2601-2001.
- ii) Demolition must be carried out by a registered demolition contractor.
- iii) A single entrance is permitted to service the site for demolition and construction. The footway and nature strip at the service entrance must be planked out with close boarded, hardwood timber footpath protection pads. The pad shall cover the entire width of the footpath opening for the full width of the fence.
- iv) No blasting is to be carried out at any time during construction of the building.
- v) Care must be taken during demolition/ excavation/ building/ construction to prevent any damage to adjoining buildings.
- vi) Adjoining owner property rights and the need for owner's permission must be observed at all times, including the entering onto land for the purpose of undertaking works.
- vii) Any demolition and excess construction materials are to be recycled wherever practicable.
- viii) The disposal of construction and demolition waste must be in accordance with the requirements of the Protection of the Environment Operations Act 1997.
- ix) All waste on the site is to be stored, handled and disposed of in such a manner as to not create air pollution (including odour), offensive noise or pollution of land and/or water as defined by the Protection of the Environment Operations Act 1997.
- x) All excavated material should be removed from the site in the approved manner and be disposed of lawfully to a tip or other authorised disposal area.
- xi) Section 143 of the Protection of the Environment Operations Act 1997 requires waste to be transported to a place which can lawfully accept it. All non-recyclable demolition materials are to be disposed of at an approved waste disposal depot in accordance with legislation.
- xii) All materials on site or being delivered to the site are to generally be contained within

the site. The requirements of the Protection of the Environment Operations Act 1997 must be complied with when placing/stockpiling loose material, disposing of concrete waste, or other activities likely to pollute drains or water courses.

- xiii) Details as to the method and location of disposal of demolition materials (weight dockets, receipts etc.) should be kept on site as evidence of approved methods of disposal and recycling.
- xiv) Any materials stored on site must be stored out of view or in such a manner so as not to cause unsightliness when viewed from nearby lands or roadways.
- xv) Public footways and roadways adjacent to the site must be fully maintained and cleared of obstructions during construction unless prior separate approval from Council is obtained including payment of relevant fees.
- xvi) Building operations such as brick cutting, washing tools or paint brushes, and mixing mortar not be performed on the roadway or public footway or any other locations which could lead to the discharge of materials into the stormwater drainage system.
- xvii) All site waters during excavation and construction must be contained on site in an approved manner to avoid pollutants entering into waterways or Council's stormwater drainage system.
- xviii) Stamped plans, specifications, documentation and the consent shall be available on site at all times during construction.

(Reason: To ensure that demolition, building and any other site works are undertaken in accordance with relevant legislation and policy and in a manner which will be non-disruptive to the local area.)

67. **SURVEY REPORT OF APPROVED LEVELS DURING AND POST CONSTRUCTION (DW)**

A Survey Certificate to Australian Height Datum shall be prepared by a Registered Surveyor as follows:

- i) At the completion of the first structural floor level prior to the pouring of concrete indicating the level of that floor and the relationship of the building to the boundaries.
- ii) At the completed height of the building, prior to the placement of concrete in form work, or the laying of roofing materials.
- iii) At the completion of the development.

Progress certificates in response to points (1) through to (3) shall be provided to the Principal Certifying Authority at the time of carrying out relevant progress inspections. Under no circumstances is work allowed to proceed until such survey information is submitted to and approved by the Principal Certifying Authority.

(Reason: To ensure compliance with the approved plans.)

CONDITIONS TO BE SATISFIED PRIOR TO THE ISSUE OF AN OCCUPATION CERTIFICATE (OC)

68. **CAR PARKING - SURPLUS VEHICULAR CROSSINGS (OC)**

All surplus vehicular crossings and/or kerb laybacks must be removed and reinstated with concrete kerb and gutter or to the existing edging profile as specified by Council. The nature strip is to be restored and the footpath area reinstated. All of the above are to be restored to the satisfaction of Council's Engineer and at full cost to the applicant, prior to the issue of any Occupation Certificate.

(Reason: Maintenance of public infrastructure.)

69. CAR PARKING - VISITOR CAR PARKING SIGNAGE (OC)

A sign shall be erected in a suitable location on the property near the driveway entrance indicating where visitor parking is available on the site. Signage shall also be erected above the visitor parking itself. Details demonstrating compliance shall be demonstrated to the Principal Certifying Authority, prior to the issue of any Occupation Certificate.

(Reason: Adequate access and egress.)

70. DRAINAGE SYSTEM - MAINTENANCE OF EXISTING SYSTEM (OC)

Where elements of the existing drainage system are to be utilised, the existing drainage system shall be overhauled and maintained clear of silt and accumulated debris. Silt and the like shall be removed, not flushed from the system.

A certificate shall be provided by a suitably qualified person (a registered plumber or a person of equivalent or greater experience or qualification) to the satisfaction of the Principal Certifying Authority, prior to the issue of any Occupation Certificate to confirm that the system is in good working order and adequate to accept additional flows having regard to any relevant standards and/or Sydney Water requirements.

(Reason: Maintenance and environment.)

71. ENGINEERING WORKS (CERTIFICATION OF)

Prior to occupation of the premises, a Work As Executed (WAE) Plan of all engineering and/or drainage works is to be submitted to the Principal Certifying Authority. The WAE Plan is to be certified by a suitably Qualified Engineer, with Corporate Membership standing in the Institution of Engineers Australia and registered on the National Professional Engineers Register (NPER) under the appropriate professional category, demonstrating that:

- i) The stormwater drainage system; and/or
- ii) The car parking arrangement and area; and/or
- iii) Any related footpath crossing works; and/or
- iv) The proposed basement pump and well system; and/or
- v) The proposed driveway and layback; and/or
- vi) Any other civil works

have been constructed in accordance with the approved plans and any relevant Standards and Council policies/specifications.

For major works, such as subdivisions, works within the road reserve (requiring separate S138 approval) and as where specified by Council, a Part 4A Certificate will be required. It is strongly recommended that an Engineer supervise all engineering related works.

Where Council is not the Principal Certifying Authority, an electronic copy of the above documents is to be provided to Council, prior to the issue of any Occupation Certificate.

(Reason: Asset management.)

72. FIRE SAFETY CERTIFICATION (OC)

A fire safety certificate shall be obtained in accordance with Part 9, Division 4 of the Environmental Planning and Assessment Regulation 2000, prior to the issue of any Occupation Certificate.

An fire safety certificate is a certificate issued by the owner of a building to the effect that each essential fire safety measure specified in the current fire safety schedule for the part of the building to which the certificate relates:

- i) Has been assessed by a properly qualified person; and
- ii) Was found, when it was assessed, to be capable of performing to at least the standard required by the current fire safety schedule for the building for which the certificate is issued.

An interim fire safety certificate must be provided before an interim occupation certificate can be used for a building under Clause 153(2) of the Environmental Planning & Assessment Regulation 2000.

A final fire safety certificate must be provided before an interim occupation certificate can be used for a building under Clause 153(1) of the Environmental Planning & Assessment Regulation 2000.

A copy of the fire safety certificate and fire safety schedule shall be:

- i) Submitted to Strathfield Council;
- ii) Submitted to the Commissioner of the New South Wales Fire Brigade; and
- iii) Prominently displayed in the building.

(Reason: Fire safety and statutory requirement.)

73. LANDSCAPING - ARBORIST'S FOLLOW UP REPORT OF TREE/S TO BE RETAINED (OC)

As part of the on-going assessment of the tree/s to be retained, the consulting arborist engaged by the applicant is to assess their health and any impacts suffered by them as a result of the proposed approved development, prior to the issue of an Occupation Certificate. Findings are to be compiled in a detailed report and submitted to the Principle Certifying Authority, which documents the following:

- i) Methods of excavation or construction used to carry out the works;
- ii) Any damage sustained by the tree/s as a result of the works;
- iii) Any subsequent remedial works required to be carried out by the consulting arborist as a result of the damage; and
- iv) Any future or on-going remedial work required to be carried out to ensure the long term retention of the tree/s.

(Reason: To ensure the survival of trees to be retained.)

74. OCCUPATION OF BUILDING (OC)

A person must not commence occupation or use (or change of use where an existing building) of the whole or any part of a new building (within the meaning of section 109H (4) of the Act) unless an Interim Occupation Certificate or Final Occupation Certificate has been issued in relation to the building or part.

The Principal Certifying Authority is required to be satisfied, amongst other things, that:

- i) all required inspections (including each applicable mandatory critical stage inspection) have been carried out; and
- ii) any preconditions to the issue of the certificate required by a development consent

have been met.

Note: New building includes an altered portion of, or an extension to, an existing building.

(Reason: Statutory requirement.)

75. STORMWATER - CERTIFICATION OF THE CONSTRUCTED DRAINAGE SYSTEM (OC)

The constructed stormwater system shall be certified by a suitably qualified person, in accordance with Council's Stormwater Management Code, prior to the issue of any Occupation Certificate.

(Reason: Adequate stormwater management.)

76. STORMWATER - COVENANT AND RESTRICTION AS TO USER FOR STORMWATER CONTROLLED SYSTEMS (OC)

Prior to the issue of any Occupation Certificate, the applicant shall register a Positive Covenant and a Restriction as to User under section 88E and or section 88B of the Conveyancing Act as appropriate in favour of Council, ensuring the ongoing retention, maintenance and operation of the stormwater facility on-site detention and water sensitive urban design components.

Where any drainage line or service conduit is to traverse any property other than that which it serves, an appropriate easement will be required. In this case, the applicant shall register an easement no less than 1200mm wide over the proposed drainage line or service concurrently with any subdivision registration.

The wording on the 88B Instrument is to make reference to the Council file where the Construction plans and the Work As Executed (as built), plans are held. Typical wording can be obtained from Council's Specification for the Management of Stormwater document.

(Reason: To ensure the on-site detention and/or pump system is maintained to an appropriate operational standard.)

77. SUBDIVISION - EVIDENCE OF CONSOLIDATION (OC)

The existing allotments shall be consolidated into a single lot. Evidence that the plan of consolidation has been registered as a deposited plan with the Land and Property Information Office must be submitted to Council, prior to occupation of the site.

(Reason: Proper management of land.)

78. VENTILATION SYSTEMS – MECHANICAL (OC)

The mechanical ventilation system is to comply with the following:

- i) The Building Code of Australia;
- ii) Protection of the Environment Operations Act 1997; and
- iii) Australian Standard AS1668-1991.

In addition, odour control measures, such as activated carbon or catalytic oxidisers, must be used to treat ventilation gases prior to discharge. The method of odour control must be designed by a suitably qualified mechanical ventilation engineer.

At the completion of the installation of the mechanical exhaust ventilation system, a

certificate from a practising mechanical engineer shall be submitted to the Principal Certifying Authority, prior to issue of the Occupation Certificate demonstrating compliance with the above.

(Reason: To ensure the mechanical exhaust ventilation system complies with the relevant requirements/standards.)

79. VENTILATION SYSTEMS – NATURAL (OC)

The natural ventilation system shall be designed, constructed and installed in accordance with the provisions of:

- i) The Building Code of Australia; and
- ii) Protection of the Environment Operations Act 1997.

Details demonstrating compliance with this condition shall be submitted to the Principal Certifying Authority, prior to issue of the Occupation Certificate.

(Reason: To ensure any natural ventilation systems comply with the relevant regulations/standards.)

CONDITIONS TO BE SATISFIED PRIOR TO THE ISSUE OF A SUBDIVISION CERTIFICATE (SC)

80. COMMENCEMENT OF SUBDIVISION WORKS - REQUIREMENTS PRIOR TO (SC)

Subdivision work in accordance with a consent must not commence until:

- i) A Construction Certificate has been issued;
- ii) the person having the benefit of the development consent has appointed the Principal Certifying Authority (PCA);
- iii) The PCA (if not Council) has, no later than two (2) days before the subdivision work commences, notified the Council (or other consent authority where applicable) of the PCA's appointment; and
- iv) The person having the benefit of the consent has given at least two (2) day's notice to the Council of the person's intention to commence the subdivision work.

NB: Crown work certified in accordance with s109R of the Environmental Planning and Assessment Act 1979 is exempted from the above requirements.

(Reason: Statutory requirements.)

81. SEPARATE APPLICATION FOR STRATA SUBDIVISION (SC)

This consent does not imply approval to create a separate title, by subdivision or otherwise. Should it be intended to subdivide the approved development into strata title allotments, Council will require the lodgement of a separate development application for consideration.

(Reason: To ensure compliance with the consent.)

82. SUBDIVISION CERTIFICATE - REQUIREMENTS PRIOR TO THE ISSUE OF (SC)

A Subdivision Certificate allows a person to lodge a plan of subdivision with NSW Land and Property Information (LPI). The plan of subdivision identifies each of the allotments approved under the original consent (if required) or each allotment subject to an exempt boundary adjustment. The plan of subdivision is required to be prepared by a registered surveyor.

All types of subdivision (Torrens, Strata and Community Title) are required to be registered with NSW LPI before a new 'allotment' of a subdivision of land can be created.

The release of a Subdivision Certificate confirms that the Principal Certifying Authority (Council or Accredited Certifier) is satisfied that works are completed in accordance with the applicable Development Consent and that the land is suitable to occupy.

Prior to the issuing of any Subdivision Certificate under section 37A of the Strata Schemes (Freehold Development) Act 1973, and section 66A of the Strata Schemes (Leasehold Development) Act 1986, and in accordance with section 29A of the Strata Schemes (Freehold Development) Regulation 2007 and section 30A of the Strata Schemes (Leasehold Development) Regulation 2007, the PCA is required to be satisfied that:

- i) The floors, external walls and ceilings depicted in the proposed strata plan for the building correspond to those of the building as constructed;
- ii) The floors, external walls and ceilings of the building as constructed correspond to those depicted in the building plans that accompanied the construction certificate for the building; and
- iii) Any facilities required by the relevant development consent (such as parking spaces, terraces and courtyards) have been provided in accordance with those requirements.

As construction of the building nears completion, or after it has been completed, the Principal Certifying Authority must inspect the building and the common property areas around the building, so as to be satisfied, as required by section 66AA of the Act, that the above requirements have been met.

The Principal Certifying Authority shall also be satisfied that:

- i) All required inspections (including each applicable mandatory critical stage inspection) have been carried out; and
- ii) Any preconditions to the issue of the certificate required by a development consent or complying development certificate have been met.

The Subdivision Certificate must not be issued until the Principal Certifying Authority has issued the Final Occupation Certificate in relation to the approved development.

(Reason: Statutory requirements.)

83. SUBDIVISION - LODGEMENT OF FINAL PLAN OF SUBDIVISION (SC)

Once a Subdivision Certificate is issued by the Principal Certifying Authority, the Final Plan of Subdivision must be registered with Land and Property Information. Documentary evidence that the linen plan has been registered with Land and Property Information must be submitted to Strathfield Council as soon as practicable.

(Reason: Statutory requirement.)

84. SYDNEY WATER - SECTION 73 CERTIFICATE (SC)

A Section 73 Compliance Certificate under the Sydney Water Act 1994 must be obtained before the issue of the Subdivision Certificate. An application must be made through an authorised Water Servicing Coordinator (refer www.sydneywater.com.au).

Following receipt of the application a 'Notice of Requirements' will be issued detailing water

and sewer extensions to be built and charges to be paid. Please make early contact with the Water Servicing Coordinator, as building of water/sewer extensions can be time consuming and may impact on other services and building, driveway or landscape design.

Sydney Water written advice that you have obtained the Notice of Requirements must be submitted to the Principal Certifying Authority

The Section 73 Compliance Certificate must be submitted to the Principal Certifying Authority prior to release of the Subdivision Certificate /any occupation of the premises.

(Reason: To comply with the statutory requirements of Sydney Water.)

85. **UTILITIES - ELECTRICITY SUBSTATION DEDICATION AS ROAD AND/OR EASEMENT FOR ACCESS (SC)**

Where an electricity substation is provided on the site adjoining the road boundary, the area within which the electricity substation is located must be dedicated as public road, free of cost to Council. The size and location of the electricity substation is to be in accordance with the requirements of the appropriate energy authority and Council. The opening of any access doors shall not intrude onto any public road (footway or road pavement).

Where access to the electricity substation is required from a public place and across the site, an easement for access across the site from the public place must be created upon the final plan of subdivision burdening the subject site and benefiting the Crown in right of New South Wales and any Statutory Corporation requiring access to the electricity substation.

The above details must be included on the final plan of subdivision, prior to the release of the Subdivision Certificate.

(Reason: Formalisation of access to utility.)

CONDITIONS TO BE SATISFIED DURING ONGOING USE OF THE PREMISES (OU)

86. **VISITOR PARKING RESTRICTION (OU)**

All visitor parking spaces must not at any time be allocated sold or leased to an individual owner/occupier and must be strictly retained as common property by the Owners Corporation.

(Reason: Compliance with approved visitor parking provision.)

87. **VISITOR PARKING RESTRICTION (OU)**

All visitor parking spaces must not at any time be allocated sold or leased to an individual owner/occupier and must be strictly retained as common property by the Owners Corporation.

(Reason: Compliance with approved visitor parking provision.)

RESOLUTION

The application be **DEFERRED** to allow for the re-notification of the application so as to include the increase to the balcony on Level 6 (unit 51). In addition, Council write to the applicant requesting the payment of Notification Fees in accordance with Council's Schedule Fees and Charges.

FOR: S. Clements, K. Lindeberg, G. Andonoski

AGAINST: Nil

**** End Minutes - Report No. 3****

TO: Strathfield Internal Development Assessment Panel Meeting - 29 May 2020

REPORT: IDAP – Report No. 4

SUBJECT: DA2020/056: 40 MYRNA ROAD, STRATHFIELD
LOT 23 DP14613

DA NO. 2020/056

RECOMMENDATION

That Development Application No. 2020/056 for demolition of existing dwelling and construction of a new two (2) storey dwelling house at 40 Myrna Road, Strathfield be **APPROVED**, subject to the following conditions:

Revised Development Description to read as follows:

Development Description: *Demolition of existing dwelling and construction of a new two (2) storey dwelling house with front boundary fencing.*

GENERAL CONDITIONS (GC)

1. APPROVED PLANS AND REFERENCE DOCUMENTATION (GC)

The development, except where modified by a condition(s) of consent, is to be carried out in accordance with the following plans and reference documentation:

Plans affixed with Council's 'Development Consent' stamp relating to Development Consent No. 2020/056:

Drawing No.	Title/Description	Prepared by	Issue / Revision & Date	Date received by Council
AM_MYRNA 2135	Site Layout and Site Analysis Plan	RS Designs Sydney	Rev 3, 12 May 2020	15 May 2020
AM_MYRNA 2135	Ground Floor Plan	RS Designs Sydney	Rev 3, 12 May 2020	15 May 2020
AM_MYRNA 2135	First Floor Plan	RS Designs Sydney	Rev 3, 12 May 2020	15 May 2020
AM_MYRNA 2135	Roof Plan	RS Designs Sydney	Rev 3, 12 May 2020	15 May 2020
AM_MYRNA 2135	East and West Elevation Plan	RS Designs Sydney	Rev 3, 12 May 2020	15 May 2020
AM_MYRNA 2135	South Elevation Plan	RS Designs Sydney	Rev 3, 12 May 2020	15 May 2020
AM_MYRNA 2135	North Elevation Plan	RS Designs Sydney	Rev 3, 12 May 2020	15 May 2020
AM_MYRNA 2135	Section A-A Plan and Driveway Gradient	RS Designs Sydney	Rev 3, 12 May 2020	15 May 2020
AM_MYRNA 2135	Sediment Control Plan	RS Designs Sydney	Rev 3, 12 May 2020	15 May 2020
AM_MYRNA 2135	Landscape Concept Plan	RS Designs Sydney	Rev 3, 12 May 2020	15 May 2020
AM_MYRNA 2135	Window Schedule	RS Designs Sydney	Rev 3, 12 May 2020	15 May 2020
AM_MYRNA	Colour Scheme	RS Designs	Rev 3, 12 May	15 May 2020

MINUTES

2135		Sydney	2020	
AM_MYRNA 2135	Front Fence Elevation and Section Plan	RS Designs Sydney	Rev 3, 12 May 2020	15 May 2020
Sheet 1	Stormwater Plan	Meares Consulting	Rev B	23 March 2020
Sheet 2	Stormwater Plan	Meares Consulting	Rev B	23 March 2020

Reference Documentation affixed with Council's 'Development Consent' stamp relating to Development Consent No. 2020/056:

Title / Description	Prepared by	Issue/Revision & Date	Date received by Council
BASIX	-	Cert No.1086 159S, issued 19 March 2020	23 March 2020
Arboriculture Impact Assessment Report	The Tree MD	10 January 2019	23 March 2020
Drainage Design Certification	Meares Consulting	2 March 2020	23 March 2020
Structural Design Certification	Meares Consulting	2 March 2020	23 March 2020
Waste Management Plan	Meares Consulting	-	23 March 2020

In the event of any inconsistency, the conditions of this consent shall prevail.

(Reason: To ensure that the form of the development undertaken is in accordance with the determination of Council.)

2. **BUILDING HEIGHT - MAXIMUM RL TO BE COMPLIED WITH (GC)**

The height of the building measured from Australian Height Datum (AHD) must not exceed Relative Level (RL) 36.921AHD to the roof ridge of the building.

(Reason: To ensure the approved building height is complied with.)

3. **CONSTRUCTION HOURS (GC)**

No construction or any other work related activities shall be carried out on the site outside the hours of 7.00 am to 5.00 pm Mondays to Fridays and 8am to 1pm Saturdays.

No building activities are to be carried out at any time on a Sunday or public holiday.

Where the development involves the use of jackhammers/rock breakers and the like or other heavy machinery, such equipment may only be used between the hours of 7.00 am - 5.00 pm Monday to Friday only.

(Reason: To maintain amenity to adjoining land owners.)

4. **CONSTRUCTION WITHIN BOUNDARIES (GC)**

The development including but not limited to footings, walls, roof barges and guttering must be constructed wholly within the boundary of the premises. No portion of the proposed

structure shall encroach onto the adjoining properties. Gates must be installed so they do not open onto any footpath or adjoining land.

(Reason: Approved works are to be contained wholly within the subject site.)

5. DEMOLITION – GENERALLY (GC)

Alteration and demolition of the existing building is limited to that documented on the approved plans (by way of notation). No approval is given or implied for removal and/or rebuilding of any portion of the existing building which is not shown to be altered or demolished.

(Reason: To ensure compliance with the approved development.)

6. DEMOLITION - SITE SAFETY FENCING (GC)

Site fencing is to be erected to a minimum height of 1.8m complying with WorkCover Guidelines, to exclude public access to the site, prior to any demolition works occurring and maintained for the duration of the demolition works.

If applicable, a separate Hoarding Application for the erection of an A class (fence type) or B class (overhead type) hoarding/fencing along the street frontage(s) complying with WorkCover requirements must be obtained including:

- payment to Council of a footpath occupancy fee based on the area of footpath to be occupied and Council's Schedule of Fees and Charges before the commencement of work; and
- provision of a Public Risk Insurance Policy with a minimum cover of \$10 million in relation to the occupation of and works within Council's road reserve, for the full duration of the proposed works, must be obtained with a copy provided to Council.

(Reasons: Statutory requirement and health and safety.)

7. LANDSCAPING - CANOPY TREES IN FRONT SETBACK (GC)

The development shall provide a new jacaranda tree planting in the front setback of the site. The tree shall be a minimum 200 litres at the time of planting.

Compliance with this condition is to be demonstrated to the Principal Certifying Authority, prior to the issue of any Occupation Certificate.

(Reason: To ensure the landscape character of the locality is maintained.)

8. ENVIRONMENTAL PROTECTION – TREE (GC)

All street trees and trees on private property that are protected under Council's controls, shall be retained except where Council's prior written consent has been obtained. The felling, lopping, topping, ringbarking, wilful destruction or removal of any tree/s unless in conformity with this approval or subsequent approval is prohibited.

All healthy trees and shrubs identified for retention on the approved drawings are to be suitably protected in accordance with Section 4, Tree protection measures, and Appendix C Tree Protection Zone Sign, of Australian Standard AS4970 - 2009, Protection of Trees on Development Sites, prior to the commencement of any works (including any demolition and excavation) and maintained for the duration of the works.

In this regard the street tree and all protected trees on or adjacent to the site will be protected as described below;

- i. A Tree Protection (Management) Plan prepared by a AQF Level 5 Arborist is to be available on site at all times prior to the issue of the Construction Certificate, for all demolition and site works. This Tree Protection (Management) Plan must be shown on the demand of Authorised Council staff.
- ii. Protective perimeter fencing must be consistent with AS 4687, using metal fence posts greater than 20mm diameter and solid or chain wire mesh 2 metres in height supported on concrete pads/feet at 2-2.5 metre spacing. Fencing placement should not be closer than 2.5 metres from the trunk of each protected tree, or at a distance as specified by the approved Tree Protection (Management) Plan and approved by Council's Tree Management Officer. Shade cloth is to be used to prevent entry of dust and contaminated liquids into the root protection area.
- iii. Signs must be placed on the Fencing. These signs must comply with AS1319. The signs must state the purpose of the fencing and the name and contact details of the builder and the appointed AQF Level 5 consultant arborist.
- iv. Root protection is to be provided in the form of mulching to a depth of 50-100mm, inside of the fenced tree protection zone.
- v. Ground (Root) Trunk and Branch Protection must comply with the diagram of Figure 4 of AS4970 – 2009. Ground protection within the tree protection zone and drip line should be in the form of heavy steel plates or timber rumble boards over mulch or aggregate. Trunk and branch protection should be to a minimum height of 2 metres and must include measures to protect the tree/s against damage from the movement of trucks, plant equipment and materials at greater heights above ground level.
- vi. Temporary signs, cables, wires must not be attached to, or suspended, on any street tree or protected tree.
- vii. Above ground utilities must not be placed within the canopy of an existing protected tree, or create the future need for clearance pruning.
- viii. Below ground utilities/services must not be located inside the fenced tree protection zone.
- ix. Scaffolding must not be located in the fenced tree protection zone unless authorised by the approved Tree Protection (Management) Plan and Council's Tree Management Officer
- x. Council must be notified in writing within 24 hours, for all temporary removal of the tree protection fencing ground (root) trunk and branch protection within the root protection area.
- xi. Pruning of a street tree is prohibited without the written consent of Council.

(Reason: To ensure the protection of trees to be retained on the site.)

9. **MATERIALS – CONSISTENT WITH SUBMITTED SCHEDULE (GC)**

All external materials, finishes and colours are to be consistent with the schedule submitted and approved by Council with the development application.

(Reason: To ensure compliance with this consent.)

10. **PRINCIPAL CERTIFYING AUTHORITY (PCA) IDENTIFICATION SIGN (GC)**

Prior to commencement of any work, signage must be erected in a prominent position on the work site identifying:

- i) The Principal Certifying Authority (PCA) by showing the name, address and telephone number of the PCA;
- ii) The Principal Contractor by showing the Principal Contractor's name, address and telephone number (outside of work hours) for that person; and
- iii) The sign must state that unauthorised entry to the work site is prohibited.

Any such sign is to be maintained while the work is being carried out, but must be removed when the work has been completed.

This clause does not apply to building work, subdivision work or demolition work that is carried out inside an existing building that does not affect the external walls of the building.

(Reason: Statutory requirement.)

11. **SITE MANAGEMENT (DURING DEMOLITION AND CONSTRUCTION WORKS)**

All of the following are to be satisfied/complied with during demolition, construction and any other site works:

- i) All demolition is to be carried out in accordance with Australian Standard AS 2601-2001.
- ii) Demolition must be carried out by a registered demolition contractor.
- iii) A single entrance is permitted to service the site for demolition and construction. Protection pads are to be installed to the kerb, gutter and nature strip where trucks and vehicles enter the site.
- iv) No blasting is to be carried out at any time during construction of the building.
- v) Care must be taken during demolition/ excavation/ building/ construction to prevent any damage to adjoining buildings.
- vi) Adjoining owner property rights and the need for owner's permission must be observed at all times, including the entering onto land for the purpose of undertaking works.
- vii) Any demolition and excess construction materials are to be recycled wherever practicable.
- viii) The disposal of construction and demolition waste must be in accordance with the requirements of the Protection of the Environment Operations Act 1997.
- ix) All waste on the site is to be stored, handled and disposed of in such a manner as to not create air pollution (including odour), offensive noise or pollution of land and/or water as defined by the Protection of the Environment Operations Act 1997. All excavated material should be removed from the site in an approved manner and be disposed of lawfully to a tip or other authorised disposal area.
- x) All waste must be contained entirely within the site.
- xi) A site plan including temporary waste storage locations, construction material storage areas and vehicular access to and from the site must be included with application.
- xii) Section 143 of the Protection of the Environment Operations Act 1997 requires waste to be transported to a place which can lawfully accept it. All non-recyclable demolition materials are to be disposed of at an approved waste disposal depot in accordance with legislation.
- xiii) Details as to the method and location of disposal of demolition materials (weight dockets, receipts, etc.) should be kept on site as evidence of approved methods of disposal or recycling and must be presented to Council and/or Principal Certifying Authority upon request.
- xiv) All materials on site or being delivered to the site are to generally be contained within the site. The requirements of the Protection of the Environment Operations Act 1997 must be complied with when placing/stockpiling loose material, disposing of concrete

- waste, or other activities likely to pollute drains or water courses.
- xv) Any materials stored on site must be stored out of view or in such a manner so as not to cause unsightliness when viewed from nearby lands or roadways.
 - xvi) Public footways, include nature strips and roadways adjacent to the site must be maintained and cleared of obstructions during construction. No building materials, waste containers or skips may be stored on the road reserve or footpath without prior separate approval from Council, including payment of relevant fees.
 - xvii) Building operations such as brick-cutting, washing tools or paint brushes, and mixing mortar not be performed on the roadway or public footway or any other locations which could lead to the discharge of materials into the stormwater drainage system.
 - xviii) All site waters during excavation and construction must be contained on site in an approved manner to avoid pollutants entering into waterways or Council's stormwater drainage system.
 - xix) Any work must not prohibit or divert any natural overland flow of water.
 - xx) Toilet facilities for employees must be provided in accordance with WorkCover NSW.

(Reason: To ensure that demolition, building and any other site works are undertaken in accordance with relevant legislation and policy and in a manner which will be non-disruptive to the local area.)

12. **STORMWATER MANAGEMENT PLAN - CERTIFICATION REQUIREMENT (GC)**

A detailed Stormwater Management Plan (SWMP) in line with Council's Stormwater Management Code is to be prepared and certified by an Accredited Civil/Hydraulic Engineer and submitted to the Principal Certifying Authority and Council, prior to the issue of a Construction Certificate. The SWMP is to be based on the approved development as modified by any conditions of consent.

(Reason: To ensure appropriate provision is made for the disposal and management of stormwater generated by the development, and to ensure public infrastructure in Council's care and control is not overloaded.)

13. **SYDNEY WATER - TAP IN™ (GC)**

The approved plans must be submitted to a Sydney Water Tap in™ to determine whether the development application will affect Sydney Water's sewer and water mains, stormwater drains and/or easements, and if further requirements need to be met. The approved plans will be appropriately endorsed. For details please refer to 'Plumbing, building and developing' section of Sydney Water's web site at www.sydneywater.com.au then see 'Building', or telephone 13000 TAP IN (1300 082 746). The Certifying Authority must ensure that a Tap in™ agent has appropriately stamped the plans prior to the issue of the Construction Certificate.

(Reason: Compliance with Sydney Water requirements.)

14. **UTILITIES AND SERVICES - PROTECTION OF (GC)**

Any footings or excavation to be located or undertaken adjacent to Council's stormwater must be designed to address the following requirements:

- i) All footings and excavation must be located wholly within the site and clear of any easement boundaries;
- ii) All footings and excavation must be located a minimum of 1000mm from the centreline of the pipeline or 500mm from the outside of the pipeline, whichever is the greater distance from the centreline; and
- iii) Footings must extend to at least the depth of the invert of the pipeline unless the

footings are to be placed on competent bedrock.

If permanent excavation is proposed beneath the obvert of the pipeline, suitable means to protect the excavation and proposed retaining structures from seepage or other water flow from the pipeline and surrounding subsoil, must be provided. The design must be prepared by a qualified practicing Structural/Civil Engineer.

Construction plans must be approved by the appropriate utility's office (e.g. council, Sydney Water Corporation) to demonstrate that the development complies with the utility's requirements.

The applicant must provide written evidence (e.g. compliance certificate, formal advice) of compliance with the requirements of all relevant utility providers (e.g. Water, Energy, Telecommunications, Gas).

(Reason: To ensure protection of Council assets.)

CONDITIONS TO BE SATISFIED PRIOR TO THE ISSUE OF A CONSTRUCTION CERTIFICATE (PCC)

15. BASIX COMMITMENTS (CC)

The approved BASIX Certificate shall be submitted to the Principal Certifying Authority with the application for a Construction Certificate.

Where a change or changes are proposed in the BASIX commitments, the applicant must submit a new BASIX Certificate to the Principal Certifying Authority and Council. If any proposed change in the BASIX commitments is inconsistent with the development consent the applicant will be required to submit a modification to the development consent to Council under Section 4.55 of the Environmental Planning and Assessment Act 1979.

All commitments in the BASIX Certificate must be shown on the plans accompanying the Construction Certificate.

(Reason: Statutory compliance.)

16. BUILDING CODE OF AUSTRALIA - COMPLIANCE WITH (CC)

All architectural drawings, specifications and related documentation shall comply with the Building Code of Australia (BCA). All work must be carried out in accordance with the requirements of the Building Code of Australia (BCA).

In the case of residential building work for which the Home Building Act 1989 requires there to be a contract of insurance in force in accordance with Part 6 of that Act, such a contract of insurance is to be in force before any building work authorised to be carried out by the consent commences.

Details demonstrating compliance with this condition are to be submitted to the Principle Certifying Authority, prior to issue of the Construction Certificate.

(Reason: This is a 'prescribed' condition under clause 98(1) of the Environmental Planning and Assessment Regulation 2000.)

17. CAR PARKING - COMPLIANCE WITH AS/NZS 2890.1:2004 (CC)

Car parking dimensions must comply with the Australian/New Zealand Standard AS/NZS

2890.1:2004 - Parking facilities - Off-street car parking. Details demonstrating compliance are to be submitted to the Principal Certifying Authority, prior to the issue of a Construction Certificate.

(Reason: To ensure compliance with Australian Standards relating to parking of vehicles.)

18. CAR PARKING - VEHICULAR CROSSING WIDTH AT PROPERTY BOUNDARY (CC)

Vehicular crossings are to have a maximum width of 3m at the property boundary. Details demonstrating compliance are to be submitted to the Principal Certifying Authority, prior to the issue of a Construction Certificate.

The vehicular crossing (and all associated excavation works) must not be constructed closer than 2 metres from a retained protected street tree.

(Reason: Compliance with SCDCP 2005.)

19. COMMENCEMENT OF WORKS (NO WORKS UNTIL A CC IS OBTAINED)

Building work, demolition or excavation must not be carried out until a Construction Certificate has been issued by either Strathfield Council or a Principal Certifying Authority.

Demolition of any part of a building triggers 'commencement of erection of building' pursuant of section 4.19 of the EP&A Act 1979. Accordingly, demolition works must not commence until a Construction Certificate has been issued, a Principal Certifying Authority has been appointed and a Notice of Commencement has been issued.

(Reason: To ensure compliance with statutory provisions.)

20. CONSTRUCTION AND ENVIRONMENTAL MANAGEMENT PLAN (CC)

The applicant must prepare and submit a Construction and Environmental Management Plan (CEMP) to the Principal Certifying Authority, including:

- i) Detailed information on any approvals required from other authorities prior to or during construction.
- ii) Traffic management, including details of:
 - ingress and egress of vehicles to the site;
 - management of loading and unloading of materials;
 - the location of heavy vehicle parking off-site; and
 - designated routes for vehicles to the site.
- iii) The proposed areas within the site to be used for a builder's site office and amenities, the storage of excavated material, construction materials and waste containers during the construction period.
- iv) Erosion and sediment control, detailing measures and procedures consistent with the requirements of Council's guidelines for managing stormwater, including:
 - the collection and treatment of stormwater and wastewater generated on site prior to discharge; and
 - procedures to prevent run-off of solid material and waste from the site.
- v) Waste management, including:
 - details of the types and estimated volumes of waste materials that will be generated;
 - procedures for maximising reuse and recycling of construction materials; and
 - details of the off-site disposal or recycling facilities for construction waste.
- vi) Dust control, outlining measures to minimise the generation and off-site transmission

of dust and fine particles, such as watering or damp cloth fences.

- vii) A soil and water management plan, which includes:
- measures to minimise the area of soils exposed at any one time and conserve top soil;
 - identification and protection of proposed stockpile locations;
 - preservation of existing vegetation and revegetation;
 - measures to prevent soil, sand, sediments leaving the site in an uncontrolled manner;
 - measures to control surface water flows through the site in a manner that diverts clean run-off around disturbed areas, minimises slope gradient and flow distance within disturbed areas, ensures surface run-off occurs at non-erodible velocities, and ensures disturbed areas are promptly rehabilitated;
 - details of sediment and erosion control measures in place before work commences;
 - measures to ensure materials are not tracked onto the road by vehicles entering or leaving the site; and
 - details of drainage to protect and drain the site during works.
- viii) Asbestos management procedures:
- Anyone who removes, repairs or disturbs bonded or a friable asbestos material must hold a current removal licence from Workcover NSW holding either a Friable (Class A) or a Non- Friable (Class B) Asbestos Removal License which ever applies and a current WorkCover Demolition License where works involve demolition. To find a licensed asbestos removalist please see www.workcover.nsw.gov.au
 - Removal of asbestos by a person who does not hold a Class A or Class B asbestos removal license is permitted if the asbestos being removed is 10m² or less of non-friable asbestos (approximately the size of a small bathroom). Friable asbestos materials must only be removed by a person who holds a current Class A asbestos license.
 - Before starting work, a work site-specific permit approving each asbestos project must be obtained from WorkCover NSW. A permit will not be granted without a current WorkCover licence. All removal, repair or disturbance of or to asbestos material must comply with the following:
 - The Work Health and Safety Act 2011;
 - The Work Health and Safety Regulation 2011;
 - How to Safety Remove Asbestos Code of Practice – WorkCover 2011; and
 - Safe Work Australia Code of Practice for the Management and Control of Asbestos in the Workplace.
 - Following completion of asbestos removal works undertaken by a licensed asbestos removalist re-occupation of a workplace must not occur until an independent and suitably licensed asbestos removalist undertakes a clearance inspection and issues a clearance certificate.
 - The developer or demolition contractor must notify adjoining residents at least two (2) working days (i.e. Monday to Friday exclusive of public holidays) prior to the commencement of asbestos removal works. Notification is to include, at a minimum:
 - the date and time when asbestos removal works will commence;
 - the name, address and business hours contact telephone number of the demolisher, contractor and/or developer;
 - the full name and license number of the asbestos removalist/s; and
 - the telephone number of WorkCover's Hotline 13 10 50
 - warning signs informing all people nearby that asbestos removal work is taking place in the area. Signs should be placed at all of the main entry points to the asbestos removal work area where asbestos is present. These signs should be weatherproof, constructed of light-weight material and

adequately secured so they remain in prominent locations. The signs should be in accordance with AS 1319-1994 Safety signs for the occupational environment for size, illumination, location and maintenance; and

- appropriate barricades installed as appropriate to prevent public access and prevent the escape of asbestos fibres. Barricades must be installed prior to the commencement of asbestos removal works and remain in place until works are completed.

(Reason: Safety, amenity and protection of public infrastructure and the environment.)

21. **COUNCIL PERMITS – FOR ALL ACTIVITIES ON COUNCIL LAND (CC)**

Works Permit

(as per Section 68 of the Local Government Act 1993 and Section 138 and 139 of the Roads Act 1993)

A Works Permit is required for construction of a vehicular crossing (driveway), new stormwater down pipe connection to kerb and gutter, new footpath and/or stormwater connection. A Works Permit Application Form is available from Council's Customer Centre or can be downloaded from Council's website. The applicable fees and charges are located on Council's website.

Standing Plant Permit

This permit must be applied for where it is intended to park a concrete pump, crane or other plant on the roadway or footpath. A Standing Plant Permit Application Form is available from Council's Customer Centre or can be downloaded from Council's website. The applicable fees and charges are located on Council's website. Please note a Road Closure Permit is not required for standing plant.

Skip Bin Permit

This permit must be applied for if you intend to place a skip bin on the roadway or footpath. A Skip Bin Application Form is available from Council's Customer Centre or can be downloaded from Council's website. The applicable fees and charges are located on Council's website.

Temporary Full or Part Road Closure Permit

This permit must be applied for if you require a full or a part road closure to take place to assist in your construction works. Please use the Works Permit Application Form, which is available from Council's Customer Service Centre or can be downloaded from Council's website. The applicable fees and charges are located on Council's website. Please note a Road Closure Permit is not required for standing plant.

Hoarding/Fencing Permit

This permit must be applied for if you intend to erect a Class A (fence type) or Class B (overhead type) hoarding/fencing along the street frontage(s). A Hoarding Permit Application Form is available from Council's Customer Service Centre or can be downloaded from Council's website. The applicable fees and charges are located on Council's website.

Work Zone Permit

This permit must be applied for if you require permanent parking along the kerbside at the front of the site during construction works. A Work Zone Permit Application Form is available from Council's Customer Service Centre or can be downloaded from Council's website. The applicable fees and charges are located on Council's website.

Ground Anchoring Permit

This permit must be applied for, for the installation of ground anchors under Council's footway/road reserve. It does not cover ground anchors under private properties. A separate approval is required to be obtained from Roads and Maritime Services (RMS) if it is proposed to install ground anchors under a State or Classified Regional Road (please refer to the end of this application form for more information).

(Reason: Council requirement.)

22. LANDSCAPING - MAINTENANCE STRATEGY (CC)

To ensure the survival of landscaping following works, a landscape maintenance strategy for the owner/occupier to administer over a 12 month establishment period following the issue of the Occupation Certificate shall be prepared and provided to the satisfaction of the Principal Certifying Authority with the Construction Certificate application. The strategy is to address maintenance issues such as, but not limited to plant survival, irrigation, soil testing, weeding, staking, fertilizing, remedial pruning and plant replacement.

(Reason: Ensure landscape survival.)

23. PRIVACY - OBSCURE GLAZING IN WET AREAS (CC)

All bathroom, ensuite and toilet windows shall be installed with obscure glazing. Plans shall be notated accordingly and details demonstrating compliance submitted to the Principal Certifying Authority, prior to the issue of a Construction Certificate.

(Reason: Privacy amenity.)

24. SECTION 7.12 CONTRIBUTION PAYMENT - INDIRECT CONTRIBUTIONS PLAN) (CC)

In accordance with the provisions of Section 7.13 of the Environmental Planning and Assessment Act 1979 and the Strathfield Indirect Development Contributions Plan 2010-2030, a contribution in the form of cash, cheque or credit card (financial transaction fee applies) shall be paid to Council for the following purposes:

Local Amenity Improvement Levy	\$9,000.00
--------------------------------	-------------------

The total amount of the contribution is valid as at the date of determination and is subject to quarterly indexation. The amount of the contribution under this condition shall be indexed in accordance with clause 4.12 of the Strathfield Indirect Development Contributions Plan 2010-2030.

Contributions must be receipted by Council and submitted to the Accredited Certifier, prior to the issue of any Construction Certificate.

A copy of this condition is to be presented to Council's Customer Service Centre when paying the contribution so that it can be recalculated.

Note: A copy of Strathfield Council's Section 7.12 Indirect Development Contributions Plan may be downloaded from Council's website.

(Reason: To enable the provision of public amenities and services required/anticipated as a consequence of increased demand resulting from the development.)

25. STORMWATER - RAINWATER RE-USE (CC)

A rainwater re-use system shall be provided in accordance with either the BASIX minimum requirements, any relevant Council Rainwater Policy and/or specification of the management of stormwater, whichever is applicable. A detailed stormwater plan showing the proposed re-use system shall be submitted to and approved by the Principal Certifying Authority, prior to the issue of a Construction Certificate.

(Reason: Compliance and amenity.)

26. TREE BONDS (CC)

A tree bond of **\$10,000.00** (calculated in accordance with Council's adopted Fees and Charges) shall be paid to Council, prior to the issue of a Construction Certificate.

The deposit is required as security against any damage to existing trees to be retained on Council's road reserve, during works on the site. The applicant must bear the cost of all restoration works to Council's property damaged during the course of this development.

Payment may be accepted in the form of cash, bank guarantee, cheque or credit card (financial transactions fees apply). Note: Additional fees apply for the lodgement of a bank guarantee in lieu of cash bond applies in accordance with Council's adopted Fees and Charges.

A refund of the Tree Bond must be made in writing.

Tree Bonds may be forfeited if a tree is dead, made dangerous or has been terminally damaged, or will be held until tree/s have fully recovered from the construction damage or were replacement/planted trees have become fully established and are over 6 metres in height.

(Reason: To ensure the protection of trees to be retained on Council's Road Reserve.)

27. WATER SUSTAINABILITY – GENERALLY (CC)

Water collected in the rainwater tank must comprise roof water only and not surface water. Water from the rainwater tank must only be used for following purposes and not for human consumption:

- i) Toilet flushing;
- ii) Clothes washing;
- iii) Garden irrigation;
- iv) Car washing and similar outdoor uses;
- v) Filling swimming pools, spa pools and ornamental ponds; and
- vi) Fire fighting.

(Reason: To promote sustainable water management practice.)

28. WATER HEATING SYSTEMS - LOCATION OF (CC)

Water heating systems shall be located so as not to be visible from public places and the ground level of adjoining properties. Details (type and location) of the water heaters shall be submitted to and approved by the Principal Certifying Authority, prior to the issue of a Construction Certificate.

(Reason: To maintain streetscape character.)

CONDITIONS TO BE SATISFIED PRIOR TO THE COMMENCEMENT OF WORKS (PCW)

29. APPOINTMENT OF A PRINCIPAL CERTIFYING AUTHORITY (PCA) (CW)

No work shall commence in connection with this Development Consent until:

- i) A construction certificate for the building work has been issued by the consent authority or a Principal Certifying Authority.
- ii) The person having the benefit of the development consent has appointed a principal certifying authority for the building work, and notified the principal certifying authority that the person will carry out the building work as an owner/builder, if that is the case.
- iii) The principal certifying authority has, no later than 2 days before the building work commences:
 - notified the Council of his or her appointment, and
 - notified the person having the benefit of the development consent of any critical stage inspections and other inspections that are to be carried out in respect of the building work.
- iv) The person having the benefit of the development consent, if not carrying out the work as an owner-builder, has:
 - appointed a principal contractor for the building work who must be the holder of a contractor licence if any residential building work is involved;
 - notified the principal certifying authority of such appointment; and
 - unless that person is the principal contractor, notified the principal contractor of any critical stage inspections and other inspections that are to be carried out in respect of the building work.
- v) The person having the benefit of the development consent has given at least 2 days' notice to the Council of the person's intention to commence the erection of the building.

Note: If the principal certifying authority is the Council, the nomination will be subject to the payment of a fee for the service to cover the cost of undertaking all necessary inspections and the issue of the appropriate certificates.

Under the Environment Planning and Assessment (Quality of Construction) Act, 2003, a sign must be erected in a prominent position on the work site showing the name, address and telephone number of the principal certifying authority; the name of the principal contractor (if any) for the building work and a telephone number at which that person may be contacted outside working hours. That sign must also state that unauthorised entry is prohibited. The sign must not be removed until all work has been completed.

(Reason: Statutory requirement.)

30. HOME BUILDING COMPENSATION FUND (CW)

No residential building work within the meaning of the Home Building Act 1989 may commence until:

- i) A contract of insurance in accordance with Part 6 of the Home Building Act 1989 is entered into and in force, where such a contract is required under that Act (this is a prescribed condition of consent pursuant to clause 981(b) Environmental Planning and Assessment Regulation 2000.
- ii) The PCA is satisfied that the principal contractor for the work is the holder of the appropriate licence and is covered by the appropriate insurance, in each case if required by the Home Building Act 1989 (unless the work is to be carried out by an owner-builder).
- iii) If the work is to be carried out by an owner builder, that the owner builder is the

- holder of any owner -builder permit required under the Home Building Act 1989.
- iv) Written notice of the following information has been provided to Council (this is a prescribed condition of consent pursuant to clause 98B of the Environmental Planning and Assessment Regulation 2000):
- In the case of work for which a principal contractor is required to be appointed:
 - the name and licence number of the principal contractor; and
 - the name of the insurer by which the work is insured under Part 6 of the Home Building Act 1989.
- In the case of work to be done by an owner-builder:
- the name of the owner-builder; and
 - if the owner-builder is required to hold an owner-builder permit under the Home Building Act 1989, the number of the owner-builder permits.

Where Council is not the PCA, the PCA is responsible for notifying Council of the above matters.

Note: Where arrangements for doing residential building work change while the work is in progress so that the above information becomes out of date, the PCA (where not the Council) must provide Council with written notice of the updated information.

(Reason: Statutory requirement.)

31. NOTICE OF COMMENCEMENT (CW)

No work shall commence until the following details are submitted to Council:

- A Notice of Commencement (form will be attached with issue of a Construction Certificate or available from our website) within two (2) days of the date on which it is proposed to commence works associated with the Development Consent;
- Details of the appointment of a Principal Certifying Authority (either Council or another Principal Certifying Authority); and
- Details of the name, address and licence details of the Builder.

(Reason: Statutory requirement.)

CONDITIONS TO BE SATISFIED DURING DEMOLITION AND BUILDING WORKS (DBW)

32. FILL MATERIAL (DW)

The only waste derived material which may be received at the development site is:

- Virgin excavated material (within the meaning of the Protection of the Environment Operations Act 1997), and
- any other waste-derived material the subject of a resource recovery exemption under cl.51A of the Protection of the Environment Operations (Waste) Regulation 2005 that is permitted to be used as fill material.

Any (b)-type material received at the development site must be accompanied by documentation certifying by an appropriately qualified environmental consultant the materials compliance with the exemption conditions; and this documentation must be provided to the Principal Certifying Authority on request.

(Reason: To ensure imported fill is of an acceptable standard for environmental protection purposes.)

33. OBSTRUCTION OF PUBLIC WAY NOT PERMITTED DURING WORKS (DW)

The public way must not be obstructed by any materials, vehicles, refuse, skips or the like, under any circumstances, without the prior approval of Council.

(Reason: To maintain public access and safety.)

34. PUBLIC INFRASTRUCTURE AND SERVICES (DW)

The applicant must comply with the requirements (including financial costs) of any relevant utility provider (e.g. Energy Australia, Sydney Water, Telstra, RMS, Council etc.) in relation to any connections, works, repairs, relocation, replacements and/or adjustments to public infrastructure or services affected by the development.

(Reason: To maintain public infrastructure and/or services.)

35. SURVEY REPORT OF APPROVED LEVELS DURING AND POST CONSTRUCTION (DW)

A Survey Certificate to Australian Height Datum shall be prepared by a Registered Surveyor as follows:

- i) At the completion of the first structural floor level prior to the pouring of concrete indicating the level of that floor and the relationship of the building to the boundaries.
- ii) At the completed height of the building, prior to the placement of concrete inform work, or the laying of roofing materials.
- iii) At the completion of the development.

Progress certificates in response to points (1) through to (3) shall be provided to the Principal Certifying Authority at the time of carrying out relevant progress inspections. Under no circumstances is work allowed to proceed until such survey information is submitted to and approved by the Principal Certifying Authority.

(Reason: To ensure compliance with the approved plans.)

CONDITIONS TO BE SATISFIED PRIOR TO THE ISSUE OF AN OCCUPATION CERTIFICATE (POC)

36. CAR PARKING - SURPLUS VEHICULAR CROSSINGS (OC)

All surplus vehicular crossings and/or kerb laybacks must be removed and reinstated with concrete kerb and gutter or to the existing edging profile as specified by Council. The nature strip is to be restored and the footpath area reinstated. All of the above are to be restored to the satisfaction of Council's Engineer and at full cost to the applicant, prior to the issue of any Occupation Certificate.

(Reason: Maintenance of public infrastructure.)

37. ENGINEERING WORKS (CERTIFICATION OF)

Prior to occupation of the premises, a Work As Executed (WAE) Plan of all engineering and/or drainage works is to be submitted to the Principal Certifying Authority. The WAE Plan is to be certified by an Accredited Civil/Hydraulic Engineer demonstrating that:

- i) The stormwater drainage system; and/or
- ii) The car parking arrangement and area; and/or
- iii) Any related footpath crossing works; and/or
- iv) The proposed basement pump and well system; and/or

- v) The proposed driveway and layback; and/or
- vi) Any other civil works

have been constructed in accordance with the approved plans and any relevant Standards and Council policies/specifications.

For major works, such as subdivisions, works within the road reserve (requiring separate S138 approval) and as where specified by Council, a Part 4A Certificate will be required. It is strongly recommended that an Engineer supervise all engineering related works.

Where Council is not the Principal Certifying Authority, an electronic copy of the above documents is to be provided to Council, prior to the issue of any Occupation Certificate.

(Reason: Asset management.)

38. **OCCUPATION OF BUILDING (OC)**

A person must not commence occupation or use (or change of use where an existing building) of the whole or any part of a new building (within the meaning of section 109H (4) of the Act) unless an Interim Occupation Certificate or Final Occupation Certificate has been issued in relation to the building or part.

The Principal Certifying Authority is required to be satisfied, amongst other things, that:

- i) All required inspections (including each applicable mandatory critical stage inspection) have been carried out; and
- ii) Any preconditions to the issue of the certificate required by a development consent have been met.

Note: New building includes an altered portion of, or an extension to, an existing building.

(Reason: Statutory requirement.)

39. **RAINWATER TANKS (OC)**

Rainwater tanks must be installed on residential properties by a suitably qualified and licensed plumber and in accordance with the following:

- i) Australian/New Zealand Standard AS/NZS 3500:2003;
- ii) NSW Code of Practice Plumbing and Drainage, 2006 produced by Committee on Uniformity of Plumbing and Drainage Regulations in NSW (CUPDR); and
- iii) Council's rainwater tank policy.

Details demonstrating compliance with this condition are to be submitted to the Principal Certifying Authority, prior to the issue of any Occupation Certificate.

(Reason: To protect public health and amenity.)

40. **STORMWATER - CERTIFICATION OF THE CONSTRUCTED DRAINAGE SYSTEM (OC)**

The constructed stormwater system shall be certified by a suitably qualified person, in accordance with Council's Stormwater Management Code, prior to the issue of any Occupation Certificate.

(Reason: Adequate stormwater management.)

RESOLUTION

The application be **APPROVED** subject to the recommended conditions and the addition of Condition 24A to read as follows:

24A. SECURITY PAYMENT - DAMAGE DEPOSIT FOR COUNCIL INFRASTRUCTURE (CC)

A security (damage deposit) of **\$12,200** (calculated in accordance with Council's adopted Fees and Charges) shall be paid to Council, prior to the issue of a Construction Certificate.

The deposit is required as security against any damage to Council property during works on the site. The applicant must bear the cost of all restoration works to Council's property damaged during the course of this development. All building work must be carried out in accordance with the Building Code of Australia.

Payment may be accepted in the form of cash, bank guarantee, cheque or credit card (financial transactions fees apply). Note: Additional fees apply for the lodgement of a bank guarantee in lieu of cash bond applies in accordance with Council's adopted Fees and Charges.

Any costs associated with works necessary to be carried out to rectify any damages caused by the development, shall be deducted from the Damage Deposit.

Note: Should Council property adjoining the site be defective e.g. cracked footpath, broken kerb etc., this should be reported in writing, or by photographic record, submitted to Council at least seven (7) days prior to the commencement of any work on site. This documentation will be used to resolve any dispute over damage to infrastructure. It is in the applicant's interest for it to be as full and detailed as possible.

The damage deposit shall be refunded upon completion of all works upon receipt of a Final Occupation Certificate stage and inspection by Council.

(Reason: Protection of Council infrastructure.)

FOR: S. Clements, K. Lindeberg, G. Andonoski

AGAINST: Nil

**** End Minutes - Report No. 4****

TO: Strathfield Internal Development Assessment Panel Meeting - 29 May 2020
REPORT: IDAP – Report No. 5
SUBJECT: DA2020/022 2 ISMAY AVENUE, HOMEBUSH
LOT 16 DP35204
DA NO. DA2020/022

RECOMMENDATION

That Development Application No. DA2020-22 for a change of use from a residential dwelling to a Health Service Facility with signage and minor internal changes at 2 Ismay Avenue, Homebush be **REFUSED** on-merit, for the following reasons:

Reason For Refusal – Environmental Planning Instrument (RN2001)

Pursuant to Section 4.15 (1)(a)(i) of the [Environmental Planning and Assessment Act 1979](#), the proposed development does not comply with the relevant environmental planning instruments in terms of the following:

- (a) Environmental Planning & Assessment Act 1979 - The proposed development is considered unacceptable because it fails to meet the aim of the Environmental Planning & Assessment Act 1979 to *promote the orderly and economic use and development of land, to promote good design and amenity of the built environment, to promote the proper construction and maintenance of buildings, including the protection of the health and safety of their occupants, to provide increased opportunity for community participation in environmental planning and assessment.* Strathfield Council Local Environmental Plan (LEP) provides provisions for land-use within the Strathfield Council Local Government Area and was arrived at after comprehensive community consultation and participation. The proposed application seeks to locate a land-use that is prohibited in an R3 zone. To promote the orderly and economic use and development of land, the LEP located a B2 Local Centre Zone on the junction of Underwood Road and Pomeroy Street to coordinate with the main public transport routes running along Underwood Road
- (b) Strathfield Local Environmental Plan 2012 - The proposed development is considered unacceptable because it fails to meet the aims of the Strathfield Local Environmental Plan 2012 Cl 1.2 (2) (b) relating to promoting efficient and spatially appropriate use of land, the sustainable revitalisation of centres, the improved integration of transport and land-use, and appropriate mix of uses by regulating land-use and development., because it seeks to locate a land use prohibited within a R3 zone and undermines the viability of the B2 zoned Local Centre on the junction of Underwood Rd and Pomeroy St.
- (c) Strathfield Local Environmental Plan 2012 - The proposed development is considered unacceptable because it fails to meet the aims of the Strathfield Local Environmental Plan 2012 Cl 1.2 (2) (e) To promote future development that integrated land use and transport planning, encourages public transport use, and reduced the traffic and environmental impacts of private vehicle use because it seeks to locate a Health Service Facility isolated from public transport bus-stops, which are located within the B2 Local Centre, and does not reduce the traffic and environmental impacts of private vehicle use.
- (d) Strathfield Local Environmental Plan 2012 - The proposed development is considered unacceptable because it fails to meet the zone objectives for an R3 Zone in the Strathfield Local Environmental Plan 2012, to provide for the housing needs of the community within a medium density residential environment, nor the aim to provide a variety of housing types within a medium density residential environment, and seeks to remove permitted housing. The applicant has as the proposal does not provided any justification that the

proposed development is of a type nor scale that may accord with the zone aim to enable other land uses that provide facilities or services to meet the day to day needs of residents.

- (e) Strathfield Local Environmental Plan 2012 - The proposed development is considered unacceptable because it fails to meet the aims of the Strathfield Local Environmental Plan 2012 Cl 1.2(2) (a) To achieve high quality urban form by ensuring that new development exhibits design excellence and reflects the existing or desired future character of particular localities and neighbourhoods in Strathfield. In seeking to introduce a commercial/retail character into an area of residential character the proposed development is will undermine the character of the residential area, and the desired future character of the Local Centre B2 zone to the west. The proposed Health Service Facility does not exhibit design excellence and does not look like a Health Service Facility, nor does it provide high quality urban form and lacks legibility.
- (f) Acid Sulfate Soils – The proposed development is considered unacceptable because it fails to meet the requirements of Clause 6.1 of Strathfield Local Environmental Plan. The site is located within 500 meters of adjacent Class 2 Acid Sulfate Soil, and no information has been provided to prove all the site is not below 5 meters AHD, nor that the water table will not be lowered below 1m AHD. No preliminary assessment of the proposed works, nor Acid Sulfate Soils Management Plan has been provided.
- (g) Earthworks - The proposed development is proximate to a Waterway; Powell Creek and will require earthworks. The application has not satisfied the requirements of SLEP, Part 6.2 (3) (g).
- (h) Erection or display of signage – The proposed development is considered unacceptable because it does not meet the criteria of Part 6.6 (a) & (b) for signage
- (i) State Environmental Planning Policy 2007 Infrastructure – The proposed development is unacceptable because it fails to demonstrate compatibility with the surrounding land uses.
- (j) State Environmental Planning Policy no. 55 Remediation of Land – The proposed development is considered unacceptable because it fails to meet the requirements of section 6 of SEPP55 which specifies contamination and remediation are to be considered in the zoning or re-zoning proposal, and section 7 that specifies contamination and remediation are to be considered in determining a development application, and clause 4 (c). The site may have been subject to contamination because of the flooding of Powells Creek. Industrial uses may have been located upstream along Powells Creek in the past. The documentation provided by the applicant has not considered potential contamination of the site caused by previous flood events of Powells Creek and an investigation report has not been provided.

Reason For Refusal – Draft/Proposed Planning Instrument (RN2002)

Pursuant to Section 4.15 (1)(a)(ii) of the [Environmental Planning and Assessment Act 1979](#), the proposed development does not comply with the relevant draft/proposed planning instruments in terms of the following:

- (a) Remediation of Land SEPP – The proposed development is considered unacceptable because it fails to meet the requirements of the draft Remediation of Land SEPP as it has not satisfied an initial evaluation for the potential for the land to be contaminated.

Reason For Refusal - Development Control Plan (RN2003)

Pursuant to Section 4.15 (1)(a)(iii) of the [Environmental Planning and Assessment Act 1979](#), the proposed development does not comply with the following sections of the Strathfield Consolidated Development Control Plan 2005 in terms of the following:

- (a) Part H - Waste Management Matters - The proposed development is considered unacceptable because it fails to meet the requirements of Strathfield Consolidated Development Control Plan 2005 (SCDCP 2005) Part H Waste Management. The submitted Waste Management Plan refers to the Waste management Plan produced for residential uses under DA2013/193. A waste management plan specific to the changed land-use to Health Service Facility was not provided. A revised Waste Management Plan which details the arrangements explicitly for a Health Service Facility is required.
- (b) Part I - Parking Matters – The proposed development is considered unacceptable because it fails to meet the requirements of Strathfield Consolidated Development Control Plan 2005 (SCDCP 2005) Part I. The application is for a Health Service Facility and has not specified what level of Health Service Facility to ascertain the correct parking requirements. The proposed development has not provided any parking for people with disabilities.
- (c) Part J - Advertising & Signage - The proposed development is considered unacceptable because it fails to meet the aims of Strathfield Consolidated Development Control Plan 2005 (SCDCP 2005).
- (d) Part K – Development on Contaminated Land – The proposed development is considered unacceptable because it fails to meet the objectives of Part K of Strathfield Consolidated Development Control Plan 2005 (SCDCP 2005).
- (e) Part Q – Urban Design Controls - The proposed development is considered unacceptable because it fails to meet the aims of Part Q of Strathfield Consolidated Development Control Plan 2005 (SCDCP 2005).

Reason For Refusal – Impacts on the Environment (RN2006)

Pursuant to Section 4.15 (1)(b) of the [Environmental Planning and Assessment Act 1979](#), the proposed development is likely to have an adverse impact on the following aspects of the environment:

(a) Natural Environment –

- a.1 The applicant has not supplied any preliminary Acid Sulfate Soil investigation, nor any Acid Sulfate Management Plan, and the development will require some excavation and elements of the building could be effected by the release of acid, and the exposure of acid sulfate soils to air during excavation could leach into the adjacent parkland and ultimately Powells Creek.
- a.2 The applicant has not supplied a Waste Management Plan for a Health Service Facility and lack of proper management of medical waste could be detrimental to the locality, and Powells Creek.

(b) Built Environment –

- b.1 The applicant is seeking a change of use from residential uses to a Health Service Facility, which is likely to increase the demand for on-street parking in the locality. The applicants SEE states that the proposal does not comply with the 3 spaces per surgery, plus 1 space per 2 employees and refers to the traffic report, and states the non-compliance is acceptable on-merit. The only off-street parking for the proposed Health Service facility is one garage space that was approved as a residential dual occupancy. The development is likely to increase demand for on-street parking for both customers and staff, and there is no provision for people with disabilities. The proposed development is considered unacceptable because it encourages private vehicle use, and increases the traffic and environmental impacts of private vehicle use.

(c) Social Environment –

- c.1 The proposed Health Service Facility will detract from the character of the residential R3 Zone and change its character from a residential character to a commercial character. The commercial character of the operation of the Health Service Facility and hours of operation are likely to be detrimental to the character of a residential area. The location of the proposed Health Service Facility at 2 Ismay Avenue is likely to undermine the potential social activation and vibrancy of the Local Centre B2 Zone.
- c.2 The proposed change of use from residential to a Health Services Facility undermines the residential character of the R3 zone and the social environment of the Local Centre to the west of the site as a desired social focal point for the locale.
- c.3 The applicant has not provided sufficient regarding Public Health Matters and the specific types of medical procedures to be conducted, the equipment required to complete procedures, location of equipment and the wastes generated and where hazardous waste is stored and how hazardous waste will be disposed

(d) Economic Environment –

- d.1 The proposed Health Service Facility at 2 Ismay Avenue is likely to undermine economic activity in the Local Centre B2. The change of land use undermines the demand for commercial and retail space in the Local Centre B2 Zone, and undermines the economic viability of the Local Centre west of the subject.

Reason For Refusal – Suitability of Site (RN2007)

Pursuant to Section 4.15 (1)(c) of the [Environmental Planning and Assessment Act 1979](#), the site not considered suitable for the proposed development for the following reasons:

- (a) The subject site is Zoned R3 and the proposed use is not permitted in this zone under the SLEP. The applicant is seeking to change the land-use under SEPP Infrastructure. However, the applicant has not demonstrated that the site is suitable for the proposed change of use to a Health Service Facility.
- (b) The subject site is Zoned R3 and the proposed use is not permitted in this zone under the SLEP. The applicant is seeking to change the land-use under SEPP Infrastructure. However, the applicant has not proven that the site is suitable for the proposed change of use to a Health Service Facility.
- (c) The site is not considered suitable because it is located outside the Local Centre B3 Zone, which is where the desired future retail and commercial character is to be located.
- (d) The proposed development is considered unacceptable because it encourages private vehicle use, and increases the traffic and environmental impacts of private vehicle use.
- (e) Remediation of Land SEPP 55 - The proposed development is considered unacceptable because it fails to meet the requirements of SEPP 55 Section 6 specifies contamination and remediation to be considered in the zoning or re-zoning proposal, and section 7 specifies contamination and remediation to be considered in determining a development application. The site may have been subject to contamination because of the flooding of Powells Creek and Industrial uses may have been located upstream along Powells Creek in the past. The applicant has not provided any evidence that the site is suitable for a change of land-use to a Health Services Facility.
- (f) The site is not considered suitable for the proposed development because it has not proven that the development has considered the proper investigation and management of Acid Sulfate Soils.

Reason For Refusal – Public Interest (RN2008)

Pursuant to Section 4.15 (1)(e) of the [Environmental Planning and Assessment Act 1979](#), the proposed development is not considered to be in the public interest and is likely to set an undesirable precedent.

Reason For Refusal - (RN2008)

The proposed development is unacceptable because it fails to meet the aims of the Strathfield Council Local Strategic Planning Statement (LSPS);

- Planning Priority 1 – Collaboration ensures growth is sustained by well-planned and accessible infrastructure.
- Planning Priority 2 – Connected, integrated, efficient and accessible transport options connect Strathfield's people to their neighbourhoods, centres, jobs, and community and recreation areas
- Planning Priority 6 – Development balances growth with best practice planning and infrastructure provision to deliver sustainable, liveable and well designed neighbourhoods.
 - Action 38 – Work with service providers to design and deliver best practice infrastructure, servicing and development approaches.

RESOLUTION

The application be **REFUSED** as per the planners recommendation and reasons.

FOR: S. Clements, K. Lindeberg, G. Andonoski

AGAINST: Nil

**** End Minutes - Report No. 5****