

Minutes

Of the meeting of the:

Strathfield Internal Development Assessment Panel Meeting

Held on:

Friday, 12 June 2020

Commencing at 10:00am Main Building Meeting Room,
65 Homebush Road, Strathfield

TABLE OF CONTENTS

Item Page No.

IDAP AGENDA ITEMS

IDAP - Report No. 1

DA2019/185 - 56 Homebush Road, Strathfield - Lot A DP 1696634

The meeting of the Strathfield Internal Development Assessment Panel Meeting was held in the Main Building Meeting Room, 65 Homebush Road, Strathfield on Friday 12 June 2020.

PRESENT

Stephen Clements, Deputy CEO/General Manager Planning, Environment & Urban Services
Kandace Lindeberg, Executive Manager, Landuse Planning and Development
George Andonoski, Specialist Strategic Planner

DECLARATIONS OF PECUNIARY INTEREST / CONFLICT OF INTEREST

Nil

TO: Strathfield Internal Development Assessment Panel Meeting - 12 June 2020
REPORT: IDAP – Report No. 1
SUBJECT: DA2019/185 - 56 HOMEBUSH ROAD, STRATHFIELD - LOT A DP 169663
DA NO. DA2019/185

RECOMMENDATION

That Development Application No. DA2019.185 for the demolition of existing buildings and construction of a two (2) storey dwelling with basement level and detached secondary dwelling with associated landscaping at 56 Homebush Road be **approved**, subject to the following conditions:

SPECIAL CONDITIONS (SC)

1. FRONT BOUNDARY FENCE (SC)

An above ground lintel system along the entire length of the masonry front boundary fence is to be implemented. Amended plans demonstrating compliance with the conditions are to be submitted and approved by the Principal Certifying Authority prior to the issue of a Construction Certificate.

(Reason: Street tree protection).

2. COLOURS AND MATERIALS

The colours and materials of the front boundary fence and the secondary dwelling are to be consistent with those of the primary dwelling and dwellings within the Heritage Conservation Area. Amended plans demonstrating compliance with this condition are to be submitted to and approved by Council prior to the issue of a Construction Certificate.

(Reason: To accord with existing contributory dwellings within the HCA)

3. DRIVEWAY RETAINING WALLS

The retaining walls along the internal driveway and parallel to the southern boundary must step with the natural topography of the site. The top of these walls must not exceed the existing ground level.

This design change must be included and reflected in the revised set of Architectural Plans, Landscape Plans and Stormwater Plans, and any other documentation that are to be submitted and approved by the Principal Certifying Authority prior to the issue of a Construction Certificate.

(Reason: Streetscape presentation)

GENERAL CONDITIONS (GC)

4. APPROVED PLANS AND REFERENCE DOCUMENTATION (GC)

The development, except where modified by a condition(s) of consent, is to be carried out in accordance with the following plans and reference documentation:

Plans affixed with Council's 'Development Consent' stamp relating to Development Consent No. DA2019/185:

MINUTES

Drawing No.	Title/Description	Prepared by	Issue / Revision & Date	Date received by Council
01	Site Plan	Wincrest Group Pty Ltd	Issue N 26 May 2020	26 May 2020
25	Site Analysis	Wincrest Group Pty Ltd	Issue N 26 May 2020	26 May 2020
24	Demolition Plan	Wincrest Group Pty Ltd	Issue N 26 May 2020	26 May 2020
02	Garage Floor Plan	Wincrest Group Pty Ltd	Issue N 26 May 2020	26 May 2020
03	Ground Floor Plan	Wincrest Group Pty Ltd	Issue N 26 May 2020	26 May 2020
04	First Floor Plan	Wincrest Group Pty Ltd	Issue N 26 May 2020	26 May 2020
10	Secondary Dwelling Floor Plan	Wincrest Group Pty Ltd	Issue N 26 May 2020	26 May 2020
08	Driveway Plan	Wincrest Group Pty Ltd	Issue N 26 May 2020	26 May 2020
05	Elevations (West & North)	Wincrest Group Pty Ltd	Issue N 26 May 2020	26 May 2020
06	Elevations (East & South)	Wincrest Group Pty Ltd	Issue N 26 May 2020	26 May 2020
07	Section B-B	Wincrest Group Pty Ltd	Issue N 26 May 2020	26 May 2020
11	Secondary Dwelling Elevations	Wincrest Group Pty Ltd	Issue N 26 May 2020	26 May 2020
31	Streetscape	Wincrest Group Pty Ltd	Issue N 26 May 2020	26 May 2020
32	Roof Plan	Wincrest Group Pty Ltd	Issue N 26 May 2020	26 May 2020
L/02'B'	Proposed Fence Elevation	Wincrest Group Pty Ltd	4 October 2019	17 April 2020
L/01'B'	Proposed Landscape	Wincrest Group Pty Ltd	Revision C 4 June 2020	4 June 2020
26	Soil and Sediment Control	Wincrest Group Pty Ltd	Issue N 26 May 2020	26 May 2020
	External Colour Sample Board	Wincrest Group Pty Ltd	Issue M 4 June 2020	17 April 2020
D1	Cover sheet & Design Summary Table	Wincrest Group Pty Ltd	Issue D 29 May 2020	29 May 2020
D2	Stormwater Management Plan	Wincrest Group Pty Ltd	Issue D 29 May 2020	29 May 2020
D3	Typical Details	Wincrest Group Pty Ltd	Issue D 29 May 2020	29 May 2020
D4	Basement Drainage Design	Wincrest Group Pty Ltd	Issue D 29 May 2020	29 May 2020
D5	Proposed Absorption Trench Design	Wincrest Group Pty Ltd	Issue D 29 May 2020	29 May 2020
D5	Proposed Pump Out System	Wincrest Group Pty Ltd	Issue D 29 May 2020	29 May 2020

Reference Documentation affixed with Council's 'Development Consent' stamp relating to Development Consent No. DA2019/185:

Title / Description	Prepared by	Issue/Revision & Date	Date received by Council
Heritage Impact Statement	DOTP Town Planning Pty Ltd	Issue B August 2019	17 April 2020
Nationwide House Energy Rating Scheme Certificate	Wincrest Group Pty Ltd	5 September 2019	5 November 2019
GeoTech Lot Classification Report	Ideal Corp	8 February 2019	5 November 2019
Waste Management Plan	Wincrest Group Pty Ltd	6 October 2019	5 November 2019

In the event of any inconsistency, the conditions of this consent shall prevail.

(Reason: To ensure that the form of the development undertaken is in accordance with the determination of Council.)

5. **CONSTRUCTION HOURS (GC)**

No construction or any other work related activities shall be carried out on the site outside the hours of 7.00 am to 5.00 pm Mondays to Fridays and 8am to 1pm Saturdays.

No building activities are to be carried out at any time on a Sunday or public holiday.

Where the development involves the use of jackhammers/rock breakers and the like or other heavy machinery, such equipment may only be used between the hours of 7.00 am - 5.00 pm Monday to Friday only.

(Reason: To maintain amenity to adjoining land owners.)

6. **BUILDING HEIGHT - MAXIMUM RL TO BE COMPLIED WITH (GC)**

The height of the building measured from Australian Height Datum (AHD) must not exceed Relative Level (RL) 29.993AHD to the roof ridge of the building.

(Reason: To ensure the approved building height is complied with.)

7. **CONSTRUCTION WITHIN BOUNDARIES (GC)**

The development including but not limited to footings, walls, roof barges and guttering must be constructed wholly within the boundary of the premises. No portion of the proposed structure shall encroach onto the adjoining properties. Gates must be installed so they do not open onto any footpath or adjoining land.

(Reason: Approved works are to be contained wholly within the subject site.)

8. **DEMOLITION – GENERALLY (GC)**

Alteration and demolition of the existing building is limited to that documented on the approved plans (by way of notation). No approval is given or implied for removal and/or rebuilding of any portion of the existing building which is not shown to be altered or demolished.

(Reason: To ensure compliance with the approved development.)

9. LANDSCAPING - TREES PERMITTED TO BE REMOVED (GC)

The following listed trees are permitted to be removed to accommodate the proposed development:

Tree No. in Arborist Report	Tree	Location
T1	<i>Shinus molle</i> (Peppercorn Tree)	South-east rear corner of site.

All trees permitted to be removed by this consent shall be replaced (2 trees for each tree removed) by species selected from Council's Recommended Tree List and must have a minimum mature height of 10 metres.

Replacement trees shall be a minimum 50 litre container size. Trees are to conform to the NATSPEC guide and Guide for assessing the quality of and purchasing of landscape trees by Ross Clarke, 2003. Trees are to be true to type, healthy and vigorous at time of delivery and planting, shall be pest and disease free, free from injury and wounds and self-supporting; and shall be maintained until maturity.

All trees are to be staked and tied with a minimum of three (3) hardwood stakes. Ties are to be hessian and fixed firmly to the stakes, one tie at half the height of the main stem, others as necessary to stabilise the plant.

Root deflection barriers having a minimum depth of 600mm are to be installed adjacent to all footpaths and driveways.

Soil conditioner/fertilizer/moisture retention additive/s are to be applied in accordance with manufacturer's recommendations, and mixed into the backfilling soil after planting tree/s.

A minimum 75mm depth of organic mulch shall be placed within an area 0.5m from the base of the tree.

Details demonstrating compliance shall be demonstrated to the Principal Certifying Authority, prior to the issue of any Occupation Certificate.

(Reason: To ensure appropriate planting back onto the site.)

10. ENVIRONMENTAL PROTECTION – TREE (GC)

All street trees and trees on private property that are protected under Council's controls, shall be retained except where Council's prior written consent has been obtained. The felling, lopping, topping, ringbarking, wilful destruction or removal of any tree/s unless in conformity with this approval or subsequent approval is prohibited.

All healthy trees and shrubs identified for retention on the approved drawings are to be suitably protected in accordance with Section 4, Tree protection measures, and Appendix C Tree Protection Zone Sign, of Australian Standard AS4970 - 2009, Protection of Trees on Development Sites, prior to the commencement of any works (including any demolition and excavation) and maintained for the duration of the works.

In this regard the street tree and all protected trees on or adjacent to the site will be protected as described below;

- i. A Tree Protection (Management) Plan prepared by a AQF Level 5 Arborist is to be available on site at all times prior to the issue of the Constriction Certificate, for all demolition and site works. This Tree Protection (Management) Plan must be shown on the demand of Authorised Council staff.
- ii. Protective perimeter fencing must be consistent with AS 4687, using metal fence posts greater than 20mm diameter and solid or chain wire mesh 2 metres in height supported on concrete pads/feet at 2-2.5 metre spacing. Fencing placement should not be closer than 2.5 metres from the trunk of each protected tree, or at a distance as specified by the approved Tree Protection (Management) Plan and approved by Council's Tree Management Officer. Shade cloth is to be used to prevent entry of dust and contaminated liquids into the root protection area.
- iii. Signs must be placed on the Fencing. These signs must comply with AS1319. The signs must state the purpose of the fencing and the name and contact details of the builder and the appointed AQF Level 5 consultant arborist.
- iv. Root protection is to be provided in the form of mulching to a depth of 50-100mm, inside of the fenced tree protection zone.
- v. Ground (Root) Trunk and Branch Protection must comply with the diagram of Figure 4 of AS4970 – 2009. Ground protection within the tree protection zone and drip line should be in the form of heavy steel plates or timber rumble boards over mulch or aggregate. Trunk and branch protection should be to a minimum height of 2 metres and must include measures to protect the tree/s against damage from the movement of trucks, plant equipment and materials at greater heights above ground level.
- vi. Temporary signs, cables, wires must not be attached to, or suspended, on any street tree or protected tree.
- vii. Above ground utilities must not be placed within the canopy of an existing protected tree, or create the future need for clearance pruning.
- viii. Below ground utilities/services must not be located inside the fenced tree protection zone.
- ix. Scaffolding must not be located in the fenced tree protection zone unless authorised by the approved Tree Protection (Management) Plan and Council's Tree Management Officer
- x. Council must be notified in writing within 24 hours, for all temporary removal of the tree protection fencing ground (root) trunk and branch protection within the root protection area.
- xi. Pruning of a street tree is prohibited without the written consent of Council.

(Reason: To ensure the protection of trees to be retained on the site.)

11. MATERIALS – SCHEDULE OF EXTERNAL FINISHES TO BE SUBMITTED (GC)

A schedule detailing all external materials, colours and finishes including windows, doors, roofing and fencing materials shall be submitted to Council for approval.

All external materials, colours and finishes including windows and doors, roofing and fencing materials must be of high quality and compatible with those of the surrounding streetscape and locality. All external materials and colours shall be of low glare and reflectivity. Details demonstrating compliance with this condition shall be provided to the Principal Certifying Authority, prior to the issue of any Construction Certificate.

(Reason: To ensure a positive contribution to the streetscape and to minimise excessive glare and reflectivity.)

12. PRINCIPAL CERTIFYING AUTHORITY (PCA) IDENTIFICATION SIGN (GC)

Prior to commencement of any work, signage must be erected in a prominent position on the work site identifying:

- i) The Principal Certifying Authority (PCA) by showing the name, address and telephone number of the PCA;
- ii) The Principal Contractor by showing the Principal Contractor's name, address and telephone number (outside of work hours) for that person; and
- iii) The sign must state that unauthorised entry to the work site is prohibited.

Any such sign is to be maintained while the work is being carried out, but must be removed when the work has been completed.

This clause does not apply to building work, subdivision work or demolition work that is carried out inside an existing building that does not affect the external walls of the building.

(Reason: Statutory requirement.)

13. **SITE MANAGEMENT (DURING DEMOLITION AND CONSTRUCTION WORKS)**

All of the following are to be satisfied/complied with during demolition, construction and any other site works:

- i) All demolition is to be carried out in accordance with Australian Standard AS 2601-2001.
- ii) Demolition must be carried out by a registered demolition contractor.
- iii) A single entrance is permitted to service the site for demolition and construction. Protection pads are to be installed to the kerb, gutter and nature strip where trucks and vehicles enter the site.
- iv) No blasting is to be carried out at any time during construction of the building.
- v) Care must be taken during demolition/ excavation/ building/ construction to prevent any damage to adjoining buildings.
- vi) Adjoining owner property rights and the need for owner's permission must be observed at all times, including the entering onto land for the purpose of undertaking works.
- vii) Any demolition and excess construction materials are to be recycled wherever practicable.
- viii) The disposal of construction and demolition waste must be in accordance with the requirements of the Protection of the Environment Operations Act 1997.
- ix) All waste on the site is to be stored, handled and disposed of in such a manner as to not create air pollution (including odour), offensive noise or pollution of land and/or water as defined by the Protection of the Environment Operations Act 1997. All excavated material should be removed from the site in an approved manner and be disposed of lawfully to a tip or other authorised disposal area.
- x) All waste must be contained entirely within the site.
- xi) A site plan including temporary waste storage locations, construction material storage areas and vehicular access to and from the site must be included with application.
- xii) Section 143 of the Protection of the Environment Operations Act 1997 requires waste to be transported to a place which can lawfully accept it. All non-recyclable demolition materials are to be disposed of at an approved waste disposal depot in accordance with legislation.
- xiii) Details as to the method and location of disposal of demolition materials (weight dockets, receipts, etc.) should be kept on site as evidence of approved methods of disposal or recycling and must be presented to Council and/or Principal Certifying Authority upon request.
- xiv) All materials on site or being delivered to the site are to generally be contained within

the site. The requirements of the Protection of the Environment Operations Act 1997 must be complied with when placing/stockpiling loose material, disposing of concrete waste, or other activities likely to pollute drains or water courses.

- xv) Any materials stored on site must be stored out of view or in such a manner so as not to cause unsightliness when viewed from nearby lands or roadways.
- xvi) Public footways, include nature strips and roadways adjacent to the site must be maintained and cleared of obstructions during construction. No building materials, waste containers or skips may be stored on the road reserve or footpath without prior separate approval from Council, including payment of relevant fees.
- xvii) Building operations such as brick-cutting, washing tools or paint brushes, and mixing mortar not be performed on the roadway or public footway or any other locations which could lead to the discharge of materials into the stormwater drainage system.
- xviii) All site waters during excavation and construction must be contained on site in an approved manner to avoid pollutants entering into waterways or Council's stormwater drainage system.
- xix) Any work must not prohibit or divert any natural overland flow of water.
- xx) Toilet facilities for employees must be provided in accordance with WorkCover NSW.

(Reason: To ensure that demolition, building and any other site works are undertaken in accordance with relevant legislation and policy and in a manner which will be non-disruptive to the local area.)

14. **STORMWATER MANAGEMENT PLAN - CERTIFICATION REQUIREMENT (GC)**

A detailed Stormwater Management Plan (SWMP) in line with Council's Stormwater Management Code is to be prepared and certified by an Accredited Civil/Hydraulic Engineer and submitted to the Principal Certifying Authority and Council, prior to the issue of a Construction Certificate. The SWMP is to be based on the approved development as modified by any conditions of consent.

(Reason: To ensure appropriate provision is made for the disposal and management of stormwater generated by the development, and to ensure public infrastructure in Council's care and control is not overloaded.)

15. **SYDNEY WATER - TAP IN™ (GC)**

The approved plans must be submitted to a Sydney Water Tap in™ to determine whether the development application will affect Sydney Water's sewer and water mains, stormwater drains and/or easements, and if further requirements need to be met. The approved plans will be appropriately endorsed. For details please refer to 'Plumbing, building and developing' section of Sydney Water's web site at www.sydneywater.com.au then see 'Building', or telephone 13000 TAP IN (1300 082 746). The Certifying Authority must ensure that a Tap in™ agent has appropriately stamped the plans prior to the issue of the Construction Certificate.

(Reason: Compliance with Sydney Water requirements.)

16. **UTILITIES AND SERVICES - PROTECTION OF (GC)**

Any footings or excavation to be located or undertaken adjacent to Council's stormwater must be designed to address the following requirements:

- i) All footings and excavation must be located wholly within the site and clear of any easement boundaries;
- ii) All footings and excavation must be located a minimum of 1000mm from the centreline of the pipeline or 500mm from the outside of the pipeline, whichever is the

- greater distance from the centreline; and
- iii) Footings must extend to at least the depth of the invert of the pipeline unless the footings are to be placed on competent bedrock.

If permanent excavation is proposed beneath the obvert of the pipeline, suitable means to protect the excavation and proposed retaining structures from seepage or other water flow from the pipeline and surrounding subsoil, must be provided. The design must be prepared by a qualified practicing Structural/Civil Engineer.

Construction plans must be approved by the appropriate utility's office (e.g. council, Sydney Water Corporation) to demonstrate that the development complies with the utility's requirements.

The applicant must provide written evidence (e.g. compliance certificate, formal advice) of compliance with the requirements of all relevant utility providers (e.g. Water, Energy, Telecommunications, Gas).

(Reason: To ensure protection of Council assets.)

CONDITIONS TO BE SATISFIED PRIOR TO THE ISSUE OF A CONSTRUCTION CERTIFICATE (PCC)

17. BASIX COMMITMENTS (CC)

The approved BASIX Certificate shall be submitted to the Principal Certifying Authority with the application for a Construction Certificate.

Where a change or changes are proposed in the BASIX commitments, the applicant must submit a new BASIX Certificate to the Principal Certifying Authority and Council. If any proposed change in the BASIX commitments is inconsistent with the development consent the applicant will be required to submit a modification to the development consent to Council under Section 4.55 of the Environmental Planning and Assessment Act 1979.

All commitments in the BASIX Certificate must be shown on the plans accompanying the Construction Certificate.

(Reason: Statutory compliance.)

18. BUILDING CODE OF AUSTRALIA - COMPLIANCE WITH (CC)

All architectural drawings, specifications and related documentation shall comply with the Building Code of Australia (BCA). All work must be carried out in accordance with the requirements of the Building Code of Australia (BCA).

In the case of residential building work for which the Home Building Act 1989 requires there to be a contract of insurance in force in accordance with Part 6 of that Act, such a contract of insurance is to be in force before any building work authorised to be carried out by the consent commences.

Details demonstrating compliance with this condition are to be submitted to the Principle Certifying Authority, prior to issue of the Construction Certificate.

(Reason: This is a 'prescribed' condition under clause 98(1) of the Environmental Planning and Assessment Regulation 2000.)

19. CAR PARKING - BASEMENT CAR PARKING REQUIREMENTS (CC)

Details demonstrating compliance with the following is to be submitted to the Principal Certifying Authority, prior to issue of the Construction Certificate:

- i) Minimal internal clearance of the basement is 2.2m in accordance with BCA requirements.
- ii) Driveways shall comply with Australian/New Zealand Standard AS/NZS 2890.1:2004 - Parking facilities - Off-street car parking and achieve a maximum gradient of 1:4.
- iii) Basement entries and ramps/driveways within the property are to be no more than 3.5m wide.
- iv) Provision of pump-out systems and stormwater prevention shall be in accordance with Council's Stormwater Management Guide.

(Reason: To ensure suitable development.)

20. CAR PARKING - VEHICULAR ACCESS RAMPS (CC)

Vehicular access ramps shall comply with the provisions of AS/NZS 2890.1:2004. Plans to be submitted shall contain the following details:

- i) Longitudinal section along the extreme wheel paths of each driveway/access ramp at a scale of 1:25 demonstrating compliance with the scraping provisions of AS/NZS 2890.1:2004. It shall include all levels and grades, including those levels stipulated as boundary levels, both existing and proposed. It shall extend from the centre-line of the roadway through to the parking area.
- ii) Sections showing the clearance to the underside of any overhead structure (minimum headroom requirements 2200mm minimum for standard headroom clearance or 2400mm where disabled access provisions are to be provided) demonstrating compliance with the provisions of AS/NZS 2890.1:2004.
- iii) Longitudinal section along the gutter line showing how it is intended to transition the vehicular crossing into the existing kerb and gutter. Boundary levels shall generally run parallel with the kerb levels.
- iv) Location of verge trees, street furniture and service installations.
- v) Superimposition of vehicle turning circles for access into parking spaces.
- vi) Certification that the design complies with AS/NZS 2890.1:2004 by a Qualified Engineer.

The certification referred to in (vi) above shall be submitted to the Principal Certifying Authority prior to the issue of a Construction Certificate (for the design) and to the Principal Certifying Authority prior to the issue of any Occupation Certificate for the 'as-built works'.

(Reason: To ensure adequate vehicular access can be achieved.)

21. CAR PARKING - COMPLIANCE WITH AS/NZS 2890.1:2004 (CC)

Car parking dimensions must comply with the Australian/New Zealand Standard AS/NZS 2890.1:2004 - Parking facilities - Off-street car parking. Details demonstrating compliance are to be submitted to the Principal Certifying Authority, prior to the issue of a Construction Certificate.

(Reason: To ensure compliance with Australian Standards relating to parking of vehicles.)

22. CAR PARKING - VEHICULAR CIRCULATION, AISLE AND RAMP WIDTHS (CC)

The aisle widths, internal circulation, ramp widths and grades of the car park shall comply with the Roads and Traffic Authority Guidelines and AS/NZS 2890.1:2004 - Off-Street Car

Parking Code.

Vehicular manoeuvring paths are to be prepared demonstrating that all vehicles can enter or depart the site in a forward direction without encroaching on required car parking spaces.

(Reason: To ensure compliance with Australian Standards relating to manoeuvring, access and parking of vehicles.)

23. **CAR PARKING - VEHICULAR CROSSING WIDTH AT PROPERTY BOUNDARY (CC)**

Vehicular crossings are to have a maximum width of 3m at the property boundary. Details demonstrating compliance are to be submitted to the Principal Certifying Authority, prior to the issue of a Construction Certificate.

The vehicular crossing (and all associated excavation works) must not be constructed closer than 2 metres from a retained protected street tree.

(Reason: Compliance with SCDCP 2005.)

24. **COMMENCEMENT OF WORKS (NO WORKS UNTIL A CC IS OBTAINED)**

Building work, demolition or excavation must not be carried out until a Construction Certificate has been issued by either Strathfield Council or a Principal Certifying Authority.

Demolition of any part of a building triggers 'commencement of erection of building' pursuant of section 4.19 of the EP&A Act 1979. Accordingly, demolition works must not commence until a Construction Certificate has been issued, a Principal Certifying Authority has been appointed and a Notice of Commencement has been issued.

(Reason: To ensure compliance with statutory provisions.)

25. **DILAPIDATION REPORT - PRE-COMMENCEMENT (CC)**

Subject to access being granted, a pre-commencement Dilapidation Report is to be undertaken on all adjoining properties, which in the opinion of a suitably qualified engineer, could be potentially affected by the construction of the project. The Dilapidation Report shall be carried out prior to the issue of a Construction Certificate.

The Dilapidation Report is to be prepared by a suitably Qualified Engineer with current Corporate Membership with the Institution of Engineers, Australia or Geotechnical Practitioner. The report shall include a photographic survey of adjoining properties detailing the physical condition of those properties, both internally and externally, including walls, ceilings, roof, structural members and other such items.

If access for undertaking the dilapidation survey is denied by an adjoining owner, the applicant must demonstrate, in writing, to Council's satisfaction attempts have been made to obtain access and/or advise the affected property owner of the reason for the survey and these attempts have been unsuccessful. Written concurrence must be obtained from Council in such circumstances.

The Report shall cover structural and geotechnical factors likely to arise from the development. A copy of this Report shall be submitted to Council as a record. The person having the benefit of the development consent must, at their own cost, rectify any damage caused to other properties during the construction of the project.

(Reason: To ensure no damage to adjoining properties occurs.)

26. EROSION AND SEDIMENTATION CONTROL PLAN (CC)

An Erosion and Sediment Control Plan is to be prepared where construction or excavation activity requires the disturbance of the soil surface and existing vegetation. Details including drawings and specifications must provide adequate measures for erosion and sediment control to ensure:

- i) Compliance with the approved Soil and Water Management Plan.
- ii) Removal or disturbance of vegetation and top soil is confined to within 3m of the approved building area (no trees to be removed without approval).
- iii) All uncontaminated run-off is diverted around cleared or disturbed areas.
- iv) Silt fences or other devices are installed to prevent sediment and other debris escaping from the cleared or disturbed areas into drainage systems or waterways.
- v) All erosion and sediment controls are fully maintained for the duration of demolition/development works.
- vi) Controls are put into place to prevent tracking of sediment by vehicles onto adjoining roadways.
- vii) All disturbed areas are rendered erosion-resistant by turfing, mulching, paving or similar.
- viii) All water pumped or otherwise removed from excavations or basement areas is filtered to achieve suspended solids/non filterable residue levels complying with the Australian Water Quality guidelines for Fresh and Marine Waters.
- ix) Pumped or overland flows of water are discharged so as not to cause, permit or allow erosion before the commencement of work (and until issue of the occupation certificate).

Details of the proposed soil erosion and sedimentation controls are to be submitted to the Principal Certifying Authority with the Construction Certificate Application. Under no circumstances are any works to commence, prior to these details being approved by the Principal Certifying Authority and the controls being in place on the site.

(Reason: Environmental protection.)

27. EXCAVATION - AFFECTING ADJOINING LAND (CC)

If an excavation associated with the approved development extends below the level of the base of the footings of a building on an adjoining allotment of land, the person having the benefit of the development consent must, at the person's own expense, comply with the requirements of clause 98E of the Environmental Planning and Assessment Regulation 2000, including:

- i) Protect and support the adjoining premises from possible damage from the excavation, and
- ii) Where necessary, underpin the adjoining premises to prevent any such damage.

The condition referred to in subclause (i) does not apply if the person having the benefit of the development consent owns the adjoining land or the owner of the adjoining land has given consent in writing to that condition not applying. Details shall be submitted to the Principal Certifying Authority, prior to the issue of a Construction Certificate.

(Reason: Structural safety.)

28. PRIVACY - OBSCURE GLAZING IN WET AREAS (CC)

All bathroom, ensuite and toilet windows shall be installed with obscure glazing. Plans shall

be notated accordingly and details demonstrating compliance submitted to the Principal Certifying Authority, prior to the issue of a Construction Certificate.

(Reason: Privacy amenity.)

29. SECTION 7.11 CONTRIBUTION PAYMENT - DIRECT CONTRIBUTIONS PLAN (CC)

In accordance with the provisions of Section 7.13 of the Environmental Planning and Assessment Act 1979 and the Strathfield Direct Development Contributions Plan 2010-2030, a contribution in the form of cash, cheque or credit card (financial transaction fee applies) shall be paid to Council for the following purposes:

Provision of Community Facilities	\$1883.45
Provision of Major Open Space	\$8569.13
Provision of Local Open Space	\$2936.83
Provision Roads and Traffic Management	\$796.99
Administration	\$162.41
TOTAL	\$14,348.79

The total amount of the contribution is valid as at the date of determination and is subject to quarterly indexation. Contributions shall be indexed at the time of payment in accordance with clause 2.14 of the Strathfield Direct Development Contributions Plan 2010-2030.

Contributions must be receipted by Council and submitted to the Accredited Certifier, prior to the issue of any Construction Certificate.

Please present a copy of this condition when paying the contribution at the Customer Service Centre so that it can be recalculated.

Note: A copy of Strathfield Council's Section 7.11 Direct Development Contributions Plan may be downloaded from Council's website.

(Reason: To enable the provision of public amenities and services required/anticipated as a consequence of increased demand resulting from the development.)

30. STORMWATER - RAINWATER RE-USE (CC)

A rainwater re-use system shall be provided in accordance with either the BASIX minimum requirements, any relevant Council Rainwater Policy and/or specification of the management of stormwater, whichever is applicable. A detailed stormwater plan showing the proposed re-use system shall be submitted to and approved by the Principal Certifying Authority, prior to the issue of a Construction Certificate.

(Reason: Compliance and amenity.)

31. STORMWATER DRAINAGE (CC)

The following stormwater precautions are required to be provided on the site:

- i) Grated drains shall be provided along the driveway/basement entry at the vehicular crossing(s) and are to connect to the internal drainage system.
- ii) Overflow paths shall be provided to allow for flows in excess of the capacity of the pipe/drainage system draining the site.
- iii) Allowance shall be made for surface runoff from adjacent properties, and to retain existing surface flow path systems through the site. Any redirection or treatment of these flows shall not adversely affect any other properties

- iv) Boundary fencing shall be erected in such a manner as not to interfere with the natural flow of ground and surface water to the detriment of any other party.

(Reason: To ensure the site is drained appropriately and does not interfere with the natural flow of flood waters.)

32. **TREE BONDS (CC)**

A tree bond of **\$30,000** (calculated in accordance with Council's adopted Fees and Charges) shall be paid to Council, prior to the issue of a Construction Certificate.

The deposit is required as security against any damage to existing trees to be retained on Council's road reserve, during works on the site. The applicant must bear the cost of all restoration works to Council's property damaged during the course of this development.

Payment may be accepted in the form of cash, bank guarantee, cheque or credit card (financial transactions fees apply). Note: Additional fees apply for the lodgement of a bank guarantee in lieu of cash bond applies in accordance with Council's adopted Fees and Charges.

A refund of the Tree Bond must be made in writing.

Tree Bonds may be forfeited if a tree is dead, made dangerous or has been terminally damaged, or will be held until tree/s have fully recovered from the construction damage or were replacement/planted trees have become fully established and are over 6 metres in height.

(Reason: To ensure the protection of trees to be retained on Council's Road Reserve.)

33. **SECURITY PAYMENT – DAMAGE DEPOSIT FOR COUNCIL INFRASTRUCTURE (CC)**

A security (damage deposit) of **\$15,000.00** (calculated in accordance with Council's adopted Fees and Charges) shall be paid to Council, prior to the issue of a Construction Certificate.

The deposit is required as security against any damage to Council property during works on the site. The applicant must bear the cost of all restoration works to Council's property damaged during the course of this development. All building work must be carried out in accordance with the Building Code of Australia.

Payment may be accepted in the form of cash, bank guarantee, cheque or credit card (financial transactions fees apply). Note: Additional fees apply for the lodgement of a bank guarantee in lieu of cash bond applies in accordance with Council's adopted Fees and Charges.

Any costs associated with works necessary to be carried out to rectify any damages caused by the development, shall be deducted from the Damage Deposit.

Note: Should Council property adjoining the site be defective e.g. cracked footpath, broken kerb etc., this should be reported in writing, or by photographic record, submitted to Council at least seven (7) days prior to the commencement of any work on site. This documentation will be used to resolve any dispute over damage to infrastructure. It is in the applicant's interest for it to be as full and detailed as possible.

The damage deposit shall be refunded upon completion of all works upon receipt of a Final Occupation Certificate stage and inspection by Council.

34. VEHICULAR CROSSINGS - WORKS PERMIT FOR CONSTRUCTION OF (CC)

Full-width, heavy-duty concrete vehicular crossing(s) shall be provided across the footpath at the entrance(s) and/or exit(s) to the site and designed in accordance with Council's guidelines and specifications. In this regard, a Works Permit is to be obtained (available from Council's Customer Services Centre or downloaded from Council's website), and the appropriate fees and charges paid, prior to the lodgement of a Construction Certificate.

(Reason: To ensure appropriate access to the site can be achieved.)

CONDITIONS TO BE SATISFIED PRIOR TO THE COMMENCEMENT OF WORKS (PCW)**35. APPOINTMENT OF A PRINCIPAL CERTIFYING AUTHORITY (PCA) (CW)**

No work shall commence in connection with this Development Consent until:

- i) A construction certificate for the building work has been issued by the consent authority or a Principal Certifying Authority.
- ii) The person having the benefit of the development consent has appointed a principal certifying authority for the building work, and notified the principal certifying authority that the person will carry out the building work as an owner/builder, if that is the case.
- iii) The principal certifying authority has, no later than 2 days before the building work commences:
 - notified the Council of his or her appointment, and
 - notified the person having the benefit of the development consent of any critical stage inspections and other inspections that are to be carried out in respect of the building work.
- iv) The person having the benefit of the development consent, if not carrying out the work as an owner-builder, has:
 - appointed a principal contractor for the building work who must be the holder of a contractor licence if any residential building work is involved;
 - notified the principal certifying authority of such appointment; and
 - unless that person is the principal contractor, notified the principal contractor of any critical stage inspections and other inspections that are to be carried out in respect of the building work.
- v) The person having the benefit of the development consent has given at least 2 days' notice to the Council of the person's intention to commence the erection of the building.

Note: If the principal certifying authority is the Council, the nomination will be subject to the payment of a fee for the service to cover the cost of undertaking all necessary inspections and the issue of the appropriate certificates.

Under the Environment Planning and Assessment (Quality of Construction) Act, 2003, a sign must be erected in a prominent position on the work site showing the name, address and telephone number of the principal certifying authority; the name of the principal contractor (if any) for the building work and a telephone number at which that person may be contacted outside working hours. That sign must also state that unauthorised entry is prohibited. The sign must not be removed until all work has been completed.

(Reason: Statutory requirement.)

36. HOME BUILDING COMPENSATION FUND (CW)

No residential building work within the meaning of the Home Building Act 1989 may commence until:

- i) A contract of insurance in accordance with Part 6 of the Home Building Act 1989 is entered into and in force, where such a contract is required under that Act (this is a prescribed condition of consent pursuant to clause 981(b) Environmental Planning and Assessment Regulation 2000.
- ii) The PCA is satisfied that the principal contractor for the work is the holder of the appropriate licence and is covered by the appropriate insurance, in each case if required by the Home Building Act 1989 (unless the work is to be carried out by an owner-builder).
- iii) If the work is to be carried out by an owner builder, that the owner builder is the holder of any owner -builder permit required under the Home Building Act 1989.
- iv) Written notice of the following information has been provided to Council (this is a prescribed condition of consent pursuant to clause 98B of the Environmental Planning and Assessment Regulation 2000):
 - In the case of work for which a principal contractor is required to be appointed:
 - the name and licence number of the principal contractor; and
 - the name of the insurer by which the work is insured under Part 6 of the Home Building Act 1989.
 - In the case of work to be done by an owner-builder:
 - the name of the owner-builder; and
 - if the owner-builder is required to hold an owner-builder permit under the Home Building Act 1989, the number of the owner-builder permits.

Where Council is not the PCA, the PCA is responsible for notifying Council of the above matters.

Note: Where arrangements for doing residential building work change while the work is in progress so that the above information becomes out of date, the PCA (where not the Council) must provide Council with written notice of the updated information.

(Reason: Statutory requirement.)

37. NOTICE OF COMMENCEMENT (CW)

No work shall commence until the following details are submitted to Council:

- i) a Notice of Commencement (form will be attached with issue of a Construction Certificate or available from our website) within two (2) days of the date on which it is proposed to commence works associated with the Development Consent;
- ii) details of the appointment of a Principal Certifying Authority (either Council or another Principal Certifying Authority); and
- iii) details of the name, address and licence details of the Builder.

(Reason: Statutory requirement.)

CONDITIONS TO BE SATISFIED DURING DEMOLITION AND BUILDING WORKS (DBW)

38. OBSTRUCTION OF PUBLIC WAY NOT PERMITTED DURING WORKS (DW)

The public way must not be obstructed by any materials, vehicles, refuse, skips or the like, under any circumstances, without the prior approval of Council.

(Reason: To maintain public access and safety.)

39. PUBLIC INFRASTRUCTURE AND SERVICES (DW)

The applicant must comply with the requirements (including financial costs) of any relevant utility provider (e.g. Energy Australia, Sydney Water, Telstra, RMS, Council etc.) in relation to any connections, works, repairs, relocation, replacements and/or adjustments to public infrastructure or services affected by the development.

(Reason: To maintain public infrastructure and/or services.)

CONDITIONS TO BE SATISFIED PRIOR TO THE ISSUE OF AN OCCUPATION CERTIFICATE (POC)**40. CAR PARKING - SURPLUS VEHICULAR CROSSINGS (OC)**

All surplus vehicular crossings and/or kerb laybacks must be removed and reinstated with concrete kerb and gutter or to the existing edging profile as specified by Council. The nature strip is to be restored and the footpath area reinstated. All of the above are to be restored to the satisfaction of Council's Engineer and at full cost to the applicant, prior to the issue of any Occupation Certificate.

(Reason: Maintenance of public infrastructure.)

41. DRAINAGE SYSTEM - MAINTENANCE OF EXISTING SYSTEM (OC)

Where elements of the existing drainage system are to be utilised, the existing drainage system shall be overhauled and maintained clear of silt and accumulated debris. Silt and the like shall be removed, not flushed from the system.

A certificate shall be provided by a suitably qualified person (a registered plumber or a person of equivalent or greater experience or qualification) to the satisfaction of the Principal Certifying Authority, prior to the issue of any Occupation Certificate to confirm that the system is in good working order and adequate to accept additional flows having regard to any relevant standards and/or Sydney Water requirements.

(Reason: Maintenance and environment.)

42. ENGINEERING WORKS (CERTIFICATION OF)

Prior to occupation of the premises, a Work As Executed (WAE) Plan of all engineering and/or drainage works is to be submitted to the Principal Certifying Authority. The WAE Plan is to be certified by an Accredited Civil/Hydraulic Engineer demonstrating that:

- i) The stormwater drainage system; and/or
- ii) The car parking arrangement and area; and/or
- iii) Any related footpath crossing works; and/or
- iv) The proposed basement pump and well system; and/or
- v) The proposed driveway and layback; and/or
- vi) Any other civil works

have been constructed in accordance with the approved plans and any relevant Standards and Council policies/specifications.

For major works, such as subdivisions, works within the road reserve (requiring separate S138 approval) and as where specified by Council, a Part 4A Certificate will be required. It is strongly recommended that an Engineer supervise all engineering related works.

Where Council is not the Principal Certifying Authority, an electronic copy of the above documents is to be provided to Council, prior to the issue of any Occupation Certificate.

(Reason: Asset management.)

43. **LANDSCAPING - ARBORIST'S FOLLOW UP REPORT OF TREE/S TO BE RETAINED (OC)**

As part of the on-going assessment of the tree/s to be retained, the consulting arborist engaged by the applicant is to assess their health and any impacts suffered by them as a result of the proposed approved development, prior to the issue of an Occupation Certificate. Findings are to be compiled in a detailed report and submitted to the Principle Certifying Authority, which documents the following:

- i) Methods of excavation or construction used to carry out the works;
- ii) Any damage sustained by the tree/s as a result of the works;
- iii) Any subsequent remedial works required to be carried out by the consulting arborist as a result of the damage; and
- iv) Any future or on-going remedial work required to be carried out to ensure the long term retention of the tree/s.

(Reason: To ensure the survival of trees to be retained.)

44. **OCCUPATION OF BUILDING (OC)**

A person must not commence occupation or use (or change of use where an existing building) of the whole or any part of a new building (within the meaning of section 109H (4) of the Act) unless an Interim Occupation Certificate or Final Occupation Certificate has been issued in relation to the building or part.

The Principal Certifying Authority is required to be satisfied, amongst other things, that:

- i) All required inspections (including each applicable mandatory critical stage inspection) have been carried out; and
- ii) Any preconditions to the issue of the certificate required by a development consent have been met.

Note: New building includes an altered portion of, or an extension to, an existing building.

(Reason: Statutory requirement.)

45. **STORMWATER - CERTIFICATION OF THE CONSTRUCTED DRAINAGE SYSTEM (OC)**

The constructed stormwater system shall be certified by a suitably qualified person, in accordance with Council's Stormwater Management Code, prior to the issue of any Occupation Certificate.

(Reason: Adequate stormwater management.)

46. **STORMWATER - COVENANT AND RESTRICTION AS TO USER FOR STORMWATER CONTROLLED SYSTEMS (OC)**

Prior to the issue of any Occupation Certificate, the applicant shall register a Positive Covenant and a Restriction as to User under section 88E and or section 88B of the Conveyancing Act as appropriate in favour of Council, ensuring the ongoing retention, maintenance and operation of the stormwater facility (on-site detention, pump-out, charged

lines, etc).

Where any drainage line or service conduit is to traverse any property other than that which it serves, an appropriate easement will be required. In this case, the applicant shall register an easement no less than 1200mm wide over the proposed drainage line or service concurrently with any subdivision registration.

The wording on the 88E and/or the 88B Instrument is to make reference to the Council file where the Construction plans and the Work As Executed (as built), plans are held. Typical wording can be obtained from Council's Specification for the Management of Stormwater document.

(Reason: To ensure the on-site detention and/or pump system is maintained to an appropriate operational standard.)

47. **POSITIVE COVENANT (OC)**

A Positive Covenant under Section 88E of the Conveyancing Act shall be created on the title of the property as follows:

- (a) Full and free right must be provided to Strathfield Council employees or its authorised contractors to:
 - (i) Enter upon the land and remove any waste products using any vehicle or equipment as necessary;
- (b) The owner of the lot burdened shall be solely responsible for the cost of maintaining in good and sufficient repair at all times the internal roads or access ways used by Strathfield Council for the purpose of exercising its rights as set out in clause (a) above.

The wording of the Instrument shall be submitted to, and approved by Council prior to lodgement at Land & Property Information NSW. The Instrument shall be registered and a registered copy of the document shall be submitted to and approved by the consent authority.

(Reason: To ensure appropriate collection of waste.)

RESOLUTION

The application be **APPROVED** subject to the recommended conditions and the addition of Condition 4A to read as follows:

4A FRONT BOUNDARY SETBACK

The dwelling and ancillary built elements (including porch, roof, awning, posts, piers) must be setback 9 metres from the front boundary when measured perpendicular to the boundary line along Homebush Road. Amended plans are to be submitted to and approved by Council prior to the issue of a Construction Certificate.

FOR: S. Clements, K. Lindeberg, G. Andonoski

AGAINST: Nil

**** End Minutes - Report No. 1****