

# NOTES AND SPECIFICATIONS

Prior to carrying out any excavations, the contractor is to confirm locations of all services. Services pits and lids are not to be covered by any material. Trim and grade area to form a smooth even finish to required falls.

### GARDEN BED / MULCH

The topsoil to all deep soil garden bed areas shall be four (4 )parts site topsoil to one (1) part organic compost thoroughly blended together prior to placing into position. Where the site topsoil is considered not suitable, an imported topsoil blend meeting the requirements of AS4419-1998 shall be used. Garden bed subgrades are to be cultivated to a depth of 150mm. Topsoil depths to all garden bed areas to be 300mm (min). At the completion of all planting operations apply a 75mm layer of mulch over entire garden bed taking care not to smother plants. Reduce depth of mulch around base of plants to form "watering dish". Mulch used shall be Pine Bark Nuggets as supplied by ANL or similar. All proposed planting is subject to suitable topsoil depths on site. Where there is insufficient depth due to presence of bedrock or other structures, the proposed planting is to be modified to suit in accordance with

#### TURE / GARDEN EDGING

Turf used for this site shall be Sir Walter Buffalo or similar soft leaf variety. Unless specified otherwise, turf shall be laid over 150mm topsoil and finished flush with adjacent surfaces. Water turfed areas immediately after turfing operations. Topdress any excessively undulating areas to form a smooth level surface with a coarse grade washed river sand. All garden edging as denoted by 'GE' on the plan is to be constructed as per detail.

### PLANT MATERIAL

All plant material are to be healthy nursery stock, free from disease, injury, insects all weed or roots of weeds. No plant is to be installed which has not been hardened off or is otherwise inferior in quality. All plants are to be thoroughly soaked 1hour prior to planting.

## EXISTING TREES TO BE RETAINED

The existing trees indicated for retention shall be protected for the duration of the construction period. Install a 1.8m high temporary protective fence (TPF) to the locations as indicated on the plan. Do not store or otherwise place bulk or harmful materials under or near a tree which is to be retained. Do not attach stays, guys and the like to a tree which is to be retained. Where it is absolutely necessary to prune tree roots / limbs contractor to ensure all Council approvals have been obtained. All tree work is to be carried out by a qualified and insured arborist. Where an arborist report has been prepared for the existing tree on site; The landscape plan shall be read in conjunction with this report. All trees identified for retention shall be protected and managed in accordance recommendations of this report. These recommendations will take precedence over any measures outline in the landscape plan.

# MAINTENANCE / ON GOING CARE

Maintain all landscape areas to ensure plant health and occupant safety for period of 12 months beginning from date of practical completion to the satisfaction of Council. Maintenance will include but is not limited to the following activities: Mowing and edging lawn areas, fertilizing all plant material, pruning, watering, replacing failed planting, treating for pests and diseases, topping up of mulch areas and weeding garden beds as required. On completion of the initial 12 month period, all maintenance responsibilities shall be handed over to building management / property owner for on-going care. Note: All trees will require ongoing annual observation and maintenance by qualified arborist to ensure occupant safety, tree health and to avoid damage to surrounding structures and property.

# DISCREPANCIES


Should there be any discrepancies on the drawings with existing site conditions; contractor is to notify the landscape architect prior to proceeding with the works

# **PLANT SCHEDULE**


Code	Name	Pot Size	Mt Size	Qty
DLR	Dianella Little Rev	200mm	0.3m	30No.
DSF	Dichondra 'Silver Falls'	120mm	Ground Cover	30No.
LM	Liriope muscari	120mm	0.5m	36No.
MTB	Magnolia 'Teddy Bear'	100Litre	6.0m	1No.
NGS	Nandina 'Gulf Stream	300mm	0.6m	8No.
PT	Phormium tenax	300mm	2.0m	6No.
PX	Philodendron Xandadu	200mm	0.5m	53No
RSM	Raphiolepis 'Snow Maiden	300mm	Trim 1.2m	27No.
TJ	Trachelospermum jasminoides	200mm	Climber / G Cover	65No.
TL	Tristaniopsis laurina	100Litre	6.0m	3No.
VO	Viburnum odoratissimum	300mm	Trim to 2.0m	31No.

33 Newton St Strathfield 24 September 2021


STRATHFIELD COUNCIL **RECEIVED** S8.2A- DA2021.74 18 October 2021




















Synthetic Turf

Steel Garden Edge (to detail)

GE Garden Edge ( to detail)
CL Clothes Lines (to client requirements)
CB/TP Colorbond / Timber Paling (1.8 high)

Rainwater Tank (to Engineers Specifications)

Pavers

Stenciled Concrete (Charcoal/gunmetal)

Temporary Protection Fence (1.8m chainmesh) Gravel Surface / Path ( Nepean River Pebble)

Timber Deck

Concrete Path Bench Seat

ВТ Table / Seating

> Rev B S8.2 Review 22 Sept 2021 Rev A RFI 28 June 2021



Landscape Architects PO Box 550 Hurstville NSW 1481 michael@msla.com.au 02 9557 9833 | 0417 280 249

Details Notes Schedule 2of 2

**Proposed Residence** 33 Newton St Strathfield

1:200@A3 Dwg: L02/2- K25409 3 March 2021

ABN 15 086 982 158

